

THE SOIL

AN INTRODUCTION TO THE SCIENTIFIC
STUDY OF THE GROWTH OF CROPS

BY SIR A. D. HALL, K.C.B., F.R.S.

LATE DIRECTOR OF THE ROTHAMSTED STATION (LAWES AGRICUL-
TURAL TRUST); AND FOREIGN MEMBER OF THE ROYAL ACADEMY
OF AGRICULTURE OF SWEDEN

THIRD EDITION, REVISED AND ENLARGED

LONDON
JOHN MURRAY, ALBEMARLE STREET, W.

1921

5314

N21

DEDICATED TO
THE WORSHIPFUL COMPANY OF GOLDSMITHS
THE FIRST PUBLIC BODY IN THIS COUNTRY TO
CREATE AN ENDOWMENT FOR THE
INVESTIGATION OF THE SOIL

12549



INTRODUCTION

THE study of the soil, which is fundamental in any application of science to that part of agriculture which deals with the growth of crops, has received greatly increased attention during the past few years. The crude chemical point of view, which in the main regarded the soil as a nutritive medium for the plant, has been altogether extended, by a consideration of the soil as the seat of a number of physical processes affecting the supply of heat and of air and water to the plant, and again as a complex laboratory, peopled by many types of lower organisms, whose function is in some cases indispensable, in others noxious, to the higher plants with which the farmer is concerned. These three kinds of reaction—chemical, physical, and biological—interact upon one another and upon the crop in many ways; they are affected by, and serve to explain, the various tillage operations which have been learnt by the accumulated experience of the farming community, and the hope for future progress lies in the further adaptation for practical ends of these processes at work in the soil. But it must not be supposed that science is yet in a position to reform the procedure of farming, or even to effect an immediate increase in the productivity of the land: agriculture is the oldest and most widespread art the world has known, the applica-

tion of scientific method to it is very much an affair of the day before yesterday. Nor can we see our way to any radical acceleration of the turnover of agricultural operations that shall be economical; the seasons and the vital processes of the living organism are stubborn facts, unshapable as yet by man with all his novel powers. But even if the best farming practice is still a step beyond its complete explanation by science, yet the most practical man will find his perception stimulated and his power of dealing with an emergency quickened by an appreciation of the reasons underlying the tradition in which he has been trained; and such an introduction to the knowledge of the soil it is the aim of this little book to supply. The book is primarily intended for the students of our agricultural colleges and schools, and for the farmer who wishes to know something about the materials he is handling day by day. While a certain knowledge of chemistry is assumed, it is hoped that the subject is so treated as to be intelligible to the non-technical reader who is without this preliminary grounding. Though the book is in no sense an exhaustive treatise, it has been my desire to give the reader an outline of all the recent investigations which have opened up so many soil problems and thrown new light on difficulties that are experienced in practice. The scope of the book precludes the giving of references and authorities for all the statements which are made; but, for the sake of the more advanced student, a bibliography has been appended, which will take him to the original sources and give him the means of learning both sides of the more controversial questions.

The same reason—want of space—has prevented me from giving an adequate justification of some of the points of view indicated. Any worker in so novel and

unsurveyed a field as the study of the soil still presents, must arrive at certain personal conclusions, and I have tried to steer a middle course between an over insistence on these points on the one hand, and the colourlessness that would come from their entire exclusion on the other. No great part of a text-book can pretend to be original, but in the sections dealing with the chemical analysis and the physics of the soil, I have incorporated a good many unpublished measurements and observations; for the mass of the results on which the book is based, I am chiefly indebted to the work of Lawes and Gilbert, as set out in the *Rothamsted Memoirs*, and to the writings of Warington in this country, of King, Hilgard, and Whitney in America, of Wollny in Munich.

I have to thank Professor J. Percival, of the South-Eastern Agricultural College, for notes respecting the association of plants with specific soils, and many suggestions on biological questions; Major Hanbury Brown, C.M.G., head of the Egyptian Irrigation Department, for information concerning "salted" lands in Egypt; Mr F. J. Plymen, who has been associated with me in carrying out a soil survey of the counties of Kent and Surrey, and has executed many of the observations recorded here; Mr W. H. Aston, one of my pupils, to whom I owe the observations on p. 153; and finally, Dr J. A. Voelcker, to whom I am greatly indebted for reading the proof-sheets, and making many valuable suggestions thereon.

A. D. HALL.

PREFACE TO THE SECOND EDITION

A CONSIDERABLE number of additions and alterations have been incorporated in the present edition. These include a revision of the method recommended for the mechanical analysis of soils, the method now given being that adopted by the members of the Agricultural Education Association in this country. Owing to researches which have appeared since the publication of the first edition, I have greatly modified the views I then expressed on the nature of clay, and on the part played by zeolitic silicates in the retention of ammonium and other salts by the soil. During the last six years, however, the greatest additions to our knowledge of the soil are those dealing with bacteria; in consequence, the chapter on the living organisms of the soil has been largely rewritten and added to. A number of minor corrections have been made in the text, some of which represent the removal of errors, and others modifications due to more recent research. For the mistakes which must still remain, and which will become evident in the course of time, I must ask my readers' pardon beforehand; in dealing with so complex a subject as the soil we are still far from final conclusions, many of our most trusted conclusions are only rough approximations to the truth, and by the progress of research they may at any time require remodelling until they are hardly recognisable.

A. D. HALL.

THE ROTHAMSTED EXPERIMENTAL STATION,
May 1908.

PREFACE TO THE THIRD EDITION

AFTER an interval of eleven years, even though research in Europe has been suspended for five of them, considerable revision becomes necessary in a book dealing with a subject growing so rapidly as the science of the soil. During the period in question the chief addition to our knowledge has been the extended light upon the organisms of the soil and their function that we have gained through the investigations of Russell and Hutchinson at Rothamsted. The current views upon the structure of clay and many of the reactions of the soil in which the clay takes part have been considerably modified through the development of the conception of colloids which has taken place of late years. But in many other instances I have found it necessary either to record some additional knowledge or to modify the point of view.

A. D. HALL.

LONDON, *October* 1919.



CONTENTS

INTRODUCTORY

	PAGE
In the Scientific Study of Soils, Chemical, Physical, and Biological Considerations are involved	I

CHAPTER I

THE ORIGIN OF SOILS

Sedentary Soils, and Soils of Transport—Weathering—The Composition of Rock-forming Minerals and their Weathered Products—Distinction between Soil and Subsoil—General Classification of Soils	6
---	---

CHAPTER II

THE MECHANICAL ANALYSIS OF SOILS

Nature of Soil Constituents: Sand, Clay, Chalk, and Humus—Methods of Sampling Soils—Methods for the Mechanical Analysis of a Soil—Interpretation of Results	36
---	----

CHAPTER III

THE TEXTURE OF THE SOIL

Meaning of Texture and Conditions by which it is affected—Pore Space and Density of Soils—Capacity of the Soil for Water—Surface Tension and Capillarity—Percolation and Drainage—Hygroscopic Moisture	66
--	----

CHAPTER IV

TILLAGE AND THE MOVEMENTS OF SOIL WATER

	PAGE
Water required for the Growth of Crops—The Effect of Drainage—Effects of Autumn and Spring Cultivation, Hoeing and Mulching, Rolling, upon the Water Content of the Soil—The Drying Effect of Crops—Bare Fallows—Dry Farming—Effect of Dung on the Retention of Water by the Soil	100

CHAPTER V

THE TEMPERATURE OF THE SOIL

Causes affecting the Temperature of the Soil—Variation of Temperature with Depth, Season, etc.—Temperatures required for Growth—Radiation—Effect of Colour—Specific Heat of Soils—Heat required for Evaporation—Effect of Situation and Exposure—Early and Late Soils	135
---	-----

CHAPTER VI

THE CHEMICAL ANALYSIS OF SOILS

* Necessary Conventions as to the Material to be Analysed—Methods Adopted—Interpretation of Results—Distinction between Dormant and Available Plant Food—Analysis of the Soil by the Plant—Determination of "Available" Phosphoric Acid and Potash by the Use of Weak Acid Solvents	159
---	-----

CHAPTER VII

THE LIVING ORGANISMS OF THE SOIL

Decay and Humification of Organic Matter in the Soil—Alinit—The Fixation of Free Nitrogen by Bacteria living in Symbiosis with Leguminous Plants—Soil Inoculation with Nodule Organisms—Fixation of Nitrogen by Bacteria living free in the Soil—Nitrification—Denitrification—Protozoa—Iron Bacteria—Fungi of Importance in the Soil: Mycorrhiza, and the Slime Fungus of "Finger-and-Toe"	192
---	-----

CONTENTS

XIII

CHAPTER VIII

THE POWER OF THE SOIL TO ABSORB SALTS

	PAGE
Retention of Manures by the Soil—The Absorption of Ammonia and its Salts; of Potash; of Phosphoric Acid—Chemical and Physical Agencies at Work—The Non-Retention of Nitrates—The Composition of Drainage Waters—Loss of Nitrates by the Land—Time of Application of Manures.	247

CHAPTER IX

CAUSES OF FERTILITY AND STERILITY OF SOILS

Meaning of Fertility and Condition—"Fairy Rings"—Causes of Sterility: Drought, Waterlogging, Presence of Injurious Salts—Alkali Soils and Irrigation Water—Effect of Fertilisers upon the Texture of the Soil—The Amelioration of Soils by Warping, Liming, Marling, Claying, Paring, and Burning—The Reclamation of Peat and Heath Land	271
--	-----

CHAPTER X


SOIL TYPES

Classification of Soils according to their Physical or Chemical Nature—Geological Origin the Basis of Classification—Vegetation characteristic of Various Soil Types: Physical Structure, Chemical Composition, Natural Flora and Weeds characteristic of Sands, Loams, Calcareous Soils, Clays, Peat, Marsh, and Salt Soils—Soil Surveys, their Execution and Application	315
--	-----

APPENDICES

APPENDIX I.—Analyses of some Typical Soils	342
„ II.—Bibliography	344
INDEX	347





LIST OF ILLUSTRATIONS

FIGURES	PAGE
Photograph showing transition from Rock into Subsoil and Soil by Weathering (Hythe Beds, Great Chart, Kent)	<i>Frontispiece</i>
1. Photograph showing Glacial Drift overlying Magnesian Limestone	16
2. Photograph of Soil-sampling Tools	54
3. Diagram illustrating Pore Space	67
4. Diagram illustrating Capillary Rise and Depression of Liquids	78
5. Photograph illustrating Liquid Film round Soil Particles	78
6. Diagram illustrating Liquid Film round Soil Particles	80
7. Water Content, of Columns of wetted but thoroughly drained Sand and Soil	83
8. Diagram showing Rainfall and Percolation at Rothamsted, 1870-1905	86
9. Soil Temperatures at 9 A.M., Monthly Means, 1896	137
10. Soil Temperatures at 9 A.M., Daily Readings	139
11. Effect of Nature of Surface upon Soil Temperatures	145
12. Temperatures of Drained and Undrained Bog	150
13. Distribution of the Sun's Rays on Southerly and Northerly Slopes	152
14. Temperatures (Max. and Min.) at Various Altitudes	155
15. Nitrates in Cultivated and Uncultivated Soil	224
16. Losses of Nitrogen in Drainage from Rothamsted Wheat Plots	264
17. Nature and Distribution of Alkali Salts	286

r

•

1

2

3

4

5

6

7

8



THE SOIL

INTRODUCTORY

In the Scientific Study of Soils, Chemical, Physical, and
Biological Considerations are involved.

THE whole business of agriculture is founded upon the soil; for the soil the farmer pays rent, and upon his skill in making use of its inherent capacities depends the return he gets for his crops. Taking rent as a rough measure of the productive value of land, it is clear that enormous differences must exist in the nature of the soil, for in the same district some land may be rented at £2, and other land at as little as 5s. per acre. Of course rent is not wholly determined by the nature of the soil, but depends also on the proximity of a market and the adaptability of the land to special purposes; a light sandy or gravelly soil, almost worthless for general agricultural purposes, may be valuable in the neighbourhood of a large town, because its earliness and responsiveness to manure make it specially suitable for market gardening.

In some cases the difference between soils is seen in the quality of the crop produced rather than in the productiveness; for example, the "red lands" of Dunbar are famous for the high quality of the potatoes grown upon them: such potatoes will sell at 80s. to 90s.

per ton, when potatoes grown upon the Lincoln warp soils are at 60s., and those from the black soils of the fen country are only fetching 45s. to 50s. This extra price for the red land potatoes is due to the fact that they can be cooked a second time, after cooling, without changing colour, whereas the ordinary potato is apt to blacken a little when once cooked and allowed to grow cold.

The scientific study of soils is concerned with the differences indicated above; its endeavour is to obtain such a knowledge of the constitution of the soil and the part it plays in the nutrition of the plant, as will make clear the cause of the inferiority of any given piece of land, and ultimately enable the farmer to correct it. The problems involved are far more complex than they appear; at first sight nothing would seem easier than to make a chemical analysis of the soil and find out in what respects it differs from another soil of known value; then the deficiencies or the excesses, as compared with the good soil, could be corrected by suitable manuring. The matter is not, however, quite so simple, for if on the one hand the soil can be considered as a great reservoir of plant food which can be recovered in crops, on the other hand it is equally correct to regard the soil as a manufactory, a medium for transforming raw material in the shape of manure into the finished article—the crop. In new countries where virgin soil is being exploited, and in districts where the systems of agriculture are primitive, the former point of view is the correct one; nothing is given to the soil beyond that amount of labour which will enable some of its inherent value to be realised in a crop. Little by little the capital, which may be practically boundless, as in the great wheat lands of Manitoba, or initially little enough, as on a Connemara heath, is being drawn

upon and not replaced. But in a Kentish hop-garden or other land where an intensive system of cultivation is practised, the crop does not remove as much as it receives; often the land is intrinsically poor, and owes its value to the manner in which it will elaborate the raw material supplied as manure. And not only are these very special soils gaining, rather than losing fertility with each crop, but, from a general point of view, all countries that are being highly farmed, like parts of Great Britain, are steadily increasing in fertility at the expense of other countries which are growing crops on virgin soil; in the linseed, the maize, the cotton seed, that are fed to our stock, there travels to our soil some of the wealth of the lands upon which these crops were grown. Hence the study of the inherent resources of the soil is perhaps less important than an examination of the manner in which the soil deals with such materials supplied under cultivation.

The complete knowledge of the soil and the part it plays in the nutrition of the plant requires investigation along three lines, which may be roughly classed as—chemical, physical or mechanical, and biological; naturally these points of view are not independent of one another, but are only so separated for convenience of study.

In the first place, we know that the plant derives certain substances necessary to its development from the soil: nitrogen and all the ash constituents reach the plant in this manner. We have, therefore, to investigate the proportions in which these constituents are present in the soil, the state of combination in which they may respectively exist, and the variations in these factors normally exhibited by typical soils, all of which questions may be described under the head of chemical analysis. Further investigations of a

chemical nature deal with the power of various soils to retain manure, the causes of sterility or fertility, and the measures that can be adopted for the amelioration of soils.

The soil is, however, not merely a storehouse of food for the plant, since water is equally indispensable to its existence and is immediately derived from the soil; hence it is of prime importance to study the causes which underlie the movement of water in the land, and its supply to the growing crop. In the relation between soil and water the cultivation to which the land is subjected plays a prime part, hence it will be necessary to trace the effect of each of the main operations of tillage upon the structure of the soil. Again, the texture of the soil and the proportions of water and air it retains, affect its temperature and that responsiveness to change of season which we roughly indicate by the terms "early" and "late" soils. The general consideration of these questions may be termed soil physics.

Finally, the soil is not a dead mass, receiving on the one hand manure, which it yields again to the crop by purely mechanical or chemical processes; it is rather a busy and complex laboratory where a multitude of minute organisms are always at work. By the action of some of these organisms, vegetable residues and manures are reduced, we might almost say digested, to a condition in which they will serve as food for plants; others are capable of bringing into combination, or "fixing," the free nitrogen gas of the atmosphere, and therefore add directly to the capital of the soil; others again are noxious or destructive to the food stores in the soil.

The work of these organisms is much affected by cultivation; in fact, it would not be too much to say

that most of the operations upon the farm have received a new light from the knowledge that has been acquired in the last few years of the living processes taking place in the soil. In this direction also new developments of agriculture seem to be possible, and though the progress is only small as yet, we see indications that the productive capacity of the land may be permanently increased by the introduction of certain organisms capable of assisting the work of the higher plants or by the destruction of others which limit the development of the useful organisms.

On the biological side we have also to study the association of certain plants with particular soils; an examination of the natural flora of any district will show that some species are almost confined to sandy soils, others to soils containing chalk, rarely wandering on to different types of soil; again, particular weeds are characteristic of clay land, others of sand; and some even of our cultivated crops show a marked intolerance for particular soils.

The full story of the soil cannot yet be told; small wonder that in the course of the many centuries man has been cultivating the face of the earth, he has found out much which science can barely explain, still less improve upon. Nor are the problems simple—the food, the water, the temperature, the living organisms in the soil are all variables, affected by cultivation and climate, themselves also variable; they all act and react upon one another and upon the crops; hence we can easily understand that the smallest farm may present problems beyond the furthest stretch of our knowledge.

as we descend ; if it be gravel, the stones continue of the same size ; if brick earth, neither stones nor hard, stratified clay make their appearance. Should the exposed section be deep enough, we find at last the subsoil suddenly giving place to entirely different material—solid chalk, or massive clay, or sandstone, as the case may be—perhaps incapable, when disintegrated, of furnishing the stuff of which the upper stratum of gravel or brick earth is composed. In this upper stratum we see the clearest evidence of the action of water ; the brick earth is free from stones and is of even texture, the gravel contains hardly any fine material, and its constituent stones are worn and partly rounded ; only running water can thus sift the heterogeneous results of the weathering of rocks, and grade them into different positions. From what can be seen of the present work of the river, it is clear that the brick earth was deposited where the water was moving very slowly, in quiet bays and in cut-offs, which only from time to time get filled up with muddy flood water ; the gravel must have been laid down in the strongest wash of the currents.

Soils and subsoils of this type, which bear no particular relation to the underlying rocks, but have travelled from a distance by means of running water or moving ice or wind, are known as *soils of transport*, or, to use the terminology of the Geological Survey, as *drift* soils. The photograph, Fig. 1, shows the section of a deposit of glacial drift upon magnesian limestone, in which the abrupt change from the stratified rock to the travelled material giving rise to the soil is very marked.

Weathering.

The study of geology teaches us that nearly all the rocks termed stratified or sedimentary, which cover the greater part of the surface of the British Islands, have been formed from the waste of previous rocks by weathering, and by the subsequent redeposit and consolidation of the weathered material. A grain of sand, for example, is practically indestructible; it may have become cemented to the other grains on the sea beach where it was lying, and give rise to the rock we term sandstone; the rock thus formed may have been elevated into dry land, broken up into loose grains, and washed down to the sea to form a new beach, over and over again in the world's history; so long a time has elapsed since water first began to work on the earliest rocks. For this reason, if we want to trace out the origin of a soil in detail, we must in most cases go beyond the sedimentary rock from which it immediately derives, back to the so-called primitive or crystalline rocks, which represent in a sense the original materials of the earth's crust.

Here we shall find certain fundamental minerals, which in a weathered state, altered both mechanically and chemically, go to form both the sedimentary rocks and the soil which is our immediate study. Though the number of distinct minerals is immense, practically the mass of the earth's crust is made up of a few only; silica, various complex silicates of alumina, iron, lime, magnesia, potash, and soda, together with carbonate of lime, which is generally of organic origin, are all that need be considered in relation to soils.

The various agencies which reduce rocks to soil, grouped under the general term of weathering, may be distinguished as mechanical—including the work of alterations of temperature, frost, wind, rain, and glacial ice—



effectively than by any artificial means. The fragments that have been broken off the main rock will be continually reduced in size by successive frosts, until they reach the ultimate fragments which are no longer penetrated by water; even in a soil the disintegration is still proceeding.

The weathering agencies just described would gradually cover any exposed rock with a layer of débris, which would protect the lower layers from further action were it not that the rain is always washing the finer particles into the valleys and so leaving the rock open to fresh attack. Even on grass land the fine mould brought to the surface by worms, moles, ants, etc., is constantly travelling downhill by the agency of rain. On arable land containing stones it is a common expression to say that the stones "grow": however thoroughly the surface may be picked clean of stones, in a year or two they will seem as numerous as ever; the fine soil gets washed away to lower levels, leaving the stones standing upon the surface. Even the stones themselves gradually creep downhill, the rain undermines them till they fall over, they must fall a little lower down the slope, until they eventually reach the valley and are subject to further transport by running water. At the bottom of many of the smaller dry valleys on the chalk rests an enormous accumulation of flints of all sizes; in one case in a small upland valley the deposit was 6 or 7 feet thick, and the unworn flints were so close as to be practically in contact, only the interstices being occupied by soil; yet the surface carried good crops.

The material which thus creeps down the sides of the valleys is further sorted out by the streams and rivers and deposited as beds of gravel, sand, or clay, the "alluvium" which underlies the level river meadows. The coarser the material the more readily will it

settle, the finer particles are only deposited when the velocity of the stream has been almost entirely checked. The gravel and sand are deposited in and about the stream course itself, the finer material falls on the meadows in flood time, so that their level is gradually raised from year to year. Wherever the meadows get water-logged the surface vegetation will begin to accumulate as peat; the stream also wanders about from side to side of the valley, hence borings through any extensive deposit of alluvium will disclose alternating beds of gravel, sand, brick earth, and peat, of variable extent and thickness. The great alluvial flats or marshes at the mouths of many of our rivers are formed in this manner; the deposit takes place in the sea or in the estuary, until the tides and currents work the material up to high-water mark, after which only fresh-water beds are laid down.

Although most of the materials of which rocks are composed are in the ordinary sense insoluble in water, few of them, except the pure sand grains, can resist the attack of water charged with carbonic acid. The rain water when it reaches the ground has little carbonic acid in solution, but the gases in the soil contain a considerable quantity derived from the decay of vegetable matter in the surface layer, and the water in contact with these gases will dissolve a proportionate amount. The proportion of carbonic acid in the soil gases varies very much both with the permeability of the soil and the proportion of humus, but at a depth of 1.5 metres Wollny found it vary from 3.84 per cent. to 14.6 per cent. at various periods of the year. At greater depths the amount is still higher, so that the percolating water becomes a weak solution of carbonic acid, and attains a considerable solvent power. Not only are the alkaline silicates attacked by the weak acid thus formed, but as

lime, magnesia, and iron protoxide also form soluble bicarbonates, all minerals containing these bases are liable to attack. Probably some of the organic acids produced by the decay of vegetable matter in the surface soil aid in the solvent power of soil water; yet, undoubtedly, water containing carbonic acid is the great natural solvent, and some of the more striking cases of its action in breaking down rocks will be discussed later under the heads of felspar, augite, and calcium carbonate.

The attack of frost and water upon rocks is much assisted by the roots of plants and trees; if we examine a fresh section of the soil over a quarry or brick pit, the roots of ordinary field plants can be traced downwards for 4 feet or more, while the roots of a tree may be seen working far into tiny fissures of the almost unaltered rock. The roots follow the water in the fissures: at first they can enter very minute cracks; as they grow, the pressure they exert widens the cracks; finally, the roots decay and leave a channel down which water can percolate freely. The fine roots themselves cause a certain solvent action; after plants had been grown in a pot filled with powdered granite rock, which had been freed from all fine particles by washing, an appreciable quantity of mud and clay was found to have been formed.

The opening up of the subsoil to weathering by the action of roots is also carried out by worms, which have been observed making their burrows to the depth of 5 feet, thus introducing both air and water into the lower strata. But the great work of worms in regard to soil lies rather in the production of the fine surface layer of mould rich in vegetable matter: Darwin calculated that on an ordinary chalky pasture the whole of the fine surface soil to a depth of 10 inches was passed through worms and cast up on the surface in the course of fifty years. During their passage through the gizzard of the

worms the stony particles will receive a certain amount of rubbing and be reduced in size, so that some of the fine particles in the soil owe their origin to worms. The deposit of the fine soil on the surface in the shape of worm casts, which are afterwards spread by the action of rain and wind, explains why chalk, ashes, or even stones placed on pasture land gradually sink below the surface. Darwin found in one case that a layer of burnt marl spread on the surface had sunk 3 inches in fifteen years, in another case a layer of chalk was buried 7 inches after an interval of twenty-nine years; in neither case, however, can we estimate the part played by the accretion of dust in forming this deposit. When we consider for how long a period worms must have been working in our cultivated soils, it is clear that the whole must have been through them over and over again, and that much of the fineness of the surface soil must be due to their action, both in actually grinding the fragments and in constantly bringing the finest portions back to the top.

In addition to the alluvial deposits proper, which are still in process of formation, beds of gravel, sand, and brick earth occur in many river valleys, as terraces on the flanks of the hills, often much cut and denuded by the modern river. These high level formations probably represent alluvial deposits of a former epoch where the general slope of the land was greater and the rivers, fed by a higher rainfall in the hills, ran in greater volume. That the material of which these deposits consist has been sorted by running water is evident from the uniformity of size it possesses in each bed: while the coarseness of the gravel, and the fact that in some cases the stones are not made from the immediately underlying rock, all point to a great lapse of time and a river of higher transporting power than the present one. The wide deposits of brick earth in the neighbourhood

of London and in East Kent were probably laid either by floods on the river meadows or in quiet and lagoons of an estuary.

Over a great part of Britain north of the Thames especially in the midlands and the eastern counties the surface of the land is covered with beds of gravel and sand which owe their origin to glacial ice. Scotland, the north of England, and Wales, these are full of ice-scratched stones, and clearly represent material that has been ground down by a moving glacier: but the origin of the glacial drift of the eastern counties is more obscure, for water seems to have played some part in its formation. These glacial drifts are often described as "boulder clays," but they are necessarily very heavy or clayey in character from an agricultural point of view. Indeed in Norfolk, as in a great part of northern Europe, they may be of the lightest sandy type, and again in Cheshire, Staffordshire, where over large areas they are derived from the Mersey Red Sandstone they do not differ greatly from the light sedimentary soils originating from the same formation. When the glacial drift is derived from primitive or crystalline rocks the soils are marked by the predominance of angular fragments, "rock dust," which have undergone but little decomposition compared with the similar fragments present in soils originating from sedimentary rocks. Such soils, found in North Wales and Scotland, in which the quartz particles are unrounded and the felspar particles are but little kaolinised, differ from the more normal soils both in their chemical behaviour and in their response to cultivation operations.




FIG. 1.—Photograph showing Glacial Drift overlying Magnesian Limestone.

●

■

■

●

||

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

■

Rock-forming Minerals.

In the solid crust of the earth D'Orbigny has estimated that the chief minerals are present in the following proportions—feldspars, 48 per cent.; quartz, 35 per cent.; micas, 8 per cent.; talc, 5 per cent.; carbonates of lime and magnesia, 1 per cent.; hornblende, augite, etc., 1 per cent.; other minerals and weathered products, 2 per cent.

The following table shows the composition of these chief minerals, with a few others that play some part in the formation of soil:—

	Silica.	Potash.	Soda.	Magnesia.	Lime.	Alumina.	Ferrous Oxide.	Ferrie Oxide.	Water.
Quartz	100
Felspar {	Orthoclase 64.2	17	18.4
	Albite 68.6	...	11.8	19.6
	Anorthite 43.1	20	36.9
Mica {	45	6	0	26	1
	to	to	to	to	to
	50	10	1.5	36	4.7
{	Hornblende 39	10	10	3	3
	Augite to	27	to	to	to
Olivine	49	15	15	15	20
Talc	41	49.2	9.8
	63.5	31.7	4.8

Quartz, the crystalline form of silica, is found massive and in veins in the primitive rocks, and in fragments of all sizes in the granites, gneisses, and similar rocks. From the waste of these crystalline rocks are derived the sandstones of all geological ages, and directly or indirectly the sands now existing. In a sandstone rock the grains of quartz are bound together by a cement, which may be oxide or carbonate of iron, as in the Lower Greensand of Surrey

and Beds., and in some of the Wealden sandstones, or carbonate of lime, as in the Kentish Rag, or even silica itself, as in the hard blocks of tertiary sandstone, which are left as "grey wethers" on the surface of the chalk. In some of the older sandstones the rock is practically homogeneous; heat, pressure, and solution having thoroughly felted the grains together. Many sandstones weather rapidly, through the solution of the cement binding the grains together; the resulting sand has the same texture as it possessed before it was cemented into a rock.

The grains of sand that are first weathered from a crystalline rock possess an angular shape, but are soon rubbed down in running water into rounded grains with a surface like fine ground glass. Hence the degree of angularity which the sand grains show gives some indication of the amount of wear and tear they have suffered since their origin as sand. Below a certain size, however, quartz grains seem no longer capable of rubbing against one another, but remain angular even after long travel in running water. Daubrée has shown that angular fragments of sand of less than 0.1 mm. in diameter will travel in water without becoming rounded, hence any rounding of smaller grains of sand must have been due to solution.

Silica in the crystalline state is very slightly soluble in water, a certain amount of solution taking place even at ordinary temperatures: most natural waters show a little silica in solution, though this more probably arises from the decomposition of natural silicates by water containing carbonic acid, rather than from the direct solution of quartz.

Amorphous silica in the form of "flint" plays a conspicuous part in the constitution of many soils in the south and east of England; owing to their

durability and the former greater extension of the chalk, flints are found in many districts remote from the chalk, even in the drift beds of the Channel Islands. When first won from the chalk, flints possess a clear black translucent structure, and are easily fractured and crushed; when weathered, either in flint gravels or on the surface of the soil, they become yellow or brown in colour, more opaque, and much harder, so that weathered flints are always preferred for road-making. The surface also becomes covered with a white incrustation, extending to a depth of $\frac{1}{16}$ of an inch or more; this is, however, only incipient weathering, probably due to the freezing of the small amount of water that soaks in at the surface.

The Felspars constitute the most important group of minerals found in the crystalline rocks: they are double silicates of alumina and some other base, potash, soda, or lime, of the general formula $R_2O, Al_2O_3, 6SiO_2$, where R_2O may be either K_2O , Na_2O , or CaO . In granites and gneisses the common felspar is orthoclase or potash felspar; in the volcanic rocks plagioclase felspars predominate, in which the base is lime, generally with some admixture of soda and potash.

The felspars are all distinguished by the ease with which they are attacked by water containing carbonic acid, those containing lime more readily so than the potash felspar. The lime or the alkali is removed in solution, some of the silica is also removed; the alumina remains as a hydrated silicate, $Al_2O_3, 2SiO_2, 2H_2O$, called kaolinite. Owing to this disintegration of felspar, the crystalline rocks in which felspar is present weather rapidly, the other materials, quartz, mica, hornblende, become loosened from the matrix, and the whole rock becomes rotten. The granite of Cornwall and Devon is generally covered to a considerable

depth, as much as 100 feet in some cases, with a layer of kaolinite, in which the unchanged quartz and mica are embedded; the kaolinite, freed by washing from the quartz, mica, etc., forms the "china clay" or kaolin of commerce. In the same way the basalts and other kindred rocks give rise to a red clay, consisting of kaolinite and the red iron oxides resulting from the oxidation of the magnetite and the hornblende, augite, etc., which contain ferrous silicates. From the decomposition of the feldspars, augite, hornblende, etc., all our clays arise; as these minerals also generally contain potash, they are the source of the potash required by crops, which is always more abundant as clay predominates in the soil.

Daubrée caused 3 kilos of fragments of feldspar to revolve in an iron cylinder with 3 litres of water, so that they practically performed a journey of 460 kilometres, with the result that 2.72 kilos of mud were formed, of which 36 grams were clay, and in the water there were 12.6 grams of potash in solution as silicate.

Senft examined the action of water charged with carbonic acid upon two granites, one (A) composed of orthoclase, quartz, and potash mica, the other of (B) plagioclase, quartz, and magnesia mica, and obtained in solution—

	A.	B.
Potash as Bicarbonate . .	15 to 25 per cent.	5 to 8 per cent.
Soda as Bicarbonate . .	2 " 6 "	8 " 10 "
Lime as Bicarbonate . .	1 " 2 "	4 " 5 "
Magnesia as Bicarbonate . .	a trace	10 " 15 "
Silica . .	a little	a little
Iron as Bicarbonate . .	a trace	a trace

The undissolved residue of A was a white, of B a

yellow, clay containing fragments of quartz and flakes of mica.

The following analyses show the change that takes place in passing from orthoclase felspar to kaolin; in the third column the analysis of kaolin is recalculated to show what arises from 100 parts of felspar, on the assumption that none of the alumina is removed by solution:—

	Orthoclase Felspar.	Kaolin.	Kaolin from 100 Felspar.
Silica . .	64.2	46.8	23.1
Alumina . .	18.4	37.3	18.4
Potash . .	17	2.5	1.1
Water	13	6.4
	99.6	99.6	49

Mica is essentially a double silicate of alumina and potash, with some oxide of iron: the potash being replaced by magnesia in black mica or biotite. Mica splits up into minute flakes as the rock weathers, but these flakes are fairly resistant to chemical change, and may be detected in most sands and sandstones. Ultimately, however, they pass into hydrated silicates of alumina, and are rarely to be detected in the soils resting upon sedimentary rocks.

Hornblende and Augite, though differing in crystalline shape, are chemically identical, and consist of silicates of varying proportions of lime, magnesia, alumina, ferrous and ferric oxides; manganese and the alkali metals are generally also present. They constitute, with plagioclase felspar and magnetic oxide of iron, the chief part of the rocks that are sometimes roughly termed "greenstone"—basalts, diorites, etc., of both volcanic and plutonic origin. They decompose under the action of carbonic

acid charged water, especially those containing much lime, while those with much magnesia are the most resistant; the products of the action are kaolinite, oxides of iron, and carbonates of lime and magnesia. The following analysis (Ebelmar) show the chemical change in the weathered layers of a basalt from Bohemia and a greenstone or dolerite from Cornwall:—

	BASALT.		GREENSTONE.	
	Unaltered.	Weathered.	Unaltered.	Weathered.
Silica . . .	44.4	42.5	51.4	44.5
Potash . . .	4.8	2.0	1.6	1.2
Soda . . .	2.7		3.9	1.7
Lime . . .	11.3		5.7	1.4
Magnesia . . .	9.1	3.3	2.8	2.7
Alumina . . .	12.2	17.9	15.8	22.1
Iron Protoxide . . .	12.1	...	12.9	...
Iron Peroxide . . .	3.5	11.5	3.0	17.6
Titanium Oxide . . .	trace	1.2	0.7	1.0
Water . . .	4.4	20.4	1.7	8.6

The loss amounts to about 44 per cent. in the case of the basalt, and 34 per cent. in that of the greenstone.

Another example may be given of the analysis (Hanamann) of a basalt from Bohemia, with that of the weathered crust and of the resulting soil:—

	Rock.	Weathered Crust.	Soil.
Silica . . .	41.84	39.7	39.17
Potash . . .	0.82	0.83	0.94
Soda . . .	3.45	2.51	1.03
Lime . . .	11.16	8.02	4.72
Magnesia . . .	3.63	3.20	2.92
Alumina . . .	17.51	16.94	16.58
Iron Protoxide . . .	3.71
Iron Peroxide . . .	12.77	15.05	14.22
Phosphoric Acid . . .	0.5	0.48	0.48
Carbonic Acid . . .	0.88	2.67	0.61
Water . . .	3.56	10.5	19.28

Olivine is essentially a silicate of magnesia and protoxide of iron, not uncommon in some basalts, which easily weathers and becomes a soft hydrated silicate, called serpentine, to which *talc* is very similar in composition. These magnesian silicates are not of great importance in the British Islands; only in the Lizard district of Cornwall are they extensively developed and give rise to poor, barren soils.

Calcium Carbonate, though present in many of the older rocks in the crystalline form of Calcite or Iceland Spar, is there to be regarded rather as a secondary product brought by infiltrating water than an original mineral. *It is soluble in water charged with carbonic acid*; hence when the complex silicates containing lime are weathered, the lime is removed in this form. The calcium carbonate is redeposited when the water loses the carbonic acid either by evaporation or by diffusion on contact with air. In a massive form calcium carbonate forms many of the sedimentary formations—the older ones hardened to limestones, and the more recent ones soft like the chalk; in these cases it has been secreted from natural waters by living organisms, foraminifera, corals, etc., and only gets a crystalline structure by later change. Calcium carbonate from organic sources is present to some extent in nearly all sedimentary rocks; the vast majority of the fossils there found are constituted of calcite.

In the limestone and chalk rocks the calcium carbonate is never quite pure; in the white chalk, which is the purest, the proportion of calcium carbonate, after excluding the flints, is only about 98 per cent.; in others the proportion of clay and mud which were simultaneously deposited gradually increases, so that we can find rocks of every gradation between chalk and clay or sandstone.

Owing to its solubility, the weathering of limestone takes the form of the removal of calcium carbonate more or less completely, leaving a fine-grained residue of the insoluble clay or sand. In the case of chalk and of the purer limestones, the insoluble residue consists mainly of a fine red or yellow clay; the chalk downs, when not obscured by drift formations, are covered with a sticky, reddish soil, only as a rule a few inches in thickness, and though the actual chalk is so close, in many cases this soil is almost deprived of all its calcium carbonate. Almost exactly similar material may be obtained in the laboratory by dissolving a few pounds of chalk or limestone in dilute hydrochloric acid. Whenever a section is exposed in chalk or limestone rocks, it will be noticed that the dividing line between soil and rock is very irregular; thin as the soil may be as a whole, in places it descends into cavities and "pipes" in the rock, sometimes 20 or 30 feet deep. In these depressions the soil is the same reddish clay as occurs on the surface, mixed with flints in the case of the upper chalk; they are essentially the results of solution, and represent the lines along which the drainage of the rain water has been more active, owing to a joint or fissure in the rock below.

Other minerals which do not constitute any large proportion of the earth's crust, but still play some part in the soil, are apatite, glauconite, selenite, limonite, and iron pyrites.

Apatite, or crystallised phosphate of lime,— $\text{Ca}_5(\text{PO}_4)_3\text{F}$,—is present in small quantities in many of the fundamental rocks, and is probably the ultimate source of the phosphoric acid of soils. Apatite also occurs massive in some of the older strata, and has been worked as a raw material, for the manufacture of phosphatic manures, in Norway and Canada.

Selenite, hydrated sulphate of lime, $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$, termed gypsum when massive, is not a fundamental mineral, but occurs in most clay rocks in well developed crystals. Diffused through the soil and dissolved in soil water, selenite doubtless provides most of the sulphur required by plants.

Limonite, hydrated oxide of iron, occurs in lumps and bands in many of the sedimentary rocks; in a diffused state it is the main colouring matter of soils; in heavy, undrained soils it often forms a layer or "pan" some inches below the surface. It is deposited from water containing iron on exposure to the air; the rusty deposits and stains from chalybeate springs and wells consist of limonite. It will be noticed that stones taken from peaty land are always bleached white, through the removal of iron, and the surface sand of heathy land is always similarly bleached. On examining a section of any purely sandy formation, the surface soil will be found to be bleached below the layer of vegetable matter to the depth of a foot or more. Then comes a layer an inch or two thick nearly black in colour, where the sand is more or less cemented together by limonite, and below this the normal brown or yellow sand begins.

On other soils the limonite may form a hard continuous layer, impervious to drainage, the "iron pan," or "moor-band pan," which is found a few inches below the surface, and which must be broken up by deep cultivation before satisfactory crops can be obtained from the land. Analogous are the formations of loose rubbly concretions—"crowstone"—found below the surface of certain clay soils, and the bright red deposit of "bog iron ore" generally to be seen beneath the black peaty accumulation in swampy places. The factor common to all these deposits is the absence of

carbonate of lime from the surface soil, which generally shows an acid reaction and a tendency towards the accumulation of humus or peat. The method of formation of these deposits is still a matter of dispute. The theory at present most generally accepted is that the surface soil loses all its soluble material by leaching. Then as the rain-water continues to percolate, the oxides of iron, which are colloids (see p. 39), go into pseudo-solution as "sols" and wash down into the subsoil. During the dry season, however, the soil dries out to a certain depth, at which the "sol" solution begins to evaporate and at a certain concentration deposits solid hydrated oxide of iron. The thin layer thus formed constitutes a nucleus on which further oxide of iron deposits in succeeding seasons until the iron band is formed. Carbonate of lime in the surface soil prevents the action because it is always going into solution, and as long as soluble salts are present the oxides of iron will not assume the "sol" condition. This argument is strengthened by the fact that a definite band or pan is usually associated with a comparatively dry summer climate, such as would permit of the complete drying out of the soil down to a certain depth.

It has been supposed that the oxides of iron in the surface soil are reduced by the presence of the organic matter and carbon dioxide to the state of ferrous carbonate, which reoxidises at the evaporating surface in the summer months. However, the pan always contains alumina as well as iron, and the oxide of alumina will not undergo reduction to a soluble compound, though it will form "sols" like the oxide of iron. Again, ferrous compounds are not to be found in soils, the test generally relied upon as indicating their presence being deceptive. Other factors may, however, be at work, particularly the action of certain

bacteria. The presence of an iron pan or of rusty stains and deposits from the drainage water or in the ditches is a sure sign of a sour, unhealthy soil, which requires lime or chalk before it can be made fertile.

Glaucinite is a hydrated silicate of iron, alumina, and potash with a little lime and magnesia, which occurs as dark green grains in many sedimentary rocks, especially of the Cretaceous age. It is to the presence of this material that the Greensand formations owe their name; it is sometimes also to be seen in chalk and in the tertiary sandstones. It readily weathers to brown oxides of iron.

Zeolites. Akin to glauconite are certain hydrated double silicates of aluminium and the alkalis or alkaline earths, called generically zeolites, which play a very important part in the soil, though they may not be present in large amounts. These bodies, which result from the weathering of the feldspars, contain a considerable proportion of water, loosely combined and readily displaced, but their distinguishing feature is the ease with which the secondary bases they contain, the calcium, magnesium, sodium or potassium, are replaced by other metals, whenever their salts are brought into contact with the zeolites. Little is known of the actual nature of the zeolitic bodies in the soil, but certain zeolites occur from time to time in a pure state. The best known of them is natrolite, which crystallises in fine needles possessing the composition— Na_2O , Al_2O_3 , 3SiO_2 , $2\text{H}_2\text{O}$, a little calcium being generally present also.

Iron Pyrites, FeS_2 , occurs in small brass yellow cubic crystals in many of the older rocks, especially those of a clay character; another form, in fibrous masses of a lighter colour, is called marcasite, and is common in the more modern clays, especially the London clay, and again in round balls in the chalk.

Marcasite readily oxidises in moist air to ferrous sulphate and sulphuric acid: and many clay soils contain basic sulphates, soluble in dilute acids but not in water, that have arisen in this way. Selenite and the soluble sulphates present in well waters, especially in clay soils, are probably secondary products arising from the oxidation of marcasite. In a finely divided condition iron pyrites forms the colouring matter of many dark green or olive rocks and clays.

Soil and Subsoil.

Although the transition from soil to subsoil is gradual, the distinction between the two is, as a rule, easy to be made; the change begins an inch or so below the usual limit of cultivation on arable soils, on pastures at the depth to which the mass of the roots penetrate. The most obvious difference between the two lies in the comparative richness of the staple in decaying vegetable matter or humus, which indeed would be entirely confined to the surface layers were it not for the decay of the deeper roots and the work of worms. To the humus is also due the difference in colour; not only does the colour deepen towards black as the proportion of humus increases, but by it the sands and clay are to a greater or less extent bleached through the removal of the iron oxides which colour them, hence the inorganic material is lighter and duller in colour in the soil than in the subsoil. In stiff clays the subsoil often shows signs of imperfect oxidation at comparatively slight depths. On an old pasture on the Gault Clay a trench was dug, the top 3 inches were black or nearly so and gradually changed to a stiff brown loam which extended to a depth of 9 or 10 inches, becoming lighter and more distinctively yellow as the admixture of humus diminished; below this depth

the clay became mottled, grey and yellow mixed till at a depth of 4 feet practically the whole was blue unweathered clay, owing its colour to iron pyrites and glauconite or kindred silicates of iron protoxide. One of the greatest distinctions between soil and subsoil lies in their respective texture; in humid climates like our own the soil is almost invariably composed of coarser grains than the subsoil, though in arid climates soil and subsoil appear to be almost uniform. This is due to the rain, which constantly percolates through even the stiffest soils and washes down the finest particles; in heavy rains also, water runs off the surface into the ditches, carrying with it the finest particles of the soil and leaving behind the coarser grains on the surface. Naturally, this loss of the finer particles is greater as the soil is more worked and made open to percolation and washing; to some extent it is counterbalanced by the work of worms bringing the fine mould to the surface from below, so that the difference is least in an old pasture. *Per contra*, it is greatest in an old garden soil, where the constant working and further opening of the soil by the introduction of bulky manure often results in so complete a washing down of all the finer particles that the soil proper loses its power of cohering, falls into dust when dry, and is popularly said to be "worn out."

In addition to its humus the soil is nearly always richer than the subsoil in all the essential elements of plant food, despite the fact that crops have been raised on it for generations; the crops, in fact, have been the cause of the difference, for the deeper roots draw food from the subsoil and leave it behind on the surface as the plants decay. Potash is perhaps an exception in this connection; being essentially a product of the weathering of felspar and removable from the soil by

2349

6314

11241

water containing carbonic acid, it is often more abundant in the comparatively unweathered subsoil. The richness of the humus, its greater warmth and the freer access of air also cause the soil to be more abundantly supplied with those organisms which play such an important part in preparing the food of the higher plants: as will be seen later, subsoils become almost without living organisms at a very slight depth.

For all these reasons,—the absence of humus, and of the organisms associated with it, the comparative poverty in inorganic plant food, the presence sometimes of unoxidised material, and on stiff soils the great change of texture,—the subsoil is often comparatively unfertile and may be almost barren. Desirable as it is to work the subsoil and open it to the access of air and the free penetration of roots, all methods of cultivation should be avoided that would bury the surface soil and bring the subsoil to the top. A plough which inverts the soil should not go below the former limit of cultivation, and if it is desired to deepen this limit, it should be done by degrees, half an inch or so each year. Immense damage has been done to the fertility of many of the heavier soils by rash ploughing with steam, especially where the old "lands" were thrown down, burying the fertile soil in the furrows and baring the raw clay on the tops of the ridges.

General Classification of Soils.

In considering any general classification of soils we have to extend our survey far beyond the British Islands, which contain only one group of soils, the products of the action upon the varied range of underlying rocks of the characteristic temperate climate with a moderate, evenly distributed rainfall.

The most satisfactory general classification of soils

is indeed based upon climate, since the rocks from which all soils are formed possess very similar characteristics, and may be mineralogically identical in very distant places. Such a classification marks off the earth's surface into zones of soils, which correspond with the great natural zones of vegetation, in agreement with the general fact which we may find illustrated within our narrower range of conditions, that vegetation and crops vary in response to the climate rather than to the chemical or physical character of the soils on which they grow.

In such a "genetic" classification of soils Sibirtzev distinguishes the following great groups or types:—

1. Laterite soils developed in hot, tropical climates with a high rainfall, by the very rapid weathering of the more primitive and volcanic rocks under the prevailing conditions of heat and moisture. Laterite soils, which characteristically are bright red in colour, are distinguished by a very high percentage of hydrated oxides of iron and alumina. Laterites are found in India, Ceylon, and the other East Indian islands, China, Central Africa and America.

2. Wind-blown loess soils formed of fine particles of rock disintegrated by heat and cold and transported by wind. As a rule these soils are rich in carbonates of lime and magnesia, but are poor in humus. They are often deep and characteristically uniform and stoneless. They are chiefly developed in Central Asia, to some extent in Northern Africa and America.

3. Semi-arid soils of the dry steppe formed in climates possessing violent contrasts of heat and cold and a small rainfall (10 to 15 inches). In these soils the soluble salts arising from the decomposition of the rock have been imperfectly washed out and usually accumulate at a small distance below the surface.

Under certain conditions the salts are brought to the surface and there effloresce (alkaline soils). These soils occur in the Western States of America (Utah, Arizona, etc.), Australia, South America, Asia (Siberia, Mesopotamia), parts of Spain, etc.

4. Black soils (Tchernozem) found on the grassy steppes or prairies of the temperate zone, where a continental climate exists with sharp contrasts between winter and summer and a light rainfall of 15-20 inches, occurring mostly in summer. Under these conditions the soils are fine grained, deep, often wind-borne, with a high proportion of carbonate of lime; but most of all they are characterised by their abundance of humus, not only in the surface layer but at all depths to which the soil persists. Such black soils are found in the Middle West (Manitoba, Iowa, Nebraska, etc.), in European Russia, Hungary and Western Siberia, and in Argentina. They possess an immense reserve of fertility and constitute the chief wheat-producing soils of the world.

5. Grey soils of the forest zone, formed under somewhat similar conditions to the black soils, but where a greater rainfall induces a natural growth of forests instead of grass. These soils contain less humus than the black soils and are also poorer in lime and potash, on account of the greater bleaching to which they have been subject, whereby also their colour becomes lighter and duller. In the main the soils of the United Kingdom, Western Europe, the Eastern States of America and Canada, and the general farming soils of Australia and New Zealand belong to this group, though some fall into the next group.

6. Peat or ashy soils which originate in cold and cold temperate regions with a high rainfall, generally from glacial deposits. Under these conditions acid

humus generally forms and brings about the bleaching of the soil particles and the very complete removal of all nutrient materials like lime and potash. When dry they are poor in humus and that is confined to the surface layer, but in water-logged areas peat accumulates. They pass by insensible stages into

7. Tundra soils, which are developed in arctic climates with low temperatures and a high rainfall.

Among our own soils, though they all possess the group characteristic of comparative freedom from the soluble products of weathering, we shall find much greater and more localised variety than characterises such wide reaching and uniform soils as the loess or the black soils. Although a distinction has been drawn between sedentary soils and soils of transport, there are few sedentary soils that do not contain material which has been carried from some other formation at a distance; only on great stretches of flat country belonging to a single geological formation may be expected a soil purely derived from the rock below. Especially in Britain, where the outcrops of the different formations are generally narrow, and where the surface is always undulating, we find that the continual creeping of soil particles to lower levels has resulted in an admixture of foreign material in most soils. "La couche très mince de la terre végétale est un monument d'une haute antiquité" (Elie de Beaumont), so that in many places the soil contains the débris of formations now removed by denudation. In the south-east of England the soils that rest on the chalk, which may be only from a few inches to a few feet below, contain abundance of quartz sand, even up to 75 per cent. No such sand exists in the chalk itself, so that it has come from the lower tertiary beds which once over-spread the chalk. On the wide flats of Weald Clay

in the same district, the soil contains sand that has crept from the central hills of the Weald or from the Lower Greensand escarpment, often several miles away. The following analysis of a soil resting on a brick earth bed in the valley of the Kentish Stour, shows that the brick earth, which itself contains little or no chalk, has become covered with chalky rain-wash from the hills flanking the valley :—

Depth—Inches . .	0 to 6	6 to 12	12 to 18	18 to 24
Calcium Carbonate %	9.20	7.16	2.6	0.96

In the main, however, the bed below gives its character, both chemical and physical, to the soil; and the ordinary rough classification of soils into sands, clays, marls, and loams, follows closely the nature of the underlying geological stratum. A coarse-grained sandstone gives rise to a typically sandy soil, such as the soils derived from the Bagshot beds, which form the New Forest and the heathy land in the Aldershot district; on the Lower Greensand lie the sandy heaths in west Surrey, Hampshire, and in Beds.; again, on the Bunter beds of the New Red Sandstone lie many of the uncultivated commons and parks of the Midlands, such as Sutton Park, Cannock Chase, and Delamere Forest. These coarse sandy soils, which have so often remained unenclosed as forests and commons, are generally deficient in chalk, and accumulate peat wherever a parting of clay gives rise to stagnant water.

Clay soils are common in nearly every part of Britain; they arise from the great clay strata of all ages, like the London Clay, the Weald Clay, and the Oxford Clay, or from metamorphic rocks like slate, or from the crystalline rocks like granite and basalt, or even from the limestones by solution.

Between the sands and the clays come mixtures of

all grades, better working than the clays and more fertile than the pure sands; sometimes the clay formation itself contains sand, as in the upper beds of the London Clay, or we may have a fine-grained sandstone mixed with clay, as in some of the carboniferous rocks. In all these cases, when chalk is absent, and drainage incomplete, there will be an accumulation of humus, resulting in a peaty formation.

Some argillaceous limestones give rise to typical "marls," mixtures of chalk and clay; *e.g.*, some of the beds of the Lias and of the Keuper.

Other limestones with a sandy basis, and fine-grained sandstones cemented by carbonate of lime, give rise to "loams," which are free-working soils, mainly composed of fine sand with some clay and a little calcium carbonate. The alluvial soils in the valleys are loams, passing in places into gravels; these are generally the richest soils; as a rule they are mixtures derived from many formations, and so are well supplied with humus and the mineral elements of plant food; they are deep, and not over consolidated, thus admitting of the percolation of water and the descent of roots; yet they are fine-grained enough to prevent them drying out too rapidly. But though these terms, sands, clays, marls, loams, and peaty soils, serve for rough descriptive purposes, a more exact determination of the constituent particles is necessary to properly characterise a soil, and for this we must resort to what is termed the "mechanical analysis" of a soil.

CHAPTER II

THE MECHANICAL ANALYSIS OF SOILS

Nature of Soil Constituents : Sand, Clay, Chalk, and Humus—
Methods of Sampling Soils—Methods for the Mechanical
Analysis of a Soil—Interpretation of Results.

It has already been indicated that as soils are derived from the waste of rocks, they consist of a mass of particles of various minerals and of all sizes, together with a certain amount of humus of vegetable origin, and that they may be roughly classified according to the predominance of the coarse-grained particles called "*sand*," or the very fine material known as "*clay*."

The mechanical analysis of a soil consists in pushing this rough "eye and hand" classification a stage further into the region of exact measurement, and in determining the minute physical structure of the soil by estimating the proportions in which particles of various sizes are mixed together in the soil. Upon the physical structure of the soil so determined, or as we shall practically term it, the *texture*, depend some of its most important features, particularly its behaviour with regard to the supply of water to crops and its amenability to cultivation.

In the first place, it will be necessary to discuss a little more thoroughly the nature of the four substances to which the texture of the soil has been referred—the sand, clay, chalk, and humus—of which the first two

are of most importance, since soils which are mainly characterised by chalk or humus are less commonly in cultivation.

Sand.—On the seashore, in beds of an alluvial nature, and in formations of all geological ages, we are familiar with sand; in the main it consists of grains of quartz, rounded by continual rubbing, and more or less coloured by oxide of iron. It represents the quartz contained in the fundamental rocks, weathered and worn by water; in some cases of comparatively recent origin, in others it is material that has repeatedly been formed into a sedimentary rock, disintegrated afresh and sorted by the action of running water. The coarser the grains of which a sand is made up, the more rapid must have been the current from which it was deposited. The following table shows the rate of flow which is necessary to carry sand grains of various sizes:—

Diameter of Grains, mm.	Velocity of Current, mm. per sec.
0.5	64
0.3	32
0.16	16
0.12	8
0.072	4
0.047	2
0.036	1
0.025	0.5

A closer examination of most sands will show that they do not consist wholly of quartz grains, but also contain rounded fragments of many of the minerals present in the fundamental rocks which have any resistance to weathering. Flakes of mica are common, fragments of more or less altered felspar, of oxide of iron, and even of tinstone, rutile, and zircon, may be

identified. In fine-grained sands the fragments of minerals other than quartz become as a rule more abundant, till they begin to predominate over the quartz grains in the finest silts and muds that are deposited from very gently moving water. Under the microscope the quartz grains show a crystalline structure, and a surface more or less dulled and rounded according to the travel the grains have suffered. In mass the chief characteristic of sand is its want of coherence when dry.

Clay.—The material we call clay is characterised by certain properties that are shown when the clay has been “puddled,” *i.e.*, kneaded when in a moist condition. The clay is *plastic*, it can be moulded and worked into various shapes, even into quite thin leaves, and it will retain these shapes on drying. During the drying process a shrinkage takes place: the dry material is hard and tenacious, and can only be broken or crumbled with difficulty. The shrinkage is considerable: a little brick was made of good modelling clay 7 inches long, and about 1 square inch in section; two marks were then made on this 6 inches apart; after a fortnight's drying in a room the marks were only 5·7 inches apart, showing a shrinkage of 5 per cent. Clay is further impermeable to water when in the moist puddled condition, for which reason it is used to line the bottoms of ponds in pervious soil, and is built up inside the retaining dams of reservoirs; quite a thin layer of clay will hold water indefinitely as long as it is not allowed to dry and crack, nor to be washed away by the action of running water.

From a chemical point of view, all clays are found to consist largely of kaolinite, the hydrated silicate of alumina which is formed by the weathering of felspar; the other materials present consist of extremely

fine grains of quartz and other weathered minerals, together with more or less oxide of iron. "China clay" and the best "pipe clays" contain little or no iron; the deep-seated clay formations are generally coloured dark green or blue or black by the presence of ferrous silicates like glauconite; on weathering and exposure at the surface the clays become yellow or brown, owing to the oxidation of these ferrous to ferric salts.

Water in which a little clay has been rubbed up remains turbid for a very long time; days and even weeks elapse before the particles settle down to the bottom—indeed, however long the liquid may be at rest, a slight haze or cloudiness may be observed within it. Schloesing was the first to draw a distinction between the part of the clay, amounting to 1 or 2 per cent. only of the whole, which persists in remaining suspended and the portion which settles down; he has called it "colloid clay," and attributed the typical clay properties to the jelly-like medium of colloidal matter by which the other defined particles of the clay are surrounded. These colloids of clay may be associated with such typical colloids as the hydrates of silica and organic bodies like starch, gelatin and gum, which will pass into a kind of solution—the "sol" condition—when, however, they cannot diffuse through a membrane. Under certain conditions of temperature, or in the presence of electrolytes, their relation to the water by which they are surrounded is changed, and they set to a more or less firm jelly,—the "gel" phase,—and when they are then dried they form a hard non-crystalline mass with much shrinkage and a characteristic fracture. In their "gel" condition they will imbibe considerable quantities of water and swell. The colloids in their "sol" condition differ only from suspended matter in their fineness of grain and the intimacy of their contact with

the water, as exhibited in such matters as the surface tension between their material and water and the nature of the electric charge they carry. While truly suspended particles, however fine, may be pictured as exhibiting a sharp boundary to the water, colloids may be conceived as surrounded by successive shells of less and less hydrated material shading off into the water. They thus consist of particles too fine to settle down in water, or to be arrested by a filter even of porous porcelain, but which are still sufficiently coarse to show their presence when a strong beam of light is passed through the liquid, as is not the case with bodies truly dissolved. We thus see that clay cannot be given a purely chemical definition; the characteristic clay properties of plasticity, impermeability to water, and shrinkage and tenacity on drying depend in the first place upon the fineness of grain of the particles composing it. It is easy to show that fineness of division is a necessary factor in the existence of clay, because we can obtain material possessing the chemical composition of typical clays which yet behave physically as if they were sand. A sample of crude kaolinite rock, as dug in Cornwall from the surface of granite, was powdered and passed through a sieve retaining all particles above 0.2 mm. in diameter; the remainder, which consisted mainly of kaolinite with a little mica, was further separated by sedimentation from water into four fractions:—

Fraction.	Approximate Size of Particles in mm.	Per cent. of Original Material.
1	0.2 to 0.05	22
2	0.05 " 0.01	39
3	0.01 " 0.005	21
4	below 0.005	20

Of these fractions the first contained all the mica, the others were practically pure kaolinite, yet the second fraction showed none, and the third very little of the characteristic properties of clay; when dried they fell or could easily be rubbed into a fine powder, only the fourth and finest fraction dried into a hard coherent mass. Thus we can have material which consists entirely of kaolinite, and yet is not clay; such as we see in natural deposits of fuller's earth, which consists of kaolinite but possesses no plasticity and falls on drying into a fine powder.

In the same way a natural soil contains particles of silicates of alumina of all sizes, though they only begin to predominate in the fractions of finest grain. In fact the physical processes of weathering, abrasion in running water, cannot reduce rock materials into particles below a certain size, thus the particles in the fractions of finest grain are not quartz but materials that have been formed by the chemical disintegration of feldspar and similar rock constituting minerals.

On separating by the method to be described later (p. 56) a brick earth soil into fractions according to their size and analysing each fraction, the result shown on accompanying table (p. 42) was obtained.

While there is a steady decrease in the amount of silica and an increase in the amount of alumina and potash as the particles get smaller, there is a sudden change of composition when the two finest fractions are reached. Taking the mean of a number of analyses of the clay fraction of Rothamsted soils, then if all the alumina may be supposed to be combined as kaolinite Al_2O_3 , 2SiO_2 , $2\text{H}_2\text{O}$, the clay would contain 72 to 75 per cent. kaolinite, 11 to 12 per cent. ferric oxide, with 9 to 10 per cent. of silica, and 4 to 6 per cent. of alkalis and alkaline earths. This means that the clay contains

practically no quartz particles, all the silica being in combination with the bases.

	Fine Sand.	Silt.	Fine Silt.	Finest Silt.	Clay.
Diameter in mm.	0.2 to 0.04	0.04 to 0.01	0.01 to 0.005	0.005 to 0.002	Below 0.002
Per cent. of Soil	25.0	27.3	16.4		1.1
Silica . .	91.1	88.4	84.4	60.3	50.9
Alumina . .	2.7	6.3	5.8	21.5	22.8
Ferric Oxide . .	1.2	1.6	2.8	7.4	13.1
Lime . .	0.4	0.8	0.5	1.8	2.3
Magnesia . .	0.1	0.2	0.2	0.4	1.0
Potash . .	2.5	2.7	5.0	8.2	7.2
Phosphoric Acid	0.1	0.1	0.1	0.3	0.4

A more detailed examination of the analyses of the clay fractions suggest that two distinct forms of clay may occur, the one from comparatively fertile soils containing about 21 per cent. of alumina and 51 to 54 per cent. of silica, the other, from more infertile clay soils, containing up to 30 per cent. of alumina and less than 50 per cent. of silica. The data, however, are as yet scanty.

From these results we must conclude that kaolinite is not necessarily clay, but that fineness of grain is also an essential factor, the characteristic clay properties not being developed except in material the particles of which are less than one-fivehundredth of a millimetre in diameter.

But though fineness of grain is a factor, it is probably not the only factor; the fine particles must be of such a composition as to form a colloid system with water. This may be illustrated by a consideration of another important property of clay—its power of flocculating or coagulating under the action of minute quantities of various salts. To illustrate this point, a few grams

of good clay should be rubbed up with several litres of distilled water, and the supernatant turbid liquid poured off into a series of tall jars each holding from 300 to 500 c.c. of the liquid. To one of these jars nothing is added, to two others .018 and 0.009 gram of hydrochloric acid respectively, to a fourth 0.028 gram of calcium chloride, and to the fifth 0.58 gram of sodium chloride. The contents of the jars are shaken up until solution is effected, and they are then put aside to stand. After some time the liquids to which the salts have been added will begin to clear, and the clay particles will clot together and fall to the bottom; the jar containing the larger quantity of hydrochloric acid will clear the first, the others will clear approximately together, but the pure clay water will remain turbid for many days. If a little of the turbid clay water be examined by a $\frac{1}{8}$ -inch oil immersion lens under the microscope, it is just possible to see the clay particles in rapid "Brownian" motion, and if a little acid or salt be then introduced under the cover glass, they will be seen to move together and form into little clots or aggregates as soon as they experience the effect of the added acid or salt. By comparative experiments it can be shown that the flocculating power of any salt is proportional to its amount up to a certain limit, when the material is so completely flocculated that no further addition of salt has any effect; conversely, the flocculating power of a given amount of salt is inversely proportional to the quantity of clay suspended in the liquid. The flocculating power of a salt also varies with both the acid and the metal; the following table shows approximately their comparative effect:—

HCl	.	.	30	HNO ₃	.	.	28	H ₂ SO ₄	.	.	20
CaCl ₂	.	.	15	Ca(NO ₃) ₂	.	.	10	CaSO ₄	.	.	>5
KCl	.	.	3	KNO ₃	.	.	>2	K ₂ SO ₄	.	.	<1
NaCl	.	.	>1	NaNO ₃	.	.	<1	Na ₂ SO ₄	.	.	0.5

The alkalis and salts like phosphate of sodium, which give rise to free alkalis on hydrolysis, instead of flocculating have the opposite effect, and keep the particles in their finest state of division without any tendency to settle.

In their behaviour towards flocculating salts the finest particles of quartz and ferric oxide behave essentially differently from kaolinitic particles. Suspended in water they flocculate spontaneously and will not remain turbid for many minutes, though in their turn they can be deflocculated and made to remain in suspension by adding a trace of free alkali to the liquid.

Soils are known composed of particles of great fineness of grain, but destitute of colloidal properties, for example, soils made from the fine quartz particles—"tailings and slimes," coming from the crushing plant of a gold mine. These soils cannot be flocculated and are extremely difficult to cultivate.

We may thus conclude that fineness of grain is not the only factor in the constitution of clay, but that the characteristic clay properties which are always associated with the power of flocculation depend also upon the nature of the material; in the soil they depend upon the presence of the zeolitic double silicates derived from the weathering of the feldspars in the fundamental rocks. We may imagine the soil as consisting of particles of all sizes down to the ultra microscopic. Most of the particles possess a covering of a jelly-like colloidal character which chemically resembles the zeolites in that it is a silicate containing many bases (alumina, calcium, magnesium, potash, soda, and ammonia), which can be readily interchanged with other bases in the soil solution. The finer the particles become the thicker is the jelly layer in comparison, until the finest, in which the colloidal properties are

most fully developed, are wholly "gels." Moreover, the "gel" particles behave as if they possess a very large and active surface, indeed they are the active constituents of the soil.

The power of flocculation plays a very important part in the cultivation of clay soils. When such a soil possesses a good texture its finest particles are in a state of temporary aggregation or flocculation, so that they behave as if the soil, as a whole, were built up of much coarser particles. Just as a potter or a brick-maker brings his material into its highest condition of plasticity by repeatedly kneading and working it, by which process the naturally formed aggregates are resolved into their ultimate particles and the material is made as fine-grained as possible, so if a clay soil be in any way worked or disturbed when in a wet condition, it becomes apparently more clayey than before. It remains persistently wet and impervious to the percolation of water, and shrinks when dry into hard tenacious clods. But if the clay be exposed to the weather for some time, so that it undergoes alternations of temperature, freezing and thawing, wetting and drying, it will experience a certain amount of spontaneous flocculation and behave as though it were coarser grained, so that if caught in the right state of partial dryness it may easily be crumbled.

Flocculation may also be aided or otherwise by the use of certain artificial manures, as will be explained later; the incorporation again of humus much improves the texture, while the action of lime is particularly effective and is much employed in practice to ameliorate the working of clay soils.

Lime itself can be shown in the laboratory to possess little flocculating power, for though its base is calcium, a highly effective metal, it is combined as a hydrate, which

has a deflocculating effect. However, as soon as lime is applied to the soil it becomes converted into carbonate, and some of it will be always going into solution as bicarbonate, a salt which possesses great flocculating power.

In practice, the application of such small quantities of lime as a ton or even half a ton to the acre have the greatest value in ameliorating the working of clay land; not only does it move more readily and fall more easily into a good tilth, but by becoming coarser grained it allows the rain to percolate more freely and thus dries earlier in the season, so that the limed land can often be worked several days before the unlimed land can be touched. Though the Rothamsted soil is by no means of the heaviest, it is only because of the repeated additions of carbonate of lime in former years that it can be retained under arable cultivation; portions of the same land without carbonate of lime lie so wet in the spring that they were laid down to grass in consequence of the repeated failures to secure a good seed bed.

Chalk, or carbonate of lime, is present in all soils, with the exception of a few extremely open sands and peaty soils that are practically of vegetable origin. The proportion varies enormously, according to the origin of the soil; on some of the thin loams derived directly from the great calcareous formations like the chalk or the oolite, the calcium carbonate in the soil may rise to as high a proportion as 60 per cent., but in the majority of the loams under cultivation the proportion is below 1 per cent., and it often is barely detectable in clays and sands. Chalk in the soil is essentially a transitory substance, as it is constantly removed by the action of percolating water charged with carbonic acid, arising from the decay of vegetable

matter in the surface soil. Many of the fermentation changes that also take place in this vegetable matter give rise to acids, which in their turn combine with the calcium carbonate. So rapid are these removals of calcium carbonate that it is difficult to understand how any of it persists in the surface layers of many soils, the subsoil of which shows that they must have been initially poor in chalk, were there not some compensating agencies at work. Amongst these agencies must be reckoned the calcium salts in plants, which in many cases are drawn up by deep-seated roots from the subsoil and become calcium carbonate on the ultimate decay of the plant tissues.

In a normal soil the particles of calcium carbonate are of all sizes, many of the finer particles of silt and clay are loosely cemented together by calcium carbonate, as may be seen by the increased proportion of the finer fractions that is found if a soil be washed with dilute acid before it is separated by sedimentation.

Humus.—On examining many rocks taken from such depths that they have undergone none of the weathering processes which convert them into soil, they are found to contain both carbon and nitrogen, occasionally in quantities comparable with those found in the soil itself. This is only the case with the sedimentary rocks and particularly with indurated clays; the carbon and nitrogen in fact only represent the organic matter in the original deposit in a more or less mineralised condition. But since these carbon and nitrogen compounds are only slightly affected by any of the weathering processes by which soil is made, they must pass into the soil and there become merged with the organic matter of more recent origin. Such material, however, plays a very unimportant part in the soil, and we may pass on at once to the *débris* of vegetation of

recent origin or the humus which is characteristic of all soils proper.

The term humus is applied to the black or dark brown material of vegetable origin which gives to surface soil its characteristic darker colour as compared with the subsoil. It is essentially a product of bacterial action; there are a number of bacteria working in the absence of air and universally distributed, which attack the carbon compounds of plant tissues, especially the carbohydrates, with the production of marsh gas or hydrogen, carbonic acid, and humus. In the presence of air the characteristic humus-forming fermentation is continued by one which results in the complete combustion of the organic matter to carbonic acid. For this reason more humus is found in a pasture than in a continually aerated arable soil, more again in clays than in the lighter soils through which air is always being drawn as the rain percolates, and the accumulation of humus reaches its maximum where considerable rainfall and an impermeable stratum combine to make the soil so water-logged that all access of air is cut off, as in swamps and bogs. The presence of chalk in the soil also assists in the destruction of humus, since it neutralises the acids which largely compose the humus, and which tend to inhibit the further action of bacteria.

The chemical composition of humus is indefinite; it is a variable mixture of several substances, themselves of very complex constitution; it always contains more carbon and less hydrogen and oxygen than the vegetable tissues from which it was formed. The following figures show the composition of grass and of the top brown layer of turf in a peat bog, also of the same peat of greater age at depths of 7 and 14 feet, the mineral matter and moisture being excluded in calculation in each case:—

	Grass.	Top Turf.	Peat at 7'.	Peat at 14'.
Carbon . .	50.3	57.8	62	64
Hydrogen . .	5.5	5.4	5.2	5
Oxygen . .	42.3	36	30.7	26.8
Nitrogen . .	1.8	0.8	2.1	4.1

Substances akin to humus can be formed from the carbohydrates (such as sugar, starch, and cellulose), by heating them for some time with water under pressure, the action being more rapid if a trace of mineral acid be present; the resulting substances are weak acids and form salts, so are generally termed humic acid:—

	Humic Acid.	
	From Sugar.	Natural.
Carbon . .	63.9	56.3 to 59
Hydrogen . .	4.6	4.4 " 4.9
Oxygen . .	31.5	32.7 " 36
Nitrogen	2.8 " 3.6

As a rule, the active humus of the soil is there present in the form of salts of calcium, which on treatment of the soil with dilute hydrochloric acid are decomposed, a little of the humic acids going into solution but the greater part remaining undissolved. By filtering off the acid and then treating the soil with a weak (4 per cent. by volume) solution of ammonia or other alkali, the liberated humic acids are dissolved and may be reprecipitated either as free acids by the addition of hydrochloric acid, or as calcium salts by the addition of a solution of calcium chloride. The humic acids thus going into solution are sometimes estimated as "soluble humus," they do not include the whole of either the organic matter or the nitrogen in the soil. The brown

solution that is formed is akin to the dark liquid draining from a dung heap, which contains humus dissolved by the alkaline carbonates of the fermented urine.

Occasionally soils are found which naturally possess an acid reaction, and in which the whole or part of the soluble humus is uncombined with calcium. In practice a sharp distinction can be drawn between the acid humus of the upland moors and peat bogs, formed where the water contains no mineral bases, and the neutral humus of the black soils of the Fens, formed from vegetation that has decayed in water containing calcium carbonate. The latter is much more subject to further changes on aeration and in cultivation readily yields to plants the nitrogen it contains. •

Physically the humus of the soil is a colloid and possesses the colloid properties of swelling by imbibition of water and acting as if it possessed an extensive surface. To this extensive surface may be attributed some of the supposed chemical properties of humus, for example, its reddening effect upon blue litmus paper. This does not indicate that the humus is acid, but the base of the neutral blue litmus is more readily absorbed by the surface of the colloid than the acid portion, which is red.

Although dark brown humic substances can be prepared from carbohydrates, and therefore contain only carbon, hydrogen, and oxygen, yet the soluble humus of the soil, even when dissolved and reprecipitated, always contains some nitrogen, nor can it be obtained entirely free from phosphorus and mineral matter. The original vegetable matter is made up not only of carbohydrates, but of other carbon compounds containing nitrogen, and in some cases both nitrogen and phosphorus; these all break down under bacterial action into dark-coloured substances richer in carbon,

and roughly classed as humus. The splitting-up process continues in the soil, so that humus becomes one of the great sources of nitrogen for the food of plants, and a soil well supplied with humus is generally regarded as fertile.

During the formation and continued decomposition of humus the carbohydrates appear to be first attacked, and the nitrogen-containing bodies, *e.g.*, the nucleins in particular, resist the action of bacteria. For this reason, where we find the proportion of humus in a soil is low, the proportion of nitrogen in the humus itself will be high, the decay of the humus falls more heavily on the purely carbonaceous part of the material.

This is seen in the figures obtained by Lawes and Gilbert for the ratio that exists between the proportions of carbon and nitrogen in various soils:—

RATIO $\frac{C}{N}$.

Cereal Roots and Stubble . . .	43
Leguminous Stubble . . .	23
Dung . . .	18
Very old Grass Land . . .	13.7
Manitoba Prairie Soils . . .	13
Pasture recently laid down . . .	11.7
Arable Soil . . .	10.1
Clay Subsoil . . .	6

Hilgard and Jaffa also found that the humus of soils in an arid climate, where the deficiency of rainfall causes the soil to be very open, contains a higher proportion of nitrogen than is found in the humus of damper soils:—

	Number of Samples Examined.	Average per cent. of Humus in Soil.	Average per cent. of Nitrogen in Humus.
Arid Soils . . .	18	0.75	15.87
Semi-arid Soils . . .	8	0.99	10.03
Moist Soils . . .	8	3.04	5.24

The following table gives the results of the determination of carbon, nitrogen, humus, and the percentage of nitrogen in the humus, in a selection of extremely rich virgin soils obtained from different parts of the world; the Canadian, Russian, and Monte Video soils were very similar uniform fine-grained grey or black soils found on the great plains:—

	Locality.	Description of Soil.	Carbon.	Nitrogen.	Ratio C/N.	Soluble Humus.	Nitrogen % in Soluble Humus.
1. Canada .	Indian Head	Black Prairie	2.59	0.317	8.2	3.94	4.07
2. Canada .	Wide Awake	Black "	2.58	0.330	7.8	5.09	2.71
3. Russia .	Ploty	Black Steppe	2.19	0.268	8.2	5.66	2.42
4. Rhodesia .	Salisbury	Black Vlei	20.15	1.89	10.7	21.3	2.40
5. Monte Video	...	Black { "Camp" Soil }	1.89	0.261	7.3	4.48	3.51
6. New Zealand	{ Tararua Mountains	Black Sandy Pasture	12.66	0.949	13.2	10.35	4.67

These results would seem to indicate that the most valuable humus, *i.e.*, that which will decay rapidly and yield nitrogen compounds available as food for plants, is that possessing a high ratio of carbon to nitrogen.

Against this, Berthelot and André have investigated the ratio of carbon to nitrogen in the different portions of the humus which can be dissolved by alkalis or acids, and they find that the most soluble portions contain the highest proportion of nitrogen. It does not, however, follow that the substances most soluble in acids or alkalis are necessarily those which will most readily be converted by bacteria into a form available for plants, and, on the whole, the evidence seems to show that a humus rich in nitrogen will yield it very slowly to crops.

Humus acts as a weak cement and holds together

the particles of soil, thus it serves both to bind a coarse-grained sandy soil, and, by forming aggregates of the finest particles, to render the texture of a clay soil more open. In determining the sizes of the constituent particles of a soil, the "mechanical analysis," it is desirable to remove the humus as far as possible, and so break up these temporary aggregates.

Sampling of Soils.

The first step in the analysis of any soil, mechanical or chemical, consists in obtaining a sample that shall adequately represent the land in question.

In this country it is customary to take a sample down to a depth of 9 inches as representing the soil proper; it is, however, doubtful if this is not too deep, being below the depth to which cultivation is generally carried; probably a 6-inch sample would more truly represent the cultivated soil. In many cases it will be found that the true soil does not extend to a depth of anything like 9 inches, but that there is a sharp change into subsoil or even rock before this point: *e.g.*, on the chalk downs the soil is often not more than 4 inches deep, below which white broken chalk rock begins. In such cases the sample must only be taken to the depth at which the visible change begins.

To obtain the sample two methods are generally adopted. At Rothamsted a steel box, without top or bottom, 9 inches deep, and 6 inches square in section, is used; the sides are wedge-shaped, about $\frac{3}{4}$ inch thick at the top and tapering off to cutting edges below. The surface, if uneven arable land, is first raked over and gently beaten level, then the box is placed in position and driven down with a heavy wooden rammer till the top of the box is flush with the surrounding soil. The soil enclosed by the box is then carefully dug

and scraped out into a bag for conveyance to the laboratory; two or three samples to the same depth being taken from the same field and afterwards mixed. Should samples of the subsoil be required, the box is left in position after its contents have been scraped out, and the surrounding soil is dug away to the 9-inch level, the box is then rammed down for the second 9 inches, and its contents removed: the process being repeated till the required depth has been reached.

A modification of the Rothamsted method consists in marking out on the surface a square 9 inches on the side, and digging away the surrounding soil until a 9-inch cube of earth remains standing; over this a wooden box is slipped, and the cube is cut off by pushing a spade beneath at the 9-inch level.

On soils which do not contain many large stones, samples may be taken with an auger, both more rapidly and with greater security of obtaining an average sample. A convenient tool for the purpose consists of a cylindrical auger made of steel, about $\frac{1}{8}$ inch thick, of 2 inches internal diameter and 12 inches deep, with a slot $\frac{3}{4}$ inch wide running from top to bottom; the lower edge of the cylinder and the edges of the slot are sharpened; to the upper end of the cylinder a handle carrying a wooden crossbar is riveted. The auger is forced gently into the soil with a twisting motion until the required depth is reached, when the tool is withdrawn and the core scraped out into a bag. Six to ten cores at least are taken at regular intervals in the same field and mixed to secure an average sample. Each boring can be continued to obtain subsoil samples as deep as the length of the handle permits. It is impossible to obtain samples with the auger when the soil is dry. Fig. 2 shows a photograph of both types of soil-sampling tools.




FIG. 2.—Photograph of Soil-sampling Tools.

[To face page 54.]



When the samples reach the laboratory they are spread out on shallow trays to dry, which process may be accelerated by a gentle warmth, not exceeding 40° C. In dealing with stiff soils it is advisable to crumble all the lumps by hand while the earth is still somewhat moist. When the whole is sensibly dry the stones are separated by a sieve having round holes 3 mm. in diameter; the material that does not pass the sieve is gently worked up in a mortar with a wooden pestle, care being taken not to break the stones, chalk, etc., but only to crush the lumps of earth. Finally, the material upon the sieve is roughly weighed and well washed in a stream of water till all the fine earth is gone, dried, picked over to free it from roots and stubble, and weighed as "stones." To get the proportion borne by the stones to the soil, the fine earth is also weighed, an addition being made of the weight lost by the stones in washing.

Of course the figure obtained for the proportion of stones is only approximate, for if the stones are of any size they will be very irregularly caught by the auger or even by the 6-inch square tool. The material passing the sieve is again spread out in a thin layer in an ordinary room, until the surface maintains the same colour as the lower layers; it is then bottled up as "air-dry fine earth" for analysis.

The Mechanical Analysis of a Soil.

The mechanical analysis that follows consists in dividing the fine earth into a series of fractions consisting of particles of known size; we can use sieves to sort out the coarser grades, but the finer ones must be separated by their relative powers of remaining suspended in water.

The methods in use depend on two principles:

in one, the hydraulic method (Hilgard, Schöene, Nöbel), soil is washed by successive currents of water of velocities calculated to carry particles of the required size according to the table on p. 37; in the other, the sedimentation method of Osborne, Knop, and Schloesing, the soil is suspended in water and allowed to stand, the separation being effected either by the times required for the particles to settle down through a fixed distance, or by the distances fallen in a given time. The method to be described is based upon the latter principle. The hydraulic method requires special apparatus, and is only suited to laboratories entirely devoted to soil analysis.

Method of Analysis.

1. Ten grams of the air-dry fine earth are weighed out into a beaker or basin and treated with 100 c.c. of $N/5$ hydrochloric acid; the soil is well worked up with a rubber pestle (made by fixing a glass rod into a small solid rubber bung) until all the lumps of clay, etc., are broken up. If the soil contains much calcium carbonate, a further addition of acid may be required.

The object of the acid is to dissolve the carbonates and humates, and thus loosen the particles in any aggregates where chalk or humus form the cement. Without this preliminary treatment the amount of clay found will be largely determined by the proportion of humus present; the soil of an arable field, for example, will show more clay than the soil of an adjoining pasture, when the sedimentation is made with water alone. But after the preliminary treatment with acid to remove the humus, both fields will show the same proportion of clay (as they should do, since they are of the same origin), and only differ in the amount of humus they have accumulated—a temporary factor.

After standing with the acid for an hour, the whole is thrown on a tared filter and well washed until all acid

is removed. The filter and its contents are dried and weighed; the loss the soil has suffered represents the material dissolved and the hygroscopic moisture.

2. The soil is now washed off the filter with ammoniacal water (about 1 c.c. of strong ammonia solution in half a litre of water) on to a small sieve of 100 meshes to the linear inch, the portion passing through being collected in a beaker which is marked on the side at a distance of 8.5 cm. from the bottom.

The ammonia completes the dissolution of the humates, and also masks the effect of any traces of soluble salts which may be left and would cause aggregation in the manner indicated earlier, p. 53.

The portion which remains on the sieve is dried and weighed. It is then divided into "fine gravel" and "coarse sand" by means of a sieve with round holes of 1 mm. in diameter, the portion retained by the sieve being designated "fine gravel."

3. The portion in the beaker is well worked up with the rubber pestle, ammoniacal water is added up to the 8.5 cm. mark, and the whole is put aside to stand for twenty-four hours. The turbid, supernatant liquid is then rapidly poured off into a large jar, and the residue is rubbed up again with the rubber pestle and more ammoniacal water, as before. The whole operation of filling to the mark, standing for twenty-four hours, and pouring off the turbid liquid is carried through as before, and repeated as long as any matter remains in suspension for twenty-four hours. Generally seven to ten decantations will be sufficient, after which the united turbid liquid is evaporated to dryness in a tared basin, and weighed. This fraction consists of the "clay" particles less than 0.002 mm. in diameter, together with all the soluble and some of the insoluble humus. The contents of the dish are ignited over an Argand burner

for some time and reweighed, to obtain the weight of the "clay" after ignition.

4. The sediment from which the clay has been removed is worked up as before in the beaker, which, however, is now only filled to the depth of 7.5 cm. The contents are now allowed to stand for twelve and a half minutes only, when the liquid is poured off into a large jar as before. The operations are then repeated until all the sediment settles in twelve and a half minutes and the liquid above is left quite clear. The contents of the jar are now evaporated to dryness and weighed, as in operation 3, before and after ignition; this fraction is designated "fine silt," and lies between 0.010 and 0.002 mm. in diameter.

5. The sediment remaining in the beaker is worked up afresh just as in the previous operations, the mark being now placed 10 cm. from the bottom of the beaker, and the time of settlement fixed at one hundred seconds. The sediment is dried and weighed as "fine sand," while the portion that is poured off is obtained by evaporation as in the previous operations, and is designated as "silt." The soil has thus been divided into the following series of fractions :—

		Diameter in Millimetres.		
		Maximum.	Minimum.	
1	Stones and Gravel	3	} Separated by sifting.
2	Fine Gravel . . .	3	1	
3	Coarse Sand . . .	1	0.2	
4	Fine Sand . . .	0.2	0.04	} Separated by subsidence.
5	Silt . . .	0.04	0.01	
6	Fine Silt . . .	0.01	0.002	
7	Clay . . .	0.002	...	

If there be much "fine gravel" in the soil, it is best to make a separate determination of its amount on a sample weighing 50 grams, treating with acid as before, and then washing the whole on to the 1 mm. sieve. The result obtained should be taken as the true percentage, and the other percentages found in the analysis of 10 grams only should be recalculated to agree with it.

The sizes of the particles, the depth of the liquid, and the times adopted above, are purely conventional. The time of settlement required to obtain a fraction of any given range of size can be determined by a series of trials, the material remaining suspended in each case is measured under the microscope until the right time is hit off to secure the desired range of size in the sediment. The relationship between the time of settlement, the height of the liquid column, and the diameter of the particles, is governed by the formula:—

$$v = \frac{2ga^2(\sigma - \rho)}{9\eta}$$

where σ is the density of the particle, a its radius, ρ the density, and η the coefficient of viscosity of the liquid. The application of the formula, however, requires to be checked by observation with the microscope, because the particles are not spheres.

The hygroscopic moisture and the loss on ignition also require determination, which is described under the chemical analysis of a soil.

Interpretation of Results.

It is as yet impossible to predict the behaviour of a soil under cultivation from a consideration of its mechanical analysis; in a general way we can see whether a soil is heavy, whether it is likely to dry "steely," or whether it will crumble readily under proper cultivation, and whether it is more suitable for

market gardening or wheat growing, but the more refined points of difference connected with the management of given soils, which become known by experience to a good practical farmer, cannot as yet be deduced from the analysis. It is necessary to accumulate more data, until we possess the mechanical analysis of a large number of soils whose texture and amenability to cultivation have been ascertained by long practice; then we shall be able to assign any soil by its mechanical analysis to a known type.

The power of a soil to retain moisture and resist moderate drought depends on a predominance of the finer particles and of humus; good wheat land or land that will form sound permanent pasture will contain at least 30 per cent. of silt and clay. The ease with which a soil suffers the rain to percolate depends upon the relatively low proportion of silt and clay rather than on the amount of coarse-grained material; the fine particles pack in among the larger, and the soil is equally resistant to the passage of water, whether the finest material is diffused among coarse sand and gravel, or among the finer grades of sand. The shrinkage of a soil on drying, and its tenacity when dry, are even more dependent on low proportions of coarse sand, humus, and chalk, than on the actual amount of clay and silt which cause the shrinkage. The really difficult soils to work are those containing less than 20 per cent. of sand above 0.1 mm. in diameter.

The table on page 61 will serve to illustrate these points.

Soil No. 1 represents one of the lightest of sands, about the extreme limit of cultivation—a soil, indeed, which had been found unfit for ordinary farming, and had been planted with conifers.

It will be seen that more than 83 per cent. consists

of "sand," nearly all of the coarser kinds, while the clay only amounted to 4.7 per cent., most of which was really ferric oxide. Calcium carbonate is also entirely absent, owing to which the soil accumulates more humus than would be expected from its great aeration, and in the

	1	2	3	4	5	6	7	8
	Coarse Barren Sand.	Light Sandy Loam.	Light Loam.	Light Loam.	Heavy Sandy Loam.	Heavy Loam.	Clay.	Very Stiff Clay.
Fine Gravel . . .	4.1	1.0	3.0	1.2	1.9	1.9	1.3	0.4
Coarse Sand . . .	70.3	49.9	33.8	5.3	3.3	6.2	21.2	0.8
Fine Sand . . .	7.0	16.1	28.0	32.1	36.8	21.4	12.5	6.4
Silt . . .	1.5	11.1	5.6	33.3	21.0	32.5	15.0	18.6
Fine Silt . . .	5.8	5.6	10.8	5.3	14.3	13.8	11.9	13.6
Clay . . .	4.7	9.7	6.6	11.8	13.5	17.6	28.3	42.2
Moisture . . .	2.6	1.2	4.3	1.9	1.4	2.2	1.6	9.5
Loss on ignition . .	3.0	3.8	6.9	4.5	4.5	5.8	7.8	9.1
Calcium Carbonate	0.2	0.1	0.3	2.5	...	0.4
SUBSOILS.								
Fine Gravel . . .	6.5	1.0	4.1	0.3	2.6	1.7	0.7	0.2
Coarse Sand . . .	75.5	50.1	36.8	2.1	2.8	4.3	11.6	0.5
Fine Sand . . .	4.9	15.9	26.1	27.0	35.2	15.8	7.3	6.2
Silt . . .	1.7	12.5	5.4	40.8	19.9	24.0	9.8	15.9
Fine Silt . . .	4.2	5.9	8.4	5.7	16.1	16.7	15.2	10.2
Clay . . .	2.2	8.6	9.5	16.4	16.2	28.7	42.7	48.9
Moisture . . .	1.6	0.9	3.3	3.6	1.2	3.8	2.6	6.3
Loss on ignition . .	2.7	2.7	5.7	2.8	4.1	4.6	8.1	7.3
Calcium Carbonate	0.1	0.1	0.3	0.1	...	0.1

hollows where water lies it often becomes peaty. Such soils are rarely in cultivation, but are left as wastes, carrying a natural vegetation of heather and pine.

Because, however, of their lightness and warmth, they are sometimes valuable for market gardening on a small scale, if they are so situated that large supplies of

farmyard manure or town dung are available; strawberries being a favourite crop.

Soil No. 2 was taken from the Stackyard field of the farm of the Royal Agricultural Society at Woburn, and represents a light sandy loam, early, and extremely easy to work in any weather. Owing to the preponderance of coarse sand, it suffers somewhat from drought and rarely carries heavy crops; and though responding well to manuring, the soil is hungry and does not long retain organic manures. The soil contains enough silt to possess a distinct power of lifting the subsoil water by capillarity, and similar soils containing less coarse sand and rather more fine sand and silt are often among the most valuable, because they combine free working with a capacity to resist drought through capillary action. This soil is more suited to market gardening than to mixed farming, makes poor pastures, grows good barley and turnips, but is too light for wheat and mangolds.

Soil No. 3 is a light sandy loam from one of the most valued of the "red land" potato soils near Dunbar. In the cool climate, with a fair rainfall here prevailing, this forms an excellent arable soil for all crops, specially prized as yielding potatoes which retain their colour and are mealy after boiling.

Soil No. 4 is a typical free working loam from the Thanet sand formation, but rather lighter than usual. It is easy to work, warm and early, stands drought well, and is grateful and fairly retentive of manure. This is a highly valued soil for all ordinary arable cultivation, but is rather too light for wheat and pasture in the south or east of England. No particular fraction of the soil is predominant, but the soil is a fairly uniform mixture of particles of all grades.

It should be noticed that in these first four soils of a sandy type soil and subsoil are of very similar

structure, whereas as soon as the smaller particles predominate on the heavy lands, then the soil is coarser grained than the subsoil.

Soil No. 5 comes from the Hastings Sand in Sussex, and represents a light example of a type of soil which, with a certain amount of variation in the relative proportions of fine sand and silt, covers a considerable area in the high Weald country.

Generally it forms a sticky, heavy working soil, commonly described as a clay, though the sand and silt fractions predominate and no excessive proportion of clay is present. The soil, however, is kept very close by the lack of coarse sand and of any of the still coarser gravel and stones, the absence of carbonate of lime also makes it stickier and more difficult to work. If a good tilth is obtained, as, for instance, a seed bed for roots, and heavy rain follows, these soils are particularly liable to run together and set on drying to a glazed caked surface, very inimical to germination. When well supplied with lime and organic matter, these soils are fertile and carry magnificent crops; but they are rather late and expensive to work, so that they have in great measure been laid down to grass. They carry good grass when well treated, and particularly when dressed with lime and basic slag.

Soil No. 6 is taken from the Broadbalk Wheat Field at Rothamsted: it is a heavy loam, stubborn and intractable to work, which would lie very wet were not the land naturally under-drained by the chalk rock at a depth of ten or twelve feet below. The surface soil also contains a large number of flint stones, not shown in the analysis, and these help to keep the soil more open and assist the drainage. Heavy as it is, the soil is not a true clay; it is the silt and fine sand fractions which predominate, and to these must be attributed the

tendency of the soil to run and dry with a caked surface, if much rain falls after a fine tilth has been attained. In the soil but not the subsoil there is a fair proportion of calcium carbonate, of artificial origin, and this contributes greatly to the workability of the soil, for it has been found unprofitable to retain some of the fields, in which the calcium carbonate is absent, under arable cultivation. Land of this class is still largely under the plough, and is good wheat, mangold, and bean land, but is too heavy for barley or turnips. An occasional bare fallow is desirable to clean the land and bring it into tilth again; it also yields very fair permanent pasture.

Soil No. 7 is situated on the Kimeridge Clay formation in Cambridgeshire; it is heavy land, difficult to cultivate, and when under the plough requires a bare fallow from time to time to restore the tilth. This represents one of the heaviest soils which respond to arable cultivation, which indeed is only practicable because the soil, though containing so high a proportion of clay, also contains a good deal of coarse sand, which keeps it open and helps to render it friable.

Soil No. 8 is a heavy, undrained London Clay, which at the present time is almost pure pasture. At one time it would carry in favourable seasons heavy crops of wheat and beans, but the expense of cultivation and the danger of missing a season have rendered it quite unprofitable to farm under the plough. With the return of higher prices and the development of mechanical cultivation, which enables the farmer to handle large tracts of land in the short periods during which the soil is fit to move, this land may come back again into cultivation. But it requires a considerable expenditure of capital on drainage and liming before much can be made of the soil. It will be noticed that

the soil consists almost wholly of the finer fractions, nearly one-half being "clay"; nor is there any difference between soil and subsoil, except in the humus, which improves the texture of the surface.

The farmer's definition of land as heavy or light is largely conditioned by the prevailing rainfall. A soil that would be regarded as no more than a stiff loam in the South of England would be called a heavy clay in Scotland, with the greater rainfall and smaller evaporation. Again, a soil texture that would be too light and open for wheat or pasture in the east or south of England is well fitted to carry these crops in regions of greater rainfall. Soil is, as it were, a part of the climate, or rather the two together determine the environment to which the crop responds.

Actually in the British Isles the really heavy clays are to be found in the south: on the Oxford, Kimeridge and London Clays the heaviest soils occur. In the districts of higher rainfall not only have the soils been lightened by the washing out of the finest clay particles, but they have been more formed from the primitive crystalline rocks. Colloidal particles are less abundant, and the soils are in consequence more permeable.

CHAPTER III

THE TEXTURE OF THE SOIL

Meaning of Texture and Conditions by which it is affected—Pore Space and Density of Soils—Capacity of the Soil for Water—Surface Tension and Capillarity—Percolation and Drainage—Hygroscopic Moisture.

IN the preceding chapter, the nature of the particles composing the soil has been discussed ; it now remains to consider the manner in which they may be arranged, and the structure that results from the interaction of the soil particles, the water, and such salts as may be dissolved in the water. On these factors depend what the farmer knows as the "texture" of the soil, the degree of resistance it affords to the passage of a plough, etc., the ease or otherwise with which that prime object of cultivation, the preparation of a seed bed, can be attained.

It is clear that as a soil consists of particles there must be between them a certain amount of space which is occupied by air or water ; this is known as the "pore space," and on its amount will largely depend the density of the soil. Taking the simplest theoretical case, a soil made up of equal spheres in contact with one another, it will be found that the pore space is dependent upon the method of packing, but not upon the size of the spheres. If the system of packing shown in A and B, Fig. 3, is adopted, the pore space reaches its




FIG. 3.—Diagram illustrating Pore Space between Spherical Particles.

maximum and amounts to 47.64 per cent. of the whole volume occupied by the soil; this proportion is the same when the soil particles have a smaller diameter, as in B; as long as the spheres are uniform in size, whatever that may be, and are packed as shown in the diagram, the pore space will be at its maximum. The minimum pore space is attained by the packing shown in C and D; it amounts to 25.95 per cent., and is again independent of the size of the particles, provided they are uniform. If the spheres are, however, of very different sizes, so that smaller spheres lie wholly within the spaces between the larger spheres, as in the arrangement shown in E, the pore space may be indefinitely reduced. *Per contra*, if aggregates of particles exist in the soil, containing both pore space between the ultimate particles and between the aggregates which behave as single particles, as in F, the pore space may rise much above the maximum of 49 per cent. A soil *in situ* generally possesses a pore space larger than the proportions indicated above; various causes, such as the stirring due to cultivation, the decay of vegetation, etc., leave definite cavities in the soil: for example, if a hole be dug for any purpose in ordinary cultivated ground and afterwards filled up with its own soil, it is rarely possible to fill the hole completely, especially if a little pressure has been used to trample down each layer.

In ordinary soils the pore space varies from a little over 50 per cent. among the stiff clays, down to 25 or 30 per cent. in the case of coarse sands of uniform texture. The reason for the greater pore space with the finer grained soils lies in the fact that the weight of the small particles of clay is not sufficient to overcome the friction and move the particles into the arrangement giving the minimum pore space. If some small shot are shaken into a graduated measure and the pore space

determined by pouring in a measured volume of water, the indicated minimum will be found ; but if the experiment be repeated with sand which has been sifted to get approximately a uniform size, a higher figure will result. In the one case the particles are too light to exert much force towards the rearrangement of the mass ; in the former case the heavy smooth shot slip straightway into the most compact arrangement, because by it the shot attain their lowest position. In consequence of the pore space, the density of a soil *in situ* will differ very much from that of the materials of which it is composed, nor will all soils possess the same apparent density when dry. Perhaps the best way of ascertaining the apparent density of a soil or soil materials is to get a smooth metal pint pot or like measure, fill it with the material in question with gentle tapping, and then strike off the upper surface smooth with a rule. The weight of the contents divided by the volume gives the apparent density, from which the true volume and the pore space can be calculated, if the true density of the material be known. The following table shows the true and apparent density of the chief soil materials ; as a mean figure for purposes of calculation, 2.65 can be taken as the true density of ordinary soils :—

	True Density.	Apparent Density when dry.
Humus	1.2	.34
Clay	2.5	1
Sand	2.6	1.45
Calcium Carbonate	2.75	...
Hydrated Oxide of Iron	3.4 to 4	...

The following table shows a few determinations made in the laboratory, of the apparent density of various soils in a roughly powdered state and without

the stones, which, being solid, would add to the apparent density of the soil. The results are also recalculated to show the weight of a cubic foot of the soil, and the weight per acre of a layer 9 inches deep :—

	Apparent Density.	Weight per cubic foot.	Lbs. per acre to 9".
Heavy Clay . . .	1.062	66.4	2,150,000
Sandy Clay . . .	1.279	80	2,600,000
Sandy Clay Subsoil . . .	1.18	73.7	2,380,000
Light Loam . . .	1.222	76.4	2,480,000
Light Loam Subsoil . . .	1.144	71.5	2,320,000
Sandy Loam . . .	1.225	76.7	2,490,000
Sandy Peat . . .	0.782	49	1,580,000
Light Sand . . .	1.266	79.2	2,560,000.

The figures given above are not exactly comparable with soils under natural conditions, because of the powdering, the exclusion of stones, etc., but they serve to show that the clay soils usually described as "heavy" are really less dense, and weigh less per cubic foot than some of the lighter soils, whereas pure sands are the densest of all. The farmer's terms of "light" and "heavy" land refer to the draught of the plough, the resistance the soil opposes to being torn asunder, and not to the actual weight of the portion moved; sands which he calls "light" being, as the table shows, heavier per cubic foot than the clays which the farmer calls heavy soils.

This point will be further elucidated by the following table, which shows the weight per cubic foot of the arable soils at Rothamsted and Woburn down to a depth of 3 feet. These results represent the real weights of the soil as obtained by cutting out a block 6 inches square by 9 inches deep, weighing it, and afterwards ascertaining the deduction to be made for water. The Rothamsted soil is a stiff clay with many flints, the

Woburn soil is a loose, coarse-grained sand, containing only a little stone derived from the rock below. It will be seen that, if the stones are excluded, the density increases with the depth, because of the greater consolidation caused by the weight above and to some extent by the washing down of the finest particles, but the increase does not continue much below the depth of 3 feet, the limit of these measurements:—

		Weight per cub. foot.	Per cent. of Stones.	Weight per acre.
		Lbs.		Lbs.
Rothamsted Arable Broadbalk	0" to 9"	95.4	16.8	3,116,000
	9" " 18"	93.0	12.0	3,037,000
	18" " 27"	92.0	7.1	3,004,000
	27" " 36"	92.2	7.5	3,012,000
Woburn Arable	0" " 9"	96.6	2.96	3,157,000
	9" " 18"	103.8	5.95	3,382,000
	18" " 27"	106.2	4.92	3,462,000
	27" " 36"	106.9	7.83	3,501,000

From the data thus obtained as to density and pore space, together with a mechanical analysis to show the proportion of particles of various sizes, it is possible to calculate for any given soil both the number of soil particles and the area of the surface they expose, on the assumption that the particles are spherical. Approximately with grains 1 mm. in diameter, there would be 700 grains in 1 gram of the soil, and the number of grains to the gram will vary inversely as the third power of the diameter, *i.e.*, if the diameter be divided by 10 and become 0.1 mm., there will then be 700,000 grains to the gram. The surface possessed by all the soil grains can be similarly deduced by calculation, and will be found to vary inversely as the diameter of the individual grains; a sphere 1 inch in diameter will have only half the surface of the eight spheres of

half an inch in diameter which possess the same volume. Hence it follows that the surface of an ordinary soil must be extremely extensive, and since many of the properties of the soil are dependent upon the surface it becomes important to arrive at some measure of this quantity. By calculation only a very rough idea of its extent can be formed, both because every departure of the soil grains from the spherical form will increase the surface without affecting the weight, and also because the mechanical analysis of a soil gives only a generalised statement of the distribution of soil particles of various sizes in the soil. But the surface of the soil grains in the case of a sandy soil where the grains are all free, may be calculated from the observed rates of flow of fluids like air or water through a measured portion of the sand; and by using this method King has computed the surface of the constituent particles of various types of soil with the results set out below :—

	Pore Space, per cent.	Area of Surface in square feet, per cubic foot of Soil.
Finest Clay . . .	52.9	173,700
Fine Clay Soil . . .	48	110,500
Loamy Clay Soil . . .	49.2	70,500
Loam . . .	44.1	46,500
Sandy Loam . . .	38.8	36,900
Sandy Soil . . .	32.5	11,000

As a rough figure to remember, the surface of the particles in one cubic foot of an ordinary light loam may be taken as about an acre; this will increase as the soil approaches more and more to clay, and diminish as the soil becomes increasingly sandy. The extent of surface exposed by the soil particles is important because it is their active part; other conditions

being equal, the amount dissolved from a solid body in a given time by any solvent will be proportional to the surface exposed.

Again, the water in a soil usually exists as a film, coating the surface of the soil particles, and the amount of water that can be held under particular conditions becomes a function of the extent of surface; even the power of a soil to remove certain substances from solution is likewise dependent on the surface.

Capacity of the Soil for Water.

So far, the structure of the soil in a dry state has only been considered, it is now necessary to consider its behaviour when fully saturated with water, before passing on to the more usual state when the soil contains both air and water.

The amount of water which a soil will hold when completely saturated will depend upon the pore space, will, in fact, be the pore space together with whatever water the material of the particles can imbibe without causing any swelling. Perhaps the best method for determining the water capacity of a soil is one devised by Hilgard. A small cylindrical brass box is constructed, 1 cm. deep and 6 cm. in diameter. The bottom is a sheet of perforated brass, and the whole is supported on three legs; the capacity of the box is about 30 c.c. The exact capacity is determined by waxing up the holes, weighing, filling with water, and reweighing. A circle of thin filter paper cut to fit the box is laid inside and wetted, any superfluous water that comes through being wiped away. The box is then weighed, carefully filled with fine earth, and gently tapped to settle the soil down; finally, the surface is struck off level with a straight-edge. The box is now weighed again to find the quantity of dry soil taken, and placed in a

dish of distilled water, so that the water stands about 1 mm. above the lower surface of the soil inside the box; the dish is then covered over to prevent evaporation. The water rises in the soil, displacing the air, and in about an hour's time the soil will have absorbed all the water possible. The box is lifted above the water a little, allowed a few minutes to drain, the excess of water clinging to the under-surface is wiped away with a clean cloth or filter paper, and the whole is then weighed. A previous determination of the moisture present in the "air-dry fine earth" must also be made, to provide all the data necessary for the calculation of the water contained in the saturated soil. This calculation may be made in three ways: either the proportion the water in the saturated soil bears to the dry soil, or the proportion of water in the wet soil may be estimated, or again, the proportion by volume that is occupied by water and soil respectively may be calculated. The figures thus obtained will vary very considerably, because the less dense the soils, because of the clay and humus they contain, the more water they will absorb; thus the proportion which the water absorbed bears to the weight of the dry soil becomes exaggerated in their case. Perhaps the soundest picture of the state of affairs is attained by considering the volume that is occupied by the water in the soil, and expressing it either as a percentage by volume, or as lbs. or inches of water per cubic foot of wet soil. The following figures (p. 75) show the results obtained for four distinctive soils, calculated out in the different ways described above.

Under natural conditions a soil is rarely saturated to the extent indicated in the table; as the rain water enters from above, the surface of the soil is wetted first and the air within the soil finds a diffi-

culty in escaping, so that even after long-continued rain the pore space does not become entirely filled with water.

	MAXIMUM.			MINIMUM.			Per cent. of Water when Air dry.
	Water absorbed per 100 of Dry Soil.	Per cent. of Water in Saturated Soil by Weight.	Per cent. of Water in Saturated Soil by Volume.	Per 100 Dry Soil.	Per cent. by Weight.	Per cent. by Volume.	
Coarse Sandy Soil	45	31	50.5	18	15.3	22.2	0.8
Light Loam. .	50.5	33.5	55.8	29.2	22.6	35.4	2.9
Stiff Clay . .	98.6	49.6	67.6	56.4	36.1	45.6	6.9
Sandy Peat . .	155	60.8	63.2	116	53.7	52.8	8.3

The following table shows the water contained in a few field soils sampled a day or two after the cessation of long-continued rain, and calculated as percentages of the wet soil by weight:—

	Per cent. of Water in Wet Soil.
Sand at Water Level	18.4
Rothamsted Wheat Land, unmanured	23.0
" " manured with artificials	24.7
" " manured with dung for 26 years	37.6
Light Loam above Chalk	20.3

Hellriegel has shown that the optimum proportion of water in the soil for the growth of the plant is 40 to 50 per cent. of the maximum required for saturation.

Flow of Water through Soils.

The freedom with which water will move through soils under the action of gravity or other force will depend not only on the pore space, but upon the

mean size of the channels formed between the soil grains. King made some experiments with sands graded by sieves and formed into columns 14 inches long and 1 square foot in section, above which the water was maintained at a head of 2 inches. He obtained the following results expressed in inches of water passing in twenty-four hours; the second column gives the number of meshes to the inch of the sieves which respectively passed and retained the sand:—

Medium.	Sieves.	Inches.
Sand.	40 to 60	301
"	60 " 80	160
"	80 " 100	73.2
"	100	39.7
Clay Loam	---	1.6
Black Marsh Soil . .	---	.7

It will be noticed that there is a great diminution in the rate of flow as soon as a soil containing small clay particles is introduced; of course, one of the characteristic properties of clay is that it will not allow any flow of water through it when it has been puddled. In the puddled condition, the particles constituting the clay are no longer aggregated, and their colloid "gel" coating absorbs water and swells, whereby pore spaces between them must become extremely small. Not only is the flow diminished by the increase of friction in the narrow channels, but in the case of clay their dimensions have become so small that probably the contained water is wholly within the range of the molecular forces to be described later; it is thus prevented from flowing at all, and only moves by diffusion. If we assume for clay particles a mean diameter of 0.0002 mm., and a structure similar to A in Fig. 3, p. 67, it is easy to show that no molecule in the

space between the spheres can be further than about $\frac{1}{8}$ of the diameter of a sphere, or 0.00004 mm. from one or other surface, while the range of molecular forces as calculated by Quincke extends to about 0.00005 mm. from the surface. Spring has indeed shown that infiltration of water is impossible through clays or loams unless they are first allowed to expand by taking up water.

Surface Tension and Capillarity.

The existence of attraction between the molecules causes the free surface of any liquid to become a sort of stretched elastic film, in tension itself, and exerting a certain pressure inwards when free. The molecules within the liquid are equally attracted in all directions by the surrounding molecules, and are therefore in equilibrium; the molecules on the surface, having nothing on one side, are only attracted inwards, and so, as a whole, exert a pressure on the liquid similar to that which would be caused by a stretched elastic skin over the liquid.

The existence of this force of "surface tension," as it is called, may be demonstrated by many simple experiments, *e.g.*, by the familiar fact that a clean needle will float when placed carefully on the surface of water; or, by the fact that any portion of a liquid which is so small that the force of gravity on it is not large compared to the molecular forces, immediately assumes the spherical shape. Of all figures, a sphere has the smallest surface in proportion to its contents, *i.e.*, the stretched film on the surface of a drop of liquid shrinks as far as it can until the liquid is packed into the smallest possible compass, into the form of a sphere.

When a liquid and a solid are in contact, the form of the surface and the resulting pressure or tension depend on whether the liquid "wets" the solid or not. For

example, if a series of very fine or "capillary" glass tubes are dipped into water and mercury respectively, the water will rise up the tubes in inverse proportion to their diameters, the mercury, which does not wet the glass, will be correspondingly depressed.

The water surfaces *a*, *b*, *c* (Fig. 4) are convex to




FIG. 4.—Capillary Rise and Depression of Liquids in Glass Tubes.

the water, and become more convex the narrower the tube is; the pressure below the convex surface must be less than atmospheric, or the water would not stand higher within than without the tube; further, the pressure beneath *a*, the most convex and therefore most stretched surface film, is lower than the pressure beneath *b*, and still lower than that beneath *c*. *Per contra*. the mercury surfaces are convex outwards, and





FIG. 5.—Photograph illustrating Liquid Film round Soil Particles.

[To face page 78.]



exert pressure on the liquid beneath, depressing it below the general surface of the liquid in proportion to the degree of convexity. These instances will help us to realise that the surface of a liquid may exert either a pull or a pressure on the liquid within, according to the curvature of the surface, and the greater the curvature the greater will be the force exerted. It is this tension of the surface film which causes movements of water in soil, other than those due to gravity; for example, if a flowerpot stands in a shallow dish of water, the whole of the soil within the pot is kept moist; or if water is poured on to dry soil, it is seen to work outwards through the soil, the water advancing from particle to particle as it wets them, just in the same manner as it rises up the capillary tubes. When a soil is saturated, the whole pore space is filled with water; if this soil be allowed to drain, some of the water is pulled away by gravity, but much remains clinging round the particles in the stretched film condition, the tension in the film balancing the pull due to gravity. Perhaps the best illustration of the state of affairs in a wet but drained soil may be obtained by linking a series of toy balls together, as shown in the photograph (Fig. 5), and then dipping the whole into oil. When the oil has ceased to drip it will be seen that every ball is covered by a thin film of oil, and that between the balls there is a layer of oil much thicker in the lower than in the upper layers. The whole surface film is equally stretched, but the stretching in the upper layers is largely due to the pull from the oil below, while in the lowest layer of all the whole tension exerted by the stretched film is devoted to holding up its own thick film of oil. If oil be taken away at any point, the curvature of the film, and therefore the tension of the surface in that region, is increased: a readjust-

ment then takes place till the stretched film regains the same tension everywhere, which is effected by a motion of the oil to the place where the tension has been increased. If the withdrawal of the oil be continued, the film round the balls becomes thinner and thinner; the more it is stretched, the more closely it clings to the surface, so that the removal becomes progressively more difficult; at last the film becomes so much stretched that it ruptures and reunites again over a smaller surface, hence with a diminished tension. The rupture naturally takes place where the film is thinnest, on the top layer of balls, which becomes more or less "dry" while the lower balls are still surrounded by their film.

Just in a similar way water will always move in a soil from a wet to a dryer place, till the film surrounding the particles is equally stretched throughout.

For example, if A, B, C (Fig. 6) represent three soil particles, of which A and B are surrounded by a thin,




FIG. 6.—Diagram illustrating Liquid Film round Soil Particles.

and C by a thicker, film of water: when the spheres are in contact the water will fill up part of the angle between the spheres, as shown in the diagram. But the water surface at *a* is more curved than at *b*, *i.e.*, it corresponds to the surface at *a* in the fine capillary

tube (Fig. 4) as compared with the surface at b in the wider tube. But the diminution of pressure caused by a is greater than that caused by b , as shown by the greater height to which water is raised in the tube; hence in the same way the pressure inside the liquid at a (Fig. 6) will be lower than that at b , and there will be a flow of water from b to a , until the curvatures and corresponding surface tensions are equalised.

In a wet soil, then, surface tension is a force tending on the one hand to retain a certain amount of water round the particles, and on the other to equalise the distribution of water, by causing movement towards any point where the surface tension has been increased. For example, if the water in a soil is in equilibrium and evaporation begins at the surface, the film there is made thinner, and the curvature increased in the angles between the soil particles: hence the pull exerted by the film is increased, and water is lifted from below against gravity. *Per contra*, if rain fall on such a soil the films round the upper particles are thickened, their tension is lowered, and the pull of the film below now acts with gravity in drawing the water down into the soil.

Percolation.

The state of affairs illustrated by the model of balls dipped in oil is seen in the case of a soil which has been thoroughly saturated so that all the pore space is occupied by water, and then allowed to drain until the remaining water is held in the soil by surface tension only.

In the upper layers the film will be stretched to the utmost, or even broken by the pull of the water below; in the lower layers the film will be wholly engaged in holding the water immediately in contact with the particles of the layer: these layers may be saturated,

while the upper layers hold an amount dependent on their distance from the saturated zone, and on the extent of surface exposed by the particles.

The accompanying diagram (Fig. 7) expresses the results of an experiment of King's, where columns of sand and soil, 8 feet and 7 feet long respectively, were saturated and then allowed to drain till they parted with no further water, which required a period of six days in the case of the soil columns, and of more than two years for the sand. The tubes were then cut up, and the proportion of water in the sand or soil in successive 3-inch lengths of the tubes was determined.

It will be seen that the sands retain very little water by surface tension in the upper layers, whereas the clay loam, with the enormous area its particles expose, holds practically the same proportion throughout.

If we also consider the following table, showing the time taken by the same sands and soils to part with their water, the difference of the texture of the soils will be even more evident:—

	INCHES OF WATER LOST IN				
	30 min.	31 to 60 min.	24 hrs. (?)	2 to 11 days.	12 to 21 days.
No. 20 Sand .	10.25	4.68
" 60 " .	5.67	4.52
" 100 " .	1.21	.84
Sandy Loam	2.64	5.07	.9
Clay Loam	1.96	2.11	.49

The downward movement of rain water through soils is known as "percolation," and is distinguished from "flow" by the fact that the water is supposed to have free surfaces, so that surface tension comes into play




FIG. 7.—Water Content of Columns of wetted but thoroughly drained Sand and Soil.

It takes place under the action of gravity through the pore space proper, and also through the cracks, the worm tracks, the passages left by decayed roots, and other adventitious openings in the soil. The percolation proceeds until the zone is reached where the pore space is completely filled; this is known as the "water table," and is the level at which water stands in the wells. Above the water table the soil will be more or less in the state represented in the diagram showing sands and soils in which percolation has ceased; though there will be most probably a more irregular distribution, with zones which contain an excess of water travelling downwards with greater or less rapidity according to the texture of the soil. It is these temporarily saturated zones which cause the ordinary tile drains to run, although situated many feet above the permanent water table. A soil in which percolation has ceased, though it may still contain much water, will not part with it to a drain; the water cannot break away from the elastic film and run off down the drain, unless it be present in such an excess that the surface tension is insufficient to hold it against gravity. But in a clay soil, percolation is so slow that the upper few feet of soil may become saturated by the winter rains and remain so for months, if percolation has to proceed all the way down to the water table; by the introduction of drains, the percolating column is shortened to the distance between the surface and the drain. In a coarse-grained sandy soil percolation is very rapid, the land dries quickly after rain, and retains a minimum of water by surface tension; in fine-grained soils, which are, however, not too fine for percolation, the excess of rain will be removed rapidly enough to keep the soil below the saturated condition, yet enough water may be retained

to supply the needs of the crop between the intervals of rain.

While the flow of water from a field-drain may be taken as a rough measure of the amount of percolation going on at any given time for that soil, the movement may be followed more closely by means of a lysimeter or drain-gauge. As a rule, the records of these instruments are vitiated by the disturbance undergone by the soil in filling them; but the drain-gauges at Rothamsted were constructed by building cemented walls round blocks of earth *in situ*, and then gradually introducing a perforated iron plate below to carry the soil. The following diagram (Fig. 8) shows the mean monthly records of rainfall and percolation through a depth of 20 inches and 60 inches respectively, over a period of thirty-five years.

It will be seen that of the total rainfall a little less than one-half percolates through 60 inches of the Rothamsted soil; it should be remembered, however, that the surface of these gauges is kept free from weed or any growth. The total drainage through 20 inches of soil is practically the same as that through 60 inches, but rather a greater proportion of the rainfall comes through the 60-inch gauge in the winter and through the 20-inch gauge in the summer. In the winter months the percolation reaches as much as 80 per cent. of the rainfall, in August little more than 20 per cent. of the rainfall finds its way through the layer of soil. When the ground has become dried to any depth in the summer, percolation may be much hindered by the air within the soil and the want of a continuous film of wetted surfaces to lead the water down by surface tension. The top layer of soil becomes thoroughly wetted and will not allow the air below to escape; only after some time are local displacements of




FIG. 8.—Diagram showing Rainfall and Percolation at Rothamsted, 1870-1905.

The two heavy curves show rainfall and percolation through the 60" gauges in inches; the dotted and the lighter continuous curves show the percolation through the 20" and 60" gauges as percentages of this rainfall.

(Reproduced from the "Journal of Agricultural Science" by permission of the Cambridge University Press.)

the air set up, which enable the water above to make connection with the wetted subsoil below, so that percolation can begin. For this reason summer rains falling in a season of drought are often noticed to be of little benefit to the crop, because they are retained near the surface until wholly evaporated, instead of increasing the stock of moisture at the lower levels where the roots of the plant are then operative in obtaining water.

Minimum Capacity of Soil for Water.

The amount of water retained in a soil by surface tension alone, when percolation has removed as much as possible, is rather an important factor to determine, as upon it depends to some extent the power of the soil to resist drought by retaining water for the crop between intervals of rain. If short columns of sand and soil which have been saturated and then allowed to drain away into a state of equilibrium are considered, it is clear that very different proportions of water are retained by the various soils. Suppose, however, the column be of such a length that at some level the upper film of water cannot be further stretched, but the particles cease to be wet; the layer immediately below this dry soil contains the minimum amount of water consistent with a continuous film at all. Soil in this condition may be regarded as at the minimum of saturation; it will part with no more water by drainage, and will become drier only by evaporation. In order to obtain such a sample of soil for determination of its water content, much trouble would be necessary, and a long time must elapse before equilibrium could be obtained in the long tube filled with wet soil. Practically, however, the same result can be reached with the apparatus previously described

for estimating the maximum capacity of the soil for water, by constantly bringing the thin layer of soil there used into contact with dry soil, until the previously saturated soil no longer parts with water to the new soil.

After the determination of maximum water capacity, as previously described (p. 73), a little more fine earth, which has been standing for some time over water in a closed space so that it has acquired all the hygroscopic moisture it can, is shaken lightly over the surface of the wet soil in the box to the depth of $\frac{1}{4}$ inch or so. It rapidly becomes wet, as will be evident by a change in colour, whereupon it is struck off by drawing a fine tightly stretched wire across the top of the box and shaking the loosened layer off. More fine earth is then shaken on and struck off as before when wetted, the operation being repeated again and again, until a thin dry layer remains on the surface for half an hour or so without showing by change of colour any absorption of water. During this wait the box should be in a closed chamber over water. With fine-grained clays and loams the process does not take long, with a coarse sand the water moves slowly into the dry layer, and it is difficult to hit off the exact end-point, when the soil particles are still surrounded by water but the surface tension is too great to allow this water to pass into dry soil. Finally, the box and its contents are weighed, dried in the oven, and reweighed. The second weighing when dry is necessary, because the box will be found to hold more dry soil than was originally filled into it; a certain amount of consolidation has taken place through the addition of the dry earth and the subsequent striking off when wet. The numbers in the columns headed Minimum in the table on p. 75 were obtained in this way: they show that though the maximum

capacity for water, or pore space, may not vary very greatly for different soils, there is a much wider and more important divergence between the amounts of water they will retain by surface tension alone, this latter being the important factor in judging of the power of the soil to retain a reserve of moisture for crops.

It will, however, be found that this determination, like that of the maximum water capacity of the soil (p. 73) will vary somewhat with the same soil according to the condition in which it is left after sampling and preparation for analysis. It is practically impossible to reproduce in the laboratory the state in which the soil existed *in situ* or to bring into the laboratory an unchanged sample of the soil in the field. In consequence the conclusions that can be drawn from determinations of maximum and minimum water capacity of the soil are limited and of little service in practice. Of more value is a determination of the optimum working condition of a soil, a conception introduced by F. K. Cameron. It represents that condition of the soil in which it is neither too dry nor too wet to be worked, when under the operations of cultivation it can be readily broken down into fine aggregates without becoming puddled. It is the condition that must be attained on a strong soil before it can be made into a good seed bed.

Several pounds of the dry soil are placed in a large basin and slowly wetted with a fine spray of distilled water, care being taken with a clay soil not to over wet any portion. The soil is carefully worked about with the hands to equalise the wetting, and it will be found that a point is eventually reached when the soil is distinctly moist, but yet can be broken down to a crumb without getting into a pasty condition. With a heavy soil time must be given as this condition is neared, the

soil being left to stand for a time with a cover over the basin in order to let the water diffuse thoroughly. If the moisture is increased beyond the optimum point the soil becomes obviously wet and gets sticky and puddled as it is worked. The experimenter must use his judgment as to when the right point has been reached, whereupon a sample of the soil is taken, weighed and dried in order to ascertain its water content. With a little practice successive determinations will agree within one or two per cent. The mean of several such determinations may be taken as the optimum water content.

Variations in Surface Tension.

The surface tension of water is very high, but it is easily raised or lowered by the presence of small amounts of material in solution. The effect of altering the surface tension of a film at any point is to cause motion, as is seen in the well-known experiment of covering a plate with a thin film of coloured water and dropping a little alcohol into the middle of the film. The alcohol immediately weakens the surface tension of the film in the middle to such an extent that all the liquid runs to the outer edge and leaves the plate bare in the middle. Most of the salts which are used as artificial manures and are soluble in water increase the surface tension of the soil water, hence an application of salt or nitrate of soda may, by increasing the tension of the surface film, lift more water from the subsoil and maintain the top layer of soil in a moister condition. *Per contra*, solutions of organic matter, particularly of the many organic substances used as manure which have a little oil in them, extracts of dung, etc., have a surface tension below that of water. To this fact may be attributed the "burning" of soils which is sometimes

seen when organic manures are applied late in the season and dry hot weather succeeds; the soil water at the top in contact with the manure has a lower surface tension and consequently less lifting power for the subsoil water; hence any shallow rooted crop is deprived of some of the subsoil water which would have otherwise been lifted to it. A rise of temperature diminishes the surface tension of water, and therefore lessens the sustaining power of the film; as it also lessens the viscosity of water, it will often cause percolation to begin afresh from soil that had apparently ceased to yield any more drainage. This effect may sometimes be seen in variations in the flow of land drains or in the level of water in shallow wells. The following table shows the comparative surface tension of water and various solutions:—

Nature of Solution.	Density.	Surface Tension.
		Dynes per sq. cm.
Water	1.0	7.532
Common Salt	1.1	7.911
Kainit	1.1	7.9
Nitrate of Soda	1.1	7.73
Dung	1.0013	7.464
Superphosphate	1.0104	7.414
Soil Extract	1.0	7.244
Garden Soil Extract	1.0	7.089

Cohesion caused by Surface Tension.

In certain cases the stretched film surrounding soil particles will give them an apparent cohesion by enclosing them and drawing them together. A handful of wet sand can be moulded into shape, but falls in pieces as soon as it is dry: just as in a camel-hair pencil the bristles, which stand apart when dry or wholly immersed in water, are drawn together to a

point if the brush be dipped in water and withdrawn. Or again, a flat sandy beach from which a smooth sea is receding will often show above tide-mark one stretch of sand quite dry and loose, in which the feet sink deeply, and another very soft stretch immediately left by the tide where the sand grains are completely surrounded by water. Between the two is a stretch of sand of the same character, but firm to walk upon; this is partly wet, and there is enough water to form a film round the grains and hold them in position with a certain amount of force. That this sand is really just as loosely arranged as the softer tracts that are either wetter or drier, may be seen by the fact that it will easily pack more closely together under repeated gentle pressure with the foot. The shrinkage of soils, especially of clays, as they dry, may be attributed in part to the surface tension of the films surrounding the groups of soil particles; as the water content is lessened the films exert more force in their effort to contract, and drag some of the particles closer together, especially the very small particles whose weight is trivial compared to the forces exerted by the film. In part also we must reckon the swelling of the "gel" films as they imbibe water. Clay shrinks more than other soils because of the larger quantity of "gel" it contains and the greater number of particles, their small size, and the higher proportion of pore space into which motion can take place. The tenacity of wet clay is due to the number of water films that have to be ruptured; the vastly greater cohesion of dry clay probably to the fact that many of the particles have been dragged within the range of one another's molecular forces. There is a stage in the drying of clay when it will fall to pieces when worked; probably this represents the stage analogous to the partly wet sand, when cohesion is due to the surface

films only. The clay is neither so wet that the particles just slip over one another when pressure is applied—the pasty condition; nor have they been drawn so closely together as to cohere without the aid of any water. A piece of clay swells again when wetted because the “gels” can imbibe water and expand.

Hygroscopic Moisture.

If the withdrawal of water from a soil by evaporation be continued, a point is at last reached when the soil becomes air-dry: it still retains some water, which will vary in amount with the degree of humidity of the atmosphere and the temperature. This film of hygroscopic moisture can be produced by condensation alone, when perfectly dry soil is placed in an atmosphere containing water vapour: the surface of materials like glass, sand, etc., has sufficient attraction for water to condense it from a state of vapour. The amount of water retained or absorbed will in fact vary with the tension of water vapour in the atmosphere with which the soil is in contact until a state of equilibrium is attained.

The hygroscopic moisture, however, retained by soil is not simply determined by the surface, as it would be if the material were sand or powdered glass. The soil colloids exert a considerable effect in retaining these last traces of water and in absorbing them from the moist atmosphere.

If a layer of powdered glass or sand in a moist condition is set to evaporate in a dry atmosphere and the rate at which the water is lost is determined, it will be found that while the rate falls off as the material dries, the results are such as might be expected from the extent of the evaporating surface of the particles and the rate of diffusion of water vapour out of the

loose mass. But soils give a very different set of measurements, the rate of evaporation slowing down much more rapidly as the water content of the soil is reduced. If the soil is first ignited, thus destroying the colloids, it then behaves like sand or glass. The soil colloids, therefore, may be regarded as exercising a specific attraction for water, weak as regards a large quantity of water, but becoming stronger and stronger as the proportion of water in the "gel" is reduced.

If the rate of evaporation of water from a soil is plotted, the curve is a smooth one, showing no breaks or discontinuities which would indicate the removal at that point of all the water in a particular state. The points determined, the maximum, minimum or optimum water content or the hygroscopic moisture, do not stand for portions of the soil water that are held in a different fashion, but merely conditions of equilibrium between the moist soil and the external system with which it was in contact.

The roots of plants, for example, have a certain attractive power for water; as long as this is greater than the soil's the roots will continue to draw water from the soil. But as the amount of water in the soil is reduced, there comes a point when the attraction of the soil balances that of the root, the roots cease to draw any more water from the soil and the plant begins to wilt. The proportion of water then held has been called the wilting coefficient of the soil. But again, it represents an equilibrium point, and not a change of condition, when the free water has been removed and only bound or combined water remains.

All the same, only the water in the soil in excess of the amount indicated by the wilting coefficient is available for the crop. Sachs was the first to show by experiments in pots that tobacco plants will begin

to wilt before the soil has parted with all its moisture. When wilting began with a sandy soil the sand in the pot still contained 1.5 per cent. of water, with a clay soil 8 per cent. of water; with a mixture of sand and humus there was as much as 12.3 per cent. of water retained by the soil. Heinrich has also shown that wilting begins before the water content of the soil has been reduced to the hygroscopic water limit, as the following figures demonstrate—

	WATER PER 100 OF DRY SOIL.	
	When Plants Wilt.	Hygroscopic Water.
Coarse Sand . . .	1.5	1.15
Sandy Garden Soil . .	4.6	3
Fine Sand, with Humus .	6.2	3.98
Sandy Loam . . .	7.8	5.74
Chalky Loam . . .	9.8	5.2
Peat	49.7	42.3

King has made some observations of the amount of water still present in soils in the field which had become so dry that growth was at a standstill and the plants were wilting.

Depth.	Nature of Soil.	Per cent. of Water under Clover.	Under Maize.
0" to 6"	Clay Loam	8.4	7
6" " 12"		8.5	7.8
12" " 18"	Reddish Clay	12.4	11.6
18" " 24"		13.3	12
24" " 30"	Sandy Clay	13.5	10.8
40" " 43"	Sand	9.5	4.2

Under these conditions all the soils were about equally dry, so far as any power to part with their water went; if the estimates made previously of the area of surface of the particles constituting various kinds

of soil be combined with these percentages to calculate the thickness of film of the water on that surface, it will be found that on all soils the film possesses approximately the same thickness, about 0.00003 inch.

Because of the quantity of water which some soils will retain rather than give up to the plant, it is possible that such soils may have less available water for the plant than a much coarser grained soil which starts with a lower initial amount of water. For example, the clay and sand in the table, p. 95, contain when saturated about 26 per cent. and 18 per cent. of water respectively; as the crop can reduce this to 12 per cent. in one case, and 4.2 per cent. in the other, both sand and clay yield about the same amount of water to the crop.

A good example of the fact that only the water in the soil which is in excess of the moisture held at the wilting point is available for the crop, is seen in F. J. Alway's studies of soil moisture conditions in the "Great Plains" region of north-western America. There the rainfall is only from 12 to 15 inches annually, and falls chiefly during the summer months; because of its insufficiency for the production of continuous crops, it is customary to take a bare fallow one season in three in order to accumulate the rainfall for the benefit of the two succeeding grain crops.

The table shows the water content of the soil down to the depth of 6 feet on two fields near Indian Head, Saskatchewan, taken at the end of July 1904, field B having been fallowed, and C having carried a crop of oats which had shown the effects of drought. Figures are given for the total water in the soil as sampled, the hygroscopic moisture as determined in the laboratory, and the difference, which Alway termed the free water:—

Foot Section.	B, AFTER FALLOW. WATER.			C, AFTER OATS. WATER.		
	Total.	Hygro- scopic.	Free.	Total.	Hygro- scopic.	Free.
First . .	29.4	12.0	17.4	20.0	12.7	7.3
Second . .	14.9	3.9	11.0	22.4	13.2	9.2
Third . .	16.4	4.7	11.7	21.6	13.5	8.1
Fourth . .	17.4	5.5	11.9	16.1	4.6	11.5
Fifth . .	21.8	7.6	14.2	15.1	4.2	10.9
Sixth . .	19.6	8.0	11.6	15.9	5.9	10.0
Mean .	19.9	...	12.9	18.5	...	9.5


In each field the upper layer of soil possesses a higher capacity for retaining hygroscopic moisture than does the lower layer, but in field C this upper layer is thicker than in field B. It will be seen from the table that as regards total water there is no great difference between the two fields, but when the hygroscopic moisture is deducted, B contains 3.4 per cent. more water available for the plant. This difference was manifested in the following season in the yield, which was only 2160 lbs. of grain and straw on C and 9200 lbs. on B. Had the really free water been determined, that which is in excess of the amount held by the soil when wilting sets in, these differences would have been even more pronounced, as is evident from the fact that the moisture in the soil at the wilting point is greater than the hygroscopic moisture but is in proportion to it. A relationship has been established between the wilting coefficient and the hygroscopic moisture; as both are points on the same curve, of which the determining factors are the surface of the particles and the amount of the colloids, their connection is intelligible enough.

Though the hygroscopic moisture gathered by the surface soil in the cooler and damper periods of the

night cannot be passed on to the subsoil and given up to the roots, yet by its evaporation the next day it may help to keep the temperature of the soil down, and so indirectly diminish the loss of water to the soil. Of course in certain conditions of air and soil temperature there is condensation upon the soil of visible water which can be available to the crops; for example, in some months drain-gauges yield more water than the rainfall, though a certain amount of loss by evaporation must also have taken place. This usually happens in the early spring, and can be set down to the condensation of dews by the thoroughly chilled ground from a warm and moist atmosphere. Warrington has suggested that the persistent wetness of the soil in February must be attributed to this cause. In a coarse-grained soil mostly filled with air, the cooling of the surface that comes by radiation at night may result in an upward distillation of water from the wetter and warmer subsoil. Hilgard has suggested this explanation to account for the capacity of some Californian soils to maintain a crop during a rainless winter, when the soil itself shows only 3 per cent. or so of water.

A. Mitscherlich has made a number of determinations of the heat that is evolved on moistening dry soil (*benetzungs-warme*), due to the condensation of the hygroscopic water on the surface of the soil particles, and to the imbibition of water by the soil colloids, which is accompanied by a contraction of the total volume and a consequent evolution of heat. The figure thus obtained is of some significance in judging of the physical properties of a soil, since it provides a measure of the effective surface of all the particles composing the soil if we regard a colloid as essentially a matter of surface. Mitscherlich obtained results of the following order, in calories evolved per gram of

soil—sand 0.01, calcium carbonate 0.38, sandy soil 0.79, sandy loam 2.37, strong clay 14.98, peat 22.66. Probably the results are parallel to those obtained by other methods which measure something dependent upon surface or upon the colloids, as, for example, the hygroscopic moisture. In any case the determination is by no means an easy one to make, and no sufficient number of results have been obtained with soils of known behaviour in the field to enable one to form a judgment of the value of the method.



CHAPTER IV

TILLAGE AND THE MOVEMENTS OF SOIL WATER

Water required for the Growth of Crops—The Effect of Drainage—Effects of Autumn and Spring Cultivation, Hoeing and Mulching, Rolling, upon the Water Content of the Soil—The Drying Effect of Crops—Bare Fallows—Dry Farming—Effect of Dung on the Retention of Water by the Soil.

THE amount of water transpired by various plants during their growth has been investigated by Lawes and Gilbert at Rothamsted, by Hellriegel in Germany, and Wollny in Munich, and by King in America. The general principle upon which these observers have worked, has been to grow the plants in pots and measure the amount of water consumed during growth, care being taken to eliminate or allow for losses by evaporation from the bare ground, and also to render the conditions of the plant's life as similar to those of the open field as possible. Finally, the plant is washed free of soil, dried, and weighed, so that a ratio is obtained between the dry matter produced and the water consumed during growth.

Some of the numbers obtained are given in the table below: it will be seen that the same plant gives very different results with the different observers.

	Lawn and Gilbert.	Hellriegel.	Wollny.	King.
Wheat . . .	225	359
Barley . . .	262	310	393	774
Oats	402	557	665
Red Clover . .	249	330	453	...
Peas . . .	235	292	477	447

The divergencies in these results are intelligible, if we consider that the "transpiration" process by which the water is lost, and the "assimilation" process by which the plant gets heavier, have no necessary connection, though both become active under the same stimuli of light and warmth. Some leaves transpire rapidly as a means of maintaining a low temperature whilst absorbing large amounts of radiant energy from the sun; other plants which have to resist drought reduce the transpiration by a thickened cuticle, or by a more concentrated cell sap. Dr H. Brown has shown that of the radiant energy falling upon a sunflower leaf on a bright August noonday, about 95 per cent. was consumed in evaporating the transpiration water; of the energy falling upon the same leaf in bright diffuse daylight, only 28 per cent. was used up in evaporation. Comparing in these two cases the water transpired with the carbohydrate produced (and this will be about $\frac{1}{10}$ of the total dry matter) we find in the sunlight the ratio was 347 to 1, in the diffuse daylight 234 to 1. Further investigations are desirable; but, taking the whole group of observations, we shall be justified in assuming that our ordinary field crops transpire about 300 lbs. of water for each lb. of dry matter produced. It now remains to translate this approximate figure into tons of water per acre required to grow the ordinary crops. The following table shows the weight at harvest of a

fair yield of the crop in question, the percentage of water contained in the crop, the weight of dry matter produced per acre, then the water transpired as deduced from the dry matter produced, and in the last column this same amount of transpired water recalculated as inches of rain.

Crop.	Weight at Harvest.	Per cent. of Water.	Weight of Dry Matter at Harvest.	Calculated Water transpired during Growth.	
	Tons per acre.		Tons per acre.	Tons per acre.	Inches of Rain.
Wheat . .	2.5	18	2.05	615	6.09
Barley . .	2	17	1.66	498	4.93
Oats . .	2.5	16	2.10	630	6.24
Meadow Hay .	1.5	16	1.26	378	3.74
Clover Hay .	2.0	16	1.68	504	(P)
Swedes . .	17	88	2.04	612	6.06
Mangolds .	30	88	3.60	1080	10.69
Potatoes . .	7.5	75	1.87	561	5.55
Beans . .	2	17	1.66	498	4.94

It will be seen that in all cases the amount of water transpired by the crop is a notable fraction of the total annual rainfall, particularly so in the case of a root crop like mangolds, which in the south and east of England will often require a full half of the total rain falling within the year. As much of the rainfall runs straight off the surface into the ditches, and another portion is lost to the land by percolation into the springs, as again a considerable fraction is evaporated at certain seasons from the bare surface of the soil, it is evident that the water supply, even in our humid climate, is far from sufficient for the maximum of production, and may easily fall below that which is required for an average crop. Indeed, we may take it as a truism that the yield is more often determined by the water available than by lack of the other essentials of growth—

light and heat, manure, etc. Of this we can have no better proof than the enormous crops grown by irrigation on sewage farms. Where the conditions are favourable, and the farm is situated on a free draining sandy or gravelly soil, so that the water can be often renewed and drained away to keep the soil supplied with air as well as water, the production of grass, cabbages, and other green crops is multiplied five or even tenfold by the unlimited supply of water. Speaking generally, over a great part of England, where the annual rainfall is from 35 to 25 inches, a large proportion of which falls in the non-growing season, it is necessary to husband the water supply, and it will be found that one at least of the objects of many of our usual tillage operations is the conservation of the moisture in the ground for the service of the crop. From this point of view, the various operations dealing with the land can now be considered, such as drainage, ploughing, hoeing, rolling, and other cultivations.

The Effect of Drainage.

Drainage is usually regarded as a means of freeing the land from an excess of water, but it also has an important effect in rendering a higher proportion of the annual rainfall available for the crop, so that drained land will suffer less from drought than the same land in an undrained condition.

Land may require drainage for various reasons: it may possess a naturally pervious subsoil, and yet be water-logged owing to its situation, or the subsoil may be so close in texture that percolation is reduced to a minimum and the surface soil remains for long periods almost saturated with water, especially if the slope is gentle and water lies after rain until very large amounts soak in. The flat meadows adjoining a river are

often water-logged because their surface is little higher than the water in the river and the general water table in the adjoining soil. In these cases tile drains are of no value because of the want of fall; open cuts and ditches draw off the water best, and by exposing some of the subsoil water both to aeration and evaporation, lead to the improvement of the land. Another cause of swampy water-logged land is the rising to the surface of a spring or a line of soakage, such as is always formed at the junction of a clay or other stiff soil with an overlying pervious formation, "when the sand feeds the clay," as the old rhyme runs. Such wet spots can be drained by tiles or by an open ditch cutting the springs or the line of soakage. Land lying on an impervious subsoil at the foot of a slope is often very wet because the water which has accumulated in the hill and soaked downwards is forced to the surface by the hydraulic pressure of the water above; such seepage water rising to the surface from the subsoil is characteristic of many valley soils, and can best be dealt with by a system of tile drains. But tile drains are most generally employed and are of greatest value in dealing with stiff impervious subsoils, which cannot get rid of the rain falling upon them; indeed, one of the prime improvements effected in English agriculture was the drainage of something like 3,000,000 acres of heavy land between the years 1840-70. A great portion of the work was unfortunately of little avail, because at first there was a tendency to set the drains too deep, at 4 feet instead of the 2 to 3 feet which have been found to answer best. The benefits conferred by drainage depend upon the lowering of the permanent water table to the depth at which the drains are laid, so that instead of constantly stagnant water a movement of both water and air is established in the soil above

the drain. In the first place, the introduction of the air which follows the water drawn off by the drains brings the whole depth of soil into activity, whereas previously only the portion not water-logged was available. Plant roots cannot grow without oxygen from the air, hence in a water-logged soil the roots are confined to the surface layer only; after drainage the roots can penetrate as far as the air extends. At the same time, all the fundamental chemical and biological processes of the soil, such as nitrification and weathering, are brought into action by the introduction of the oxygen upon which they depend. Later it will be seen that a water-logged soil results in the loss of nitrogen to the land when such manures as nitrate of soda are applied to it. It is the extended root range of the crop resulting from the introduction of air by drainage which enables the drained land to resist a drought better than before. In an undrained soil the roots are confined to a shallow layer, which they soon deprive of all moisture; further supplies of water from the saturated soil move upwards very slowly in a clay soil, so that the plant may suffer greatly. In a drained soil, on the contrary, the roots traverse the whole 3 feet or so into which air has been admitted; this mass of soil, even after it has given up by percolation all the water it can, will still hold much more than is contained in the shallow layer alone traversed by roots before drainage. Following upon drainage, a slow improvement in the texture of clay soil is always manifest: by the drawing of air into the soil, by the consequent evaporation and drying, a certain amount of shrinkage and a clotting of the fine clay particles result, which is never entirely undone when they are wetted again. Roots, which afterwards decay and leave holes, and deep worm tracks, are all brought into the soil by its

aeration, and result in more rapid percolation. Again, the washing through the soil of soluble salts derived from the surface, especially the bicarbonate of lime which is so characteristic a constituent of drainage water, also induces flocculation of the fine clay particles. Lastly, there is a steady removal by the drains of the finest clay stuff, for whenever tile drains are running freely the water will be found slightly turbid with clay matter. All these causes contribute to establish a better texture in the drained soil, beginning at the tiles and spreading slowly outwards. The other result of drainage which may be noted here is the greatly increased warmth and earliness of a drained soil; the high specific heat of water, and the cooling produced by evaporation when the water table is near the surface, combine to hinder a water-logged soil from warming up under the sun's heat in the spring, so that undrained land is notoriously cold and late.

Effect of Autumn Cultivation upon the Water Content of the Soil.

In regions where the annual rainfall is not very high and occurs chiefly during the early winter months, it is important to get as much of it as possible into the soil for the use of the subsequent crop. Breaking up the stubbles after harvest is an important factor in catching the winter rain; all land which is to lie idle through the winter, previous to the sowing of roots or spring corn, should be early turned over with the plough and left rough through the rainy season. On the old stubble which has been made solid by the weather and the trampling during harvest, the rain lies for some time and evaporates, and if the land be at all on a slope the water shoots off into the ditches. But the broken surface of a ploughed field both hinders the flow of the water and

affords it many openings by which to sink in; at the same time the increase of pore space in the loose ploughed layer enables this portion to absorb more water before percolation begins. King has observed in May a difference of 2.3 per cent. of water in the top 3 feet of soil between land ploughed in the autumn and the adjoining land not ploughed; the gain in this case due to the ploughing was 110 tons of water per acre, or rather more than 1 inch of rain.

The following table shows the effect of ploughing up a stubble in autumn on a thin chalky loam at Wye, Kent, where the soil is only about 2 feet deep. The samples were taken on 3rd March 1902; there had been but little rainfall except in the previous December. The figures show mean percentages of water in the wet soil exclusive of stones.

	Land Ploughed in Autumn.	Adjoining Land not Ploughed.
1st foot .	16.45	16
2nd foot .	15.8	14.6

Of course the autumn ploughing has many other beneficial effects in addition to the above-mentioned gain of water; the ploughed soil gets alternately frozen and thawed, wetted and dried, with the result that on the stiff lands the puddling effects of trampling, etc., are obliterated, and the soil acquires a loose, open texture, out of which a seed bed can be made. From the point of view of tilth the all-important thing is to get the ploughing done before the frosts are over. However wet the soil may have been during ploughing, if it gets two or three freezings, followed then by drying weather, it will crumble naturally and can be harrowed down to a good seed bed. But if a clay soil is cultivated when

wet and then dries rapidly, as it often will do in March, it forms obstinate clods which no operation will reduce to a good tilth. Again, the additional surface which is exposed to the action of frost and rain causes increased weathering, and some of the dormant mineral plant food is brought into a more available condition.

Spring Cultivation.

In such climates as prevail in parts of England, where it is necessary to retain as much of the winter's rainfall in the land as possible, and where spells of drying weather are apt to set in with the spring, it is desirable to cross plough or otherwise move any land that is destined for a summer crop at as early a date as it will bear cultivation. This spring working is necessary for two reasons: to obtain a mulch, or layer of loose soil, which will conserve moisture in the subsoil during the dry periods that follow, and to give the surface soil an opportunity of drying gradually into a condition that will yield a good tilth. The land, even though ploughed in the autumn, will become consolidated again to a considerable degree by the beating rains of winter. In this closely-packed material capillary water can move freely, and as the surface layer dries under the action of the sun and wind, fresh supplies of water are lifted from the subsoil by surface tension, with the result that there is a steady and continuous drain of subsoil water through its connection with the exposed and rapidly evaporating surface. But if the top layer of soil is broken up and left loose upon the land by the cultivator, there is no longer a continuous film joining the exposed surface and the subsoil water; surface tension can only lift water as far as the film is unbroken, *i.e.*, as far as the unstirred soil extends, and this layer is protected from evaporation by the loose

soil above. Regarding it from another point of view—in the undisturbed land there exist fine passages and capillary spaces extending from the surface down to the subsoil; up these passages water will rise as long as it is withdrawn by evaporation at the top; in consequence, the surface soil is not allowed to dry, being fed with subsoil water which is constantly drawn from below. But when the land is cultivated the capillary channels are broken, water cannot rise into the loose layer of surface soil, which in the main is separated from the firm soil below by large spaces across which water cannot rise; hence the surface soil can become dry, because it is cut off from the subsoil water, which in its turn is preserved for use later. The drying of the surface soil which ensues, through its severance from the water-yielding subsoil, is of the greatest possible importance in obtaining a tilth. At a certain stage the soil can be dragged and will fall in pieces, but if it be not detached from the subsoil it will either remain persistently wet, so that it cannot be harrowed down, or if it be forced to dry under the action of wind and sun, it will set very hard and “steely,” should it contain any admixture of clay. The sudden forced drying of strong land always produces hard and intractable clods, which may defy all the efforts of the cultivator during the rest of the season, unless a fortunate succession of weather enable him to begin to make his tilth over again.

It may be thought that the amount of water lifted by surface tension cannot be so large as to result in any serious losses to the subsoil store, but in soils of suitable texture enough can certainly be raised to keep the crop alive during periods of drought. In some of King's experiments with a cylinder full of very fine sand, he found that the evaporating surface lost daily an amount of water equal to 0.46 inch if the per-

manent water level were 1 foot below, 0.405 if the water had to be lifted 2 feet, and 0.18 inch if the water had to rise 4 feet to the evaporating surface. When the sand was replaced by a clay loam, the lift of water to the surface was somewhat less, but in all cases the amounts were probably less than would be realised under field conditions, because the evaporation was not enough to dry the surface, and was further checked by the formation of a saline crust on the surface. Working in the field, King obtained a daily loss at the evaporating surface of 1.3 lb. per square foot, or 0.19 inch of water, the water table being from 4 to 5 feet below the surface.

The following table illustrates how the subsoil may act as a regulator to the amount of water contained in the surface layer, absorbing the water which descends by percolation during rainy periods, and giving it up again by capillarity to the surface soil during periods of drought. The first line shows the rainfall during the periods indicated, the second line the amount of evaporation during the same period, while the third line shows the changes in the water content of the top foot of soil. As this change is not represented by the difference between the rainfall and the evaporation, it is clear that water must have been in some cases passed down to the subsoil, in others lifted from it, in quantities shown by the last set of figures.

Water in inches.	80/iv. to 80/v.	80/v. to 9/vil.	9/vil. to 7/x.	7/x. to 27/x.
Rainfall	0.18	4.53	3.17	5.65
Evaporation	3.45	2.96	5.71	1.83
Gain or Loss of Water in top foot	-1.0	+1.4	-0.24	+0.61
Water furnished by (-), or passed on to (+) Subsoil	-2.27	+0.17	-2.0	+3.21

During the first period, the month of May, a dry spell prevailed, only 0.18 inch of rain fell, while the evaporation amounted to 3.45 inches; despite this loss the top foot of soil only contains 1 inch of water less than at the beginning, so that the rest of the excess of evaporation over rainfall must have come from the subsoil, which had in fact to furnish 2.27 inches. In the second period more water fell as rain than was evaporated; the surface soil gained 1.4 inch, which did not account for all the excess of rain over evaporation, a further .17 inch must have descended into the subsoil.

The extent to which the deeper subsoil below the range of the roots of the crop is able to supply the surface soil and the growing plant with water by capillarity has been the subject of considerable discussion. It has been very generally considered that the uplift which must go on from the permanent water table, at whatever depth, provided the subsoil or underlying rock is of the texture that permits of capillary movements, must be a factor in the supply of water to the crop during protracted periods of drought. It seems probable, however, that the amount so lifted can be of no material service, and that the effective capillary movements are those of comparatively small range which bring the water in the soil a few inches or even fractions of an inch to the actual surface of the root hairs. In the first place, as indicated above in King's experiments, the rate of capillary uplift diminishes very rapidly as the distance from the water table is increased. At Rothamsted (p. 85) the two drain-gauges consist of isolated blocks of undisturbed soil, one 18 inches, the other 6 feet deep. The surfaces of both are freely exposed to rainfall and evaporation. Over a long period of years the proportion of the

rainfall percolating through and evaporating from the surface of either gauge are identical, except for certain minor differences explicable on other grounds. Thus the water remaining in the deeper layers of the 6-foot gauge, even when saturated after a rainfall, has never been lifted to the surface and evaporated. Again, there would generally seem to be water enough in the layer of soil and subsoil traversed by the roots of the plant to supply the crop with the water it actually uses. The fact that has to be explained is the capacity of a soil to maintain the crop during drought, even to carry it through all its stages of growth without any rainfall, as in certain regions of North America and Australia. On reference to Alway's figures (p. 97) it will be seen that the fallowed land down to a depth of 6 feet had an average of 12.9 per cent of "free water." Assuming the soil to weigh about three million pounds per acre foot, there would have been approximately 1000 tons of free water down to the 6-foot depth, equivalent to 10 inches of rainfall. This of itself would be sufficient for far more than the average growth made under these conditions. Further, Alway has shown that after a crop, however thoroughly the soil may have been dried out down to the depth (4 to 6 feet) to which the roots of the crop penetrate, yet the layer below will still be moist and possess the same proportion of water which the similar layer contains below uncropped land alongside. Leather has adduced similar evidence from India, and these considerations lead one to conclude that in the main the crop draws for its water supply only upon the zone penetrated by the roots of the plant, and that the movements of water from still lower zones are so small as to be a negligible factor in crop production. It cannot, however, be said that the evidence for this view is complete, and the question merits further investigation.

In any case the freedom of movement of water within the soil by capillarity is a factor of great importance in bringing to the roots the water that is close at hand. In a drought it is always the gravels and coarse sands which suffer first, and this not so much because they start with less water, for we have already seen that what they absorb they can give up almost wholly to the plant, whereas a clay, which absorbs much more, can only hand over about the same proportion to the plant as the sand did, so much being held as hygroscopic moisture. The plant suffers because the small surface of the soil particles gives the coarse-grained sand or gravel a very limited power of moving the subsoil water to the roots of the plant. Should a drought continue, the clay soils begin to suffer next, for though they start with large supplies of water and have an extensive surface of soil particles, yet water can be moved so slowly through the very fine pore spaces that the supply cannot keep pace with the loss by transpiration and evaporation. The soils which are least affected by drought are the deep loamy sands of very uniform texture, fine-grained enough to possess a considerable surface, and yet not too fine to interfere with the free movement of soil water. The root range in these soils is always greater than in clay soils because of their better aeration. The winter penetration of roots into a clay soil is often limited by its temporary saturation with water, and this comparative deficiency in the depth of soil traversed by and supplying water to the roots largely accounts for the manner in which crops on clay soils suffer in a protracted drought. The western soils which the American writers describe as capable of growing wheat with a winter rainfall of 10 to 12 inches and an unbroken summer drought of three months' duration, are deep, fine-grained, and

uniform, with practically no particles of the clay order of magnitude.

The following figures, obtained by King, illustrate how a spring ploughing preserves the soil moisture during a period of dry weather, by establishing a loose protecting layer over the water-bearing subsoil. The upper line shows the water content of the top 4 feet of a certain piece of land on 29th April, on which date part of it was ploughed and part left untouched. On 6th May, no rain having fallen, the soil was sampled again, both on the ploughed and the unploughed piece, with the results set out in the lower figures:—

Lbs. of Water in each successive cubic foot.	1st.	2nd.	3rd.	4th.
Land on 29th April	14.1	20.1	18	16.6
Land on 6th May, ploughed 29th April	13.9	20.7	18.3	16
Land on 6th May, not ploughed	10.6	18	17.3	13.9

It is seen that the ploughed land practically lost no water during the week ending 6th May, whereas during the same period the land not ploughed lost 9.1 lbs. per square foot of surface, a quantity equivalent to $1\frac{3}{4}$ inch of rain.

A similar trial made on a light loam at Wye during a dry period in the spring of 1902, gave the following percentages of water in the wet soil

	Land Ploughed Autumn and Spring.	Ploughed Autumn only.
1st foot .	16.7	15.9
2nd foot .	15.4	13.9

There can be little doubt that the earlier land which is intended for spring corn, or particularly for

roots, can be moved in the spring, the more water will be saved for the use of the subsequent crop, and the easier will a good tilth be established. The chief danger lies on the very fine sandy soils, which, when in a loose condition, are apt to run together under heavy rains and afterwards cake on drying.

Hoeing and Mulches.

The principles which have already been developed to explain the effect of an early spring ploughing in saving subsoil water, apply even more markedly to all the later spring and summer cultivations, hoeing and the like, which have for their object the maintenance of a loose tilth upon the surface. The loose soil becomes itself dry, but by reason of its discontinuity and coarse-grained condition, does not conduct the moisture from the firm subsoil to the surface exposed to sun and wind. Under these conditions the only loss will be of that water which evaporates from the moist soil into the air spaces of the loose upper layer and then diffuses into the atmosphere; the deeper the loose layer thus formed, the more effective will it be, and if it is destroyed by a fall of rain, which consolidates the ground and establishes a continuous liquid film from the subsoil water right up to the surface, it should be renewed by a fresh cultivation as soon as the land will admit of working. It is often noticed that a casual shower during a dry period, or watering a garden unless the operation is done very thoroughly, may result in a greater drying up of the soil than ever, just because a film of water is created able to lift water from the subsoil up to the evaporating surface. The loose hoed ground practically forms a mulch, though the protecting material is the soil itself instead of straw or kindred substances.

Of course, the conservation of soil moisture is not the only good effect brought about by the surface cultivation during the summer: the aeration of the soil, the mechanical distribution of the nitrifying bacteria that is effected, the warmth of the surface layers due to their dryness, all combine to render nitrification active, and to bring into a form available for the plant the reserves of nitrogen in the humus of the soil. This point will be dealt with more at length later: for the time, it will be sufficient to remind the reader how a turnip crop with its frequent spring and summer cultivations is almost independent of any nitrogenous manure, though it removes something like 100 lbs. of nitrogen per acre: whereas a wheat crop, removing less than half that quantity of nitrogen per acre, often requires the application of a nitrogenous manure, because it is grown on undisturbed soil in the cooler season of the year.

The saving of soil moisture which can be effected by hoeing is illustrated by one of King's experiments, when, during a dry period, the soil on a piece of land kept cultivated to a depth of 3 inches was sampled from time to time down to a depth of 6 feet, samples being taken simultaneously from an adjacent piece of land where the surface was kept smooth and firm. On the cultivated land there was a daily loss equivalent to $14\frac{1}{2}$ tons of water per acre, which was increased on the uncultivated land to 17.6 tons per acre; the difference during the 49 days over which the trial was spread, amounting to 1.7 inch of rain saved by the cultivation.

The value of surface cultivation is well seen in other trials of King's, where the water content down to a depth of 4 feet was compared on two adjacent pieces of land, one stirred to the depth of 3 and the other to $1\frac{1}{2}$ inches only. The 3-inch soil mulch, taking the whole

season through, preserved more soil moisture than the shallower cultivation, but by keeping the soil immediately below the mulch more moist and therefore with a better developed water film, it also enabled this layer to lift more moisture from the 3 or 4 foot depth into the top or second foot, a position more available for the crop. Thus the average of three determinations of water content on 16th July gave the following results :—

Per cent. of Water.	1st foot.	2nd foot.	3rd foot.	4th foot.
Soil cultivated, 3" deep .	12.3	18.6	16.8	14.6
" 1½" deep .	11.2	17.6	17.8	16.2

On this occasion it is seen that the upper 2 feet of soil are being kept moister by their greater power of lifting water from the lower layers, which actually contain more water under the 1½-inch mulch than under the 3-inch mulch.

Although the gardener uses the hoe freely to establish soil mulches, he also employs dung, grass-clippings, and even straw to the same end, anything to break the connection between the water-bearing subsoil and the exposed evaporating surface. Such mulches of loose organic material are even more effective in conserving soil moisture than a fine tilth, there is less tendency to form any continuity of water film between subsoil and mulch; moreover, the evaporation of the water they themselves contain helps to keep the temperature down. The great drawback to their employment is that they prevent the continual stirring of the ground which promotes aeration and nitrification.

Stones serve almost the same purpose as a mulch, especially when they are impermeable, like flints, and cover the surface at all thickly. They shield the land below from evaporation; indeed, on picking a flint off an

arable field the ground below will generally be found cool and damp. The vineyards of the Rhine, etc., are generally set on steep slopes very thoroughly drained and exposed to the sun; it will be noticed that the utmost care is taken to keep the surface of the soil covered with the broken slaty rock.

Effect of Rolling.

Though it has been pointed out that maintaining a loose tilth on the surface is the most effective means possessed by the farmer of saving the soil water and minimising losses by evaporation, yet one of the fundamental acts of husbandry in the spring consists in rolling and otherwise consolidating the land. Particularly is this the case on the chalk and similar light soils; whenever a spell of dry weather prevails in the early part of the year the farmer will be observed rolling his seeds, or his spring corn, or his newly sown turnip land, as the case may be; he will even take a heavy cart wheel down between the drills when the roller will not give him pressure enough. The result of the consolidation of the surface soil thus effected is to improve its power of lifting the soil water from below by capillarity, because the pore space is diminished and the wide intervals across which the water film cannot exist are largely closed up; just as the motion of water through surface tension almost ceases in a thoroughly loose soil, it is, *per contra*, increased when the particles are brought more closely together. Hence, on the rolled land there will be a greater lift to the evaporating surface and subsequent loss of water, but the farmer faces this loss in order to keep the upper few inches of soil supplied with moisture. Rolling is only done on land occupied by germinating seeds, young spring corn, or a young ley, where the

roots, if any, are so close to the surface that the whole crop will perish if the top layer is allowed to dry. The effect of rolling is to increase the capillary lifting power of the top soil, so maintaining it in a moister condition, although the land as a whole is made dryer by the extra evaporation which must accompany the rise of subsoil water to the surface. It is a maxim in farming on the chalk, where there is always a store of subsoil water at some depth or other, and where also the surface soil is peculiarly liable to become open in texture through the action of worms and the rapid decay of dung, that the land will become moist if it can only be got "tight" enough. On any light cultivated land it is easy to notice how much moister the soil remains when it has been consolidated by a foot mark; a gardener again, whose rich and deeply-worked soil is apt to get very open, always treads the ground as solid as possible in preparing a seed bed for onions and other small seeds. The following figures given by King as mean values from a number of measurements show how rolling dries the soil as a whole when samples are taken down to 2 feet or more, but maintains the surface soil, sampled only down to 18 inches, in a moister condition:—

Depth of Sample.	PERCENTAGE OF WATER.	
	Rolled Ground.	Unrolled Ground.
Down to 18" . . .	15.85	15.64
Down to 24" . . .	19.49	19.85
Down to 36"-54" .	18.72	19.43

Since rolling dries the soil as a whole, it is only desirable when shallow-rooted crops must be kept supplied with water at any cost; as soon as they get their roots down hoeing should begin in order to diminish the inevitable

evaporation from the firm surface. Thus a tool like the old broadsharing plough, still used on the chalk, is particularly valuable in preparing a tilth for roots, for, while creating a loose surface tilth, it is consolidating the soil below and increasing its power of lifting water from the subsoil.

Similarly, in the semi-arid regions of Western America and in Australia, where the rainfall is barely sufficient for the needs of the crop, in the preparation of the land great importance is laid on the two operations of "subsoil packing" and "the establishment of a soil mulch." This is the equivalent of the English practice of preparing a seed bed for roots; frequent cultivation without inverting the soil in order to work it down to a fine tilth, constant use of the ring roller or subsoil packer to consolidate this crumb until it will lift water by capillarity, and, finally, the production and continual renewal by means of light cultivators or horse hoes of a very thin skin of loose soil on the surface.

Valuable as the operation of rolling is on grass land in the early spring, in order to consolidate the soil round the roots of the grass after the surface has been lifted by the winter frosts and by the action of worms, it should be borne in mind that it is easy to do harm by injudicious rolling in wet weather on soils that are at all heavy. Even on grass land the clay may become so puddled or tempered that it dries round the roots with a very harsh caked surface, little permeable to air and water. This sort of damage is perhaps most often seen on lawns and cricket grounds which are rolled repeatedly with heavy rollers when the ground is thoroughly wet; a smooth, pasty surface is produced to the ultimate great detriment of the growth of the grass. Of course upon arable land the greatest care must be taken never to roll when the top is at all

wet or even damp, lest a pasty surface be developed, which will dry to a glazed baked crust. It is necessary even to wait until the dew has been dissipated before rolling strong land that has been well worked and drilled for roots.

The Drying Effect of Crops.

Since a crop transpires about 300 lbs. of water for each pound of dry matter produced, any land which is carrying a heavy crop must contain much less water than the adjoining uncropped land, unless there has been such an excess of rainfall as to saturate the soil in either case. Any summer growing crop, however, especially one of roots, transpires so large a proportion of the customary rainfall during the period of growth, that it must leave the soil much drier for its growth. As an example of this removal of water by the growing crop, the following figures obtained at Rothamsted during the very dry summer of 1870 may be quoted, showing as they do the water present in successive 9 inches of fallow and of adjoining land carrying a barley crop:—

	Percentages of Water in the Soil, June 27-28, 1870.	
	Fallow.	Barley.
First 9"	20.36	11.91
Second 9"	29.53	19.32
Third 9"	34.84	22.83
Fourth 9"	34.32	25.09
Fifth 9"	31.31	26.98
Sixth 9"	33.55	26.38

The total difference between the cropped and uncropped land down to the depth of 54 inches, amounted to more than 900 tons of water per acre, or 9 inches

of rain, which is quite half as much again as would be accounted for by the crop on the assumption that only two tons or so of dry matter had been grown at the date of sampling.

Another example of the withdrawal of water from the soil by the crop is seen in the proportions of water in the soil of certain of the permanent grass plots at Rothamsted, taken in July of the same year, 1870—

	PLOT 8.	PLOT 9.	PLOT 14.
	No Manure.	Mineral Manure + Ammonium Salts.	Mineral Manure + Nitrate of Soda.
Crop, 1870 . . .	5½ cwt. of Hay.	20½	56½
Per cent. of Water.			
First 9" . . .	10.83	13.00	12.16
Second 9" . . .	13.34	10.18	11.80
Third 9" . . .	19.23	16.46	15.65
Fourth 9" . . .	22.71	18.96	16.30
Fifth 9" . . .	24.28	20.54	17.18
Sixth 9" . . .	25.07	21.34	18.06
Means . . .	19.24	16.75	15.19

Down to the depth of 54 inches the plot receiving minerals and ammonium salts contained 200 tons, and the plot receiving minerals and nitrate 325 tons, less water than the unmanured plot, quantities in this case somewhat less than would be indicated by the amount of dry matter produced.

There are two important cases in which the drying effect of vegetation needs to be taken into account, in the use of catch crops and in the planting of fruit trees. On the lighter lands of the south of England catch crops are not uncommonly taken on the land before roots. The stubbles are quickly broken up, and

vetches, trifolium, or rye, are sown in time to make a start while the land is warm, and to be either cut green or fed off before the land is wanted for turnips in the following spring. The advantages of the practice are that the summer-formed nitrates in the stubble-ground are saved from washing out, and that a valuable bite of early fodder is obtained: with the leguminous crops also, the farm is enriched by the nitrogen gathered from the atmosphere. The difficulty of getting catch crops lies in the fact that the stubble ground is left very dry by the preceding crop, so that a timely rainfall is needed to obtain a plant. The danger of their use is that they may so deplete the available soil water as to give the succeeding crop of roots a very poor chance of germinating or growing well. In America the practice has been suggested of sowing some leguminous crop like clover in the tillage orchards about the end of July, so that the new surface crop should so dry the ground as to forward the ripening of the apples on the trees; again, any second growth of the trees due to a late summer rainfall would be prevented, this moisture being dealt with by the catch crop.

The second illustration worthy of notice is that fruit trees when newly planted in grass land often make a very poor growth for a year or two. This is because a fruit tree when planted is but indifferently supplied with water-collecting roots; inevitably they are few in number and have a very restricted range. Hence they must be in a soil well supplied with moisture if they are to provide the tree with the necessary water, and they are very ill fitted to compete with a crowd of fibrous grass roots surrounding them, should the season turn out dry. In one experiment the moisture in the top foot of a pasture was found to be only half that present in the top foot of neighbouring uncropped land.

The following table shows the percentages of water in the fine earth of an orchard on heavy soil, part of which was under grass and part kept tilled; it will be seen that in the winter the grass land carries as much or even more water than the bare soil, but towards the end of the summer the drying effect of the grass becomes very pronounced, even down to the third foot.

	1ST 9 INCHES.		2ND 9 INCHES.		3RD 9 INCHES.	
	Grass.	Bare.	Grass.	Bare.	Grass.	Bare.
December 19/05	25.0	24.7	23.5	23.5	25.0	27.0
March 3/06	26.7	23.3	21.2	21.9	20.6	19.6
May 24/06	17.7	24.0	18.7	24.5	22.3	25.0
July 25/06	13.8	15.6	14.5	18.2	14.8	24.4
September 27/06	12.6	15.7	13.8	15.1	15.6	18.8
April 6/07	21.1	21.6	21.0	24.0	19.6	21.3
October 9/07	22.6	27.1	23.7	—	23.6	25.0

Few crops so effectually dry the surface soil as grass does, because of the intimate way in which its roots traverse the soil; hence a fruit tree cannot compete with grass for water as long as the two sets of roots are confined to the same layer. The experiments at the Woburn Fruit Farm of planting fruit trees and sowing the seed of coarse meadow grasses at the same time, show this competition at its highest degree, but even when trees are planted in old pasture care should be taken to keep a ring round the tree free from grass and well cultivated or mulched for at least two years.

Other causes are doubtless at work; it has been argued that the grass roots excrete substances toxic to the roots of the fruit trees, among which we may enumerate carbon dioxide as a very probable factor in checking development. Again, the grass roots may induce an injurious disturbance of the bacterial flora,

but it is not possible as yet to discriminate with any certainty among the actions at work. For similar reasons, when trees are planted in arable land weeds should be kept down, nor should crops like cabbages or mangolds be grown between the rows of trees; such crops are usually considered to "draw the land" and deplete it of plant food, but the harm they do lies in the water they withdraw just at the most critical season, when the tree is making its first start in its new quarters.

Bare Fallows.

The custom of fallowing land, of leaving it entirely bare for a season, during which the land is worked as often as possible, is one of the oldest in agriculture; a rotation of wheat, wheat, fallow, or of beans, wheat, fallow, being almost universal, until the introduction of turnips gave the farmer a chance of cleaning his land and yet growing a crop at the same time. The objects of a fallow were various: in the first place, the summer cultivations resulted in a thorough cleaning of the land and in a free development of nitrates for the succeeding crop; also on the heavy soils, which are the most suited to fallowing, a good tilth was obtained that was often impossible otherwise. Indeed, at the present day it is found desirable and even necessary to introduce an occasional bare fallow when farming on the heavy clays of the south and east of England, in order to obtain a satisfactory tilth in that dry climate.

One of the most notable effects of fallowing lies in the production of a stock of nitrates from the stores of combined nitrogen in the soil; these nitrates are at once available for the ensuing wheat crop if the autumnal rains are not too great to wash them out of the soil (see p. 129).

But in addition to the gain in available nitrogen due

to fallowing, the land which does not carry a crop during a season will accumulate a store of water which may be of the utmost service to the succeeding crop. In the preceding section some figures have been given showing how much more water is present at the end of the summer in the fallow land than in the land which had carried a crop, so that in districts where the winter rainfall is small the fallowed land will start the next season with a great advantage. Indeed, in a semi-arid climate where the annual rainfall is insufficient, satisfactory crops may yet be grown in alternate years by using an intermediate fallow period in which to accumulate a reserve of subsoil water.

The following series of measurements will illustrate this point; it shows the percentages of water in spring and autumn on fallow and cropped land respectively, also the water present in the same land in the following spring and autumn, when both plots were in oats.

	SPRING.		AUTUMN.		FOLLOWING SPRING AND AUTUMN.			
	Fallow.	Corn.	Fallow.	Corn.	Oats.	Oats.	Oats.	Oats.
	1.	2.	1.	2.	1.	2.	1.	2.
1st foot .	24 %	22 %	17 %	7 %	19 %	16 %	6 %	4 %
2nd foot .	20 "	19 "	20 "	12 "	21 "	18 "	10 "	5 "
3rd foot .	18 "	18 "	16 "	4 "	18 "	15 "	9 "	8 "

The effect of the fallowing in retaining more moisture in the soil is seen throughout the whole of the second season.

At Rothamsted portions of the wheat field were fallowed during the summer of 1904, and the following table shows the percentage of water in the fine earth on 13th September, 2.849 inches of rain having fallen since the crops had been cut:—

	UNMANURED.		DUNGED.		MEAN OF 8 PLOTS.	
	Cropped.	Fallow.	Cropped.	Fallow.	Cropped.	Fallow.
1st 9" . .	15.8	16.0	20.2	19.3	17.4	17.2
2nd 9" . .	18.9	19.8	14.5	17.0	18.8	20.0
3rd 9" . .	20.8	23.3	13.7	18.4	20.1	22.3
4th 9" . .	23.1	25.2	15.5	19.7	20.9	23.1
Mean .	19.6	20.8	16.0	18.6	19.3	20.6

In the surface layer there is practically no difference, both having become equally wet by the rains after harvest, but in the lower depths the fallow soils are the wetter, and the differences are less pronounced for the unmanured plot where a small crop had been grown than for the dunged plot with its larger crop.

The way in which fallowing land is of benefit to the crop, both by making nitrates and particularly by saving water in a dry season, is easily seen in the superior plant always found on the outside rows or edges of an experimental plot divided from the others by a bare path; on one side the plant has the benefit of fallow ground as well as of extra space, light, and air, and flourishes accordingly. The Lois-Weedon system of husbandry, where the land was divided into alternate 5-foot strips of corn and cultivated fallow land, was nothing but an application of this principle on a large scale, as indeed is any system of growing a crop in wide rows to admit of some form of hoe or cultivator working regularly at the ground between. In a humid climate or on a porous soil there is great danger of losing the nitrates formed in the summer by washing out during the autumnal and winter rains, nor is there any advantage gained by storing water where the usual winter rainfall is sufficient to saturate

the soil. For this reason, in the Rothamsted experiments, the plot growing wheat continuously has given a greater crop per acre per annum than the plot fallowed and sown with wheat in alternate years, though the wheat crop following fallow has always been larger than the crop grown the same year on the unmanured plot.

Average Crop.	WHEAT EVERY YEAR.		FALLOW AND WHEAT.	
	Grain.	Straw.	Grain.	Straw.
1856-1895 . .	Bushels. 12 $\frac{3}{4}$	Lbs. 1127	Bushels. 8 $\frac{5}{8}$	Lbs. 798

Of course the average yield on the fallowed ground was twice the above figures, *i.e.*, 17 $\frac{3}{8}$ bushels of grain and 1595 lbs. of straw, but it was only grown every alternate year.

That the autumnal rainfall is the great factor in determining whether a bare fallow shall be profitable or not to the following crop, may be well seen by a further examination of the results obtained at Rothamsted on these plots, by comparing the crops with the percolation which took place in the autumn previous.

The percolation through 60 inches of bare soil for the four months, September to December inclusive, as measured by the drain-gauge previously described on p. 85, amounted on the average to 6.45 inches for the 31 seasons, 1870-1901. If, then, we divide the harvest years into two groups according as the autumnal percolation is above or below the average, and allot to each year the crops on the continuous wheat and wheat after fallow plots for the harvest following the given percolation, we shall obtain the following average results, which show in group 1 the mean crops following autumns of less than average percola-

tion, and in group 2 those following autumns of comparatively high percolation. The percolation is given in inches, the crops in lbs. per acre of total produce, both grain and straw; and as further evidence of the extent of percolation, the average number of days are given during the four months on which water ran from the tile drain underlying the continuous wheat plot.

		Rainfall.	Percolation through 60-inch gauge.	No. of days on which tile drain ran.	CROP, LBS. PER ACRE.		
					Wheat after Wheat each Year.	Wheat after Fallow.	Gain due to Fallow.
1.	15 Years of Percolation below average . . .	8.94	3.99	4	1807	2677	870
2.	16 Years of Percolation above average . . .	13.78	8.92	13	1627	1757	130

Thus the bare fallow which increased the succeeding crop above that given by the continuous wheat plot by nearly 48 per cent. in the seasons when a comparatively dry autumn succeeded the fallow, increased it by less than 8 per cent. when there was much percolation after the fallow.

It follows, therefore, that the practice of fallowing land is only an economical one where the annual rainfall is low and where the land is too strong to admit of free percolation; it is, however, admirably adapted to the successful cultivation of clay land in dry, hot climates.

Dry Farming.

The practice of fallowing finds its greatest development in the system of "dry farming," which has been evolved in semi-arid regions, such as the Great Plains

of North America and parts of Australia and South Africa, in order to deal with land with an average rainfall of from 15 to 10 inches. There the amount of water reaching the soil is insufficient to provide for the needs of a crop every year. Failures are too numerous to allow the farmer to make a living; but it is found to be possible to obtain a crop with some certainty if it is preceded by a year of bare fallow, during which the greater part of the rainfall is accumulated for the succeeding year's crop. The bare fallow may be necessary in alternate years or may be taken every third year. For example, the regular course of cultivation on the wheat lands of South Australia, in the zone with an annual rainfall of from 12 to 20 inches, begins with a year of bare fallow, during which the ground is worked over three or four times, as often as is necessary to keep the surface loose. Then follows the wheat which is harvested by a machine that simply strips off the heads and leaves the straw standing. Sheep are then turned in and graze upon the straw and upon such weeds as may come up spontaneously during this the third year of the rotation. With better farming, especially where the rainfall is rather greater, peas may be sown on the stubble to be grazed off in the third year, thus enriching the soil in nitrogen as well as providing increased food for the sheep. But the ground is left by the wheat too dry for a substantial fallow crop, which in its turn would endanger the accumulation of the scanty rainfall for the ultimate wheat crop. In Australia the wheat is autumn sown, and the farmer's routine consists in spending the late autumn and early winter in ploughing and sowing for wheat. During spring and summer he is occupied in going regularly over the fallow land, with appropriate intervals for sheep shearing and harvest. On the Great Plains the land is frost-

bound during the long winter, and the wheat is spring sown; sheep are not kept because of the cold, but otherwise the routine of cultivation is identical. The Australian is generally content with ploughing the bare fallow repeatedly; in America the methods are a little more elaborated, and subsoil packers, followed by disc harrows and other surface cultivators, are employed in order to conserve moisture and prevent evaporation, by maintaining a firm substratum and a live surface. These simple principles of dry farming, founded upon the practice elaborated in the drier districts of the south and east of England, have enabled vast tracts of otherwise scanty grazing country to be brought under cultivation. The details of the methods to be followed, and the crops that can be grown, are being made the subject of careful investigation, now that the better farming lands are all taken up, and new settlers are being forced on to what before were ranching areas or regarded as bad lands. What are wanted are crops with a low transpiration coefficient, which elaborate a maximum of dry matter for the water they consume, or again, cereals with a high migration ratio, which transform a comparatively high proportion of their total dry matter into grain.

Effect of Dung on the Retention of Water by the Soil.

A soil which has been enriched in humus through repeated applications of farmyard manure will resist drought better than one in which the humus is low; the difference is seen not so much in the greater amount of moisture present in the soil containing humus, as in the way it will absorb a large amount of water temporarily during heavy rainfall, and then let it work more slowly down into the soil, thus keeping it longer within reach of the crop. Good examples

are afforded by the Rothamsted plots; samples of soil from the wheat land were taken on 13th September 1904, on the previous day 0.262 inch of rain had fallen, but for nine days before there had been little or no rain. The portions of the plots from which the samples were drawn had been fallowed through the summer, so that the drying effect of the crop is eliminated. Samples were also taken from the barley plots on 3rd October of the same year; 0.456 inch of rain had fallen on the 30th September, before which there had been fifteen days of fine weather. The following table shows the water in the soil of the unmanured and the continuously dunged plots respectively, as percentages of the fine earth from which the stones had been sifted:—

Percentages of Water in Rothamsted Soils.

Depth.	BROADBALK WHEAT.		HOOS BARLEY.	
	Unmanured.	Dunged.	Unmanured.	Dunged.
0" to 9"	16.0	19.3	17.0	20.7
9" " 18"	19.8	17.0	22.5	17.7
18" " 27"	23.3	18.4	22.1	18.3

It is thus seen that in both cases the dunged soil rich in humus, had retained more of the comparatively recent rainfall near the surface, so that the top soil was moister while the subsoil was drier. The difference in favour of the surface soil was about 3.5 per cent, which on that soil would amount to about 30 tons per acre or approximately 0.3 inch of rain. It is thus seen that the surface soil of the dunged plot had retained practically the whole of the preceding rainfall; and the greater dryness of the subsoil was due to the way

the soil had kept back the small rainfalls, which have been evaporated instead of passed on to the subsoil as they had been on the unmanured plots. The same fact is illustrated by the behaviour of the drains which run below the centre of each of the wheat plots at a depth of 30 inches; below the dunged plot the drain very rarely runs, only after an exceptionally heavy and long-continued fall, whereas the drain below the unmanured plot runs two or three times every winter. Putting aside the greater drying effect of the much larger crop on the dunged plot, the difference is mainly due to the way the surface soil rich in humus first of all absorbs more of the water, and then lets the excess percolate so much more slowly that the descending layer of over-saturation, which causes the drain to run, rarely or never forms.

The water-retaining power of the dung may also be seen in the superior yield of the dunged plots in markedly dry seasons. The following table shows a comparison of the yield on plot 2, receiving 14 tons of dung, and plot 7, receiving a complete artificial manure, for the years 1879, which was exceptionally wet and cold, and 1893, which was hot and dry throughout the growing period of the plant. The rainfall for this period, *i.e.*, for the four months March to June, was 13 inches in 1879 and only 2.9 inches in 1893.

WHEAT. YIELD IN BUSHELS OF GRAIN.

Plot.	1879.	1893.	Average 51 Years.
2	16.0	34.25	35.7
7	16.25	20.25	32.9

The average yield on the dunged plot is about 3

bushels more than on plot 7, but in the dry year its superiority amounted to 14 bushels, whereas in the very wet year the two plots sank to the same low level. In a bad season the bacterial changes which render the plant food in dung available for the crop go on very slowly.

CHAPTER V

THE TEMPERATURE OF THE SOIL

Causes affecting the Temperature of the Soil—Variation of Temperature with Depth, Season, etc.—Temperatures required for Growth—Radiation—Effect of Colour—Specific Heat of Soils—Heat required for Evaporation—Effect of Situation and Exposure—Early and Late Soils.

THE life of a plant is practically suspended below a certain temperature, which is about 41° F. for the majority of cultivated plants; all the various changes which are essential to the development of the plant, such as germination, vegetative activity, and the bacterial processes in the soil, show a similar dependence upon temperature.

These vital actions cease below a certain minimum, above which they usually increase with the temperature until an optimum is reached, when the action is at its greatest; beyond this point the action decreases until a superior limit is reached, which again suspends all change. It therefore becomes important to study the manner in which heat enters and leaves the soil, because upon the temperature acquired depend such practical questions as the suitability or otherwise of the land for particular crops, the season at which to sow, and the earliness or lateness of the harvest.

The surface soil receives heat in four ways:—

- (1) By direct radiation from the sun, whose rays, both of light and invisible heat, are absorbed

- and raise the temperature of the absorbing soil.
- (2) By precipitation, as in the spring when warm rain enters the ground and brings with it a considerable quantity of heat, or when aqueous vapour in the air is condensed on the colder soil.
 - (3) By conduction from the heated interior of the earth a small amount of heat reaches the surface.
 - (4) By the changes which result in the decay of the organic material of the soil, when as much heat is developed as if the same material had been burnt in a fire.

The surface soil loses heat :—

- (1) By radiation; like any other body possessing heat, the surface of the soil is always emitting invisible radiant heat, which may, or may not, be counterbalanced by the corresponding radiations it is absorbing.
- (2) By conduction either to cooler layers of earth below or to cooler air above.
- (3) By the evaporation of the water contained in the soil; at ordinary temperatures the evaporation of 1 lb. of water would absorb enough heat to lower the temperature of about 7500 lbs. of soil by 1° F.

The actual temperature attained by a given soil at any time depends upon the relative effect of the heating and cooling actions set out above.

Soil Temperatures.

The accompanying curves (Fig. 9) show the monthly mean temperatures of the soil at 6 inches, 3




FIG. 9.—Soil Temperatures at 9 A.M., Monthly Means, 1896.

feet, and 6 feet respectively, as compiled from readings taken at 9 A.M. at Wye during 1896, the soil being a light well-drained loam under grass. It will be seen that the variations in temperature diminish with the depth: in fact a point is soon reached, about 50 feet down, below which the effect of the gain or loss of heat at the surface is inappreciable, and the temperature is constant from day to day, only increasing with the depth, according to the well-known law. Each curve cuts each other curve at least twice; for a certain period the upper layer is giving, and during the rest of the year, receiving heat from the layer above or below. The maximum temperature attained at a depth of 3 feet comes a little later in the year than the maximum for 3 inches, and the maximum at 6 feet lags still further behind, owing to the slowness with which the heat is conducted. It will be seen that the curve indicating the temperature at 6 inches (and the mean figures for 3 and 9 inches are almost identical) does not reach the 41° F. required for the beginning of vegetative growth until April; it is, however, constructed from monthly averages only, and from observations taken at 9 A.M., when the surface soil has been considerably cooled during the night. Much higher temperatures are obtained during certain parts of the day even in the early spring months, otherwise no germination could take place; these diurnal and hourly fluctuations are, however, chiefly confined to the surface soil. The following curves show firstly (Fig. 10), the daily results during a fortnight of April 1902, also (Fig. 11) certain hourly readings obtained in the same month, in this case beneath smooth, well-worked arable land. The diurnal variations die away before the depth of 3 feet is reached, nor are hourly variations perceptible at the depth of




FIG. 10.—Soil Temperatures at 9 A.M., Daily Readings.

one foot, except in the case of heavy precipitation and a pervious soil. It will also be noticed from the last curves that during part of the day the temperature at the depth of 6 inches ran up to a point well above the minimum required for germination, although the mean soil temperature at 9 A.M. was near that limit.

Temperatures required for Growth.

Reference has already been made to the fact that a certain temperature is necessary before the vital processes involved in growth become active; this temperature is not always the same, but may be considered to lie between 40° and 45° F. for most of the plants grown as crops in this country.

The following table shows minimum, optimum, and maximum temperatures of growth for a few plants:—

	Minimum.	Optimum.	Maximum.
Mustard . . .	32° F.	81° F.	99° F.
Barley . . .	41	83.6	99.8
Wheat . . .	41	83.6	108.5
Maize . . .	49	92.6	115
Kidney Bean. .	49	92.6	115
Melon . . .	65	91.4	111

The next table shows the effect of soil temperature upon the growth of the root of maize—

ROOT GROWTH OF MAIZE IN 24 HOURS.

Temperature.	Millimetres.
63° F.	1.3
79	24.5
92	39
93	55
101	25.2
108.5	5.9

The osmotic absorption of water by the roots of a plant is much affected by the temperature of the soil; although some plants, like cabbage, will continue to take in a little water even near freezing point, others require a higher temperature; for example, Sachs has shown that tobacco and vegetable marrow plants will wilt even at night, when transpiration is very small, if the temperature of the soil falls below about 40° F.

The killing of plants like rose trees during frost is generally due to drying out from this cause rather than to the actual cold. As the air is often very dry during a frost, evaporation continues, especially if a wind be blowing at the same time; thus the exposed shoots of the plant are losing water which is not being replaced by the roots, whose action is suspended by the low temperature. A covering of snow or dead leaves, or even the protection afforded by a little straw, bracken, or spruce boughs, prevent the destruction of the plant, not by keeping it so much warmer, but by protecting it from evaporation.

The connection between soil temperature and vital processes is perhaps most apparent in the case of germination, for which not only is a certain minimum temperature requisite, but for several degrees above this minimum the germination is so slow and irregular that the young plant is very liable to perish while remaining in such a critical condition. The following table (p. 142) shows the range of temperatures for the germination of various cultivated plants.

The practical bearing of these figures is obvious; it is necessary to sow some seeds, like the melon, in heat; and to defer the seeding of other crops, like mangolds or maize, until the ground has acquired not only the temperature necessary for germination but

one that will ensure a subsequent rapid growth of the seedling plants.

TEMPERATURES OF GERMINATION.

	FAHRENHEIT.		
	Minimum.	Optimum.	Maximum.
Wheat	32° to 41°	77° to 88°	88° to 110°
Barley	40°	77° to 88°	100° to 110°
Oats	32° to 41°	...	88° to 100°
Pea	38° to 41°
Scarlet Runner	49°	91°	115°
Maize	49°	91°	115°
Cucumber, Melon, etc.	60° to 65°	88° to 99°	110° to 120°

For example, turnips will germinate at almost as low a temperature as barley, but the optimum temperature is higher for turnips; they are therefore sown much later in the spring, when the ground has more nearly reached this temperature, because the seed is small and the young plant very susceptible to insect attacks, so that the turnip seed must germinate and grow away rapidly if it is to succeed.

Under ordinary field conditions much of the nutrition of the crop depends upon the activity of certain bacteria in the soil, which break down organic compounds containing nitrogen, and ultimately resolve them into the nitrates taken up by the plant. Most bacteria are active within about the same limits of temperature as have been indicated above for the higher plants; the nitrification bacteria, for example, cease their work below 41° F. and above 130° F., their optimum temperature being about 99° F.

The way a low temperature will check the production of nitrates until they are inadequate for the needs of the crop is often seen in spring, and may be connected

with the yellow colour of the young corn during a spell of cold and drying east wind.

Radiation.

The main source of the soil warmth consists in the heat received from the sun by radiation; this, according to Langley, amounts to about 1,000,000 calories per hour per square metre of surface from a vertical sun in a clear sky. Supposing this energy were wholly absorbed by a layer of dry soil 10 cm. thick, its temperature would rise by as much as 90° F. in an hour. Of course in nature many other factors are at work to reduce this temperature; the sun is rarely vertical, the soil material does not completely absorb but reflects some of the sun's rays unchanged; at the same time it is always radiating in its turn rays of lower pitch than the majority of those received. The latter rays are easily caught by many substances, glass and water vapour in particular, which are transparent to the rays of higher refrangibility proceeding from the sun. A greenhouse, for example, is practically a radiant heat trap; the temperature inside runs up because the sun's rays of light and heat can penetrate the glass, whereas the obscure heat rays radiated back again from the warmed-up surfaces inside the house are not able to pass through the glass again. Just in the same way the temperature rises and the sun's heat becomes oppressive when the air is laden with water vapour, because it retains the radiations emitted by the surfaces heated by the sun. *Per contra*, the temperature of the ground falls more rapidly at night when the sky is clear and the air dry, for then there is no blanket of cloud or water vapour to arrest or reflect the radiations from the surface.

The power of soils to absorb the sun's rays depends

very much upon colour: with black soils the absorption is almost complete; it is greater for red than for yellow soils, least of all for those which look distinctly white or light coloured. It has already been shown that the colour of soils depends mainly upon humus and hydrated ferric oxide, the latter accounts for all the red, yellow, and brown shades, the former for the black coloration of the soil. Deep-seated clays are often blue or green, due to various ferrous silicates or to finely divided iron pyrites, which afterwards oxidise to brown ferric oxide. The more finely grained a soil is the more surface it possesses, and the greater amount of colouring matter that is required to produce a given colour; a coarse sand is often quite black though it contains but a small percentage of humus.

Though the colour of a soil affects the rate at which it absorbs heat, it does not follow that the dark soils will lose with a corresponding rapidity when radiation is taking place at night; the emissive power of the substance for rays of low refrangibility, such as are emitted at ordinary temperatures, is not affected by colour. Hence, the extra heat gained by a dark soil is retained and not lost by a corresponding increase in its radiating power.

The curves in the accompanying diagram (Fig. 11) show the temperatures of the soil at a depth of 6 inches during an April day with a bright sun and a strong drying wind. The land was a light loam of a grey-brown colour when dry; it had been cultivated, rolled, and the surface hoed over before the thermometers were inserted; on plot 1 the bare ground was left untouched, plot 2 received a dressing of soot until the surface was black, plot 3 was similarly whitened over with lime. It will be seen




FIG. 11.—Soil Temperatures at 6 in. depth, as affected by the state of the surface. Sun with strong N.E. wind. 27/iv/02.

that the covering of soot warmed the soil until at 3 P.M., when the maximum temperature was attained, the difference was $2^{\circ}4$; this superiority is also retained during the later cooling stages; even at 9 P.M. the blackened soil was still $2^{\circ}5$ warmer than the bare ground. The whitening with lime had caused so considerable a reflection of the radiant heat that the soil beneath was always 2 to 3° cooler than the bare ground. In carrying out this experiment it is necessary to use no more lime or soot than will distinctly colour the soil; the results will be disturbed if an excess of either loose powder acts as a mulch.

Specific Heat.

The specific heat of the substances of which soil is composed is comparatively low, ranging from 0.1 to 0.2, *i.e.*, only from one-tenth to one-fifth as much heat will be necessary to raise the temperature of 1 lb. of dry soil by 1° , as would be required to produce the same rise of temperature in an equal weight of water. The humus possesses the greatest specific heat and the sand the least; against this must be set off the fact that the densities of these soil constituents vary in the opposite sense, so that the amounts of heat required to bring about a given rise of temperature to a certain depth in different soils are more nearly equal. The specific heats are, however, small in every case when compared with that of water; hence soils which retain much water will require far more heat to raise their temperature than dry soils would. In consequence, clay and humus soils are cold because the water they retain gives them a high specific heat, they require more of the sun's rays in spring to bring them up to the proper temperature for growth, while sandy and other open-textured soils are warm because of their dryness.

If the figures given by Oemler for the specific heats of various soils be combined with their approximate densities and with their minimum capacity for water, the following results are obtained for the specific heats of certain typical soils in a saturated but completely drained condition :—

	SPECIFIC HEAT.		
	Equal Weights.	Equal Volumes.	
	Dry.	Dry.	Wet.
Water . . .	1.0	1.0	1.0
Humus . . .	0.21
Sandy Peat . . .	0.14	0.11	0.72
Loam . . .	0.15	0.18	0.53
Clay . . .	0.14	0.15	0.61
Sand . . .	0.1	0.125	0.34

The sandy soil only requires about half as much heat to raise its temperature by a given amount as would be needed by the peaty or clay soil, when all the soils are in a wet but thoroughly drained condition ; of course if the clay or peat were inadequately drained, so that a higher proportion of water was retained, their specific heats would approximate still more nearly to that of water.

Just as a clay soil is slow to warm in the spring, its high specific heat causes it to cool correspondingly slowly after the heat of the summer. On clay soils growth will be noticed to continue later into the autumn than on the lighter lands.

Heat required for Evaporation.

The coldness of a wet and undrained soil is due, not only to its high specific heat, but to the fact that so much of the heat it receives is spent in evaporating some of its retained water, without causing any rise in temperature.

The evaporation of 1 lb. of water at 62° F., *i.e.*, its conversion into water vapour at the same temperature, requires as much heat as would raise the temperature of 1050 lbs. of water by 1° F., and, if there be no source of external heat bringing about the evaporation, the substance from which the water is evaporated must become cooled to a corresponding extent. The cooling effect of evaporation is well known, but its application to the soil is not always realised; clays and even more so undrained soils are cold and late, not only because of their high specific heat, but because they retain so much water which can be evaporated. The drying winds of early spring exercise a great cooling effect whenever the soil moisture is allowed to evaporate freely, hence the importance of establishing a loose tilth, if the seed bed is to warm up the temperatures requisite for germination.

Anything providing a little shelter to check evaporation and break the force of the wind in the spring will have a considerable effect in raising the soil temperature. The dotted curve in Fig. 11 shows the effect of enclosing a plot of the same land with a slight hedge made of spruce fir boughs about 2 feet high. In the morning the temperature of the sheltered plot was below that of the open ground because of the shading from the direct rays of the sun, but as soon as this effect was over it will be seen that the wind break, by checking evaporation, maintained the soil temperature more than 2° above that of the open ground. Sufficient attention is not given in practice to the value of even slight wind breaks for checking evaporation and so raising the temperature of the soil in early spring. The raisers of specially early vegetables, radishes in particular, on a strip of light land close to the sea in Kent are, however, in the habit of breaking the sweep of wind across their fields by erecting temporary fences of lightly thatched hurdles.

Even the stones upon the surface of the land help. In the *Journal of the Royal Agricultural Society* for 1856, an experiment is described in which the flints were picked off the surface of one plot of ground and scattered over an adjoining plot, with the result that the plot with double its usual allowance of stones was three or four days earlier to harvest than the rest of the field, while the plot without stones was a week later still. It will always be noticed how the grass upon a field coated with dung starts earlier into growth, because the loose manure acts as a mulch and protects the soil from the cooling due to evaporation.

Land which is protected from evaporation, and to some extent from radiation, by a layer of vegetation, is always both warmer and less subject to fluctuations of temperature than bare soil.

The warming up of a well-tilled surface soil is increased by the fact that the conduction of heat into the soil below is much checked by a loose condition. A solid body will always conduct heat far better than the same substance in the state of powder, and the more compressed the powder is the better it will conduct, simply because there are more points of contact. Hence a rolled and tightened soil will conduct the heat it receives more rapidly to the lower layers than one which is loose and pulverulent. King has shown that, despite the increased evaporation, there is always a higher temperature below a rolled than an unrolled surface.

A few observations may be given showing the effect of drainage in enabling the sun's heat to raise the temperature of soil. The curves (Fig. 12) show the hourly temperatures of the drained and undrained portions of a peat bog during two days in June (Parkes, *J. R. Ag. Soc.*, 1844, 142), at depths of 7 inches and 13 inches respectively; the sudden rise of temperature




FIG. 12.—Temperatures of Drained and Undrained Bog.

between 3 and 4 P.M. on the second day was due to a thunderstorm, during which heavy rain at a temperature of 78° F. was falling.

The figures in the table below are derived from observations made by Bailey-Denton in 1857 (*J. R. Ag. Soc.*, 1859, 273), on a stiff clay soil situated on the Gault at Hinxworth, the drains being 4 feet deep and 25 feet apart in the drained part. It is noteworthy that the temperature of the air 9 inches above the surface is higher for the drained than for the undrained land, thus supplying further evidence of the cooling effect of evaporation.

MEAN TEMPERATURE °F. AT 9 A.M.

	A.—Land Drained.			B.—Land Undrained.		
	Air.	At 18".	At 42".	Air.	At 18".	At 42".
March	39.4	40.6	41.7	39	38.2	40.3
April	43	46	44.8	42.4	44	43.8
May	52.9	51	48.4	52.7	48.8	47.1
Mean excess over B. .	0.4	2.2	1.2

Effect of Situation and Exposure.

Other conditions being equal, in the northern hemisphere the soil temperatures will always be higher on land sloping toward the southern quadrant than with any other aspect. King found a difference of about 3° F. down to the third foot between a stiff red-clay soil with a southern slope of 18° and the same soil on the flat; Wollny obtained a mean difference of 1°·5 between the north and south sides of a hill of sandy soil inclined at 15°. The chief cause of these differences is the fact that in this country the sun is never vertical, hence a beam of sunlight represented by *xy*, Fig. 13, is spread over an area represented by AB when the ground is

flat ; if the ground slopes to the south, the same beam is spread over the smaller area represented by AC ; if the ground slopes to the north, it is spread over the larger area represented by AD. During the winter half-year, also, the southern slope will have a longer duration of sunlight than the northern slope.




FIG. 13.—Distribution of the Sun's Rays on Southerly and Northerly Slopes.

Though in a general way the temperature both of the air and the soil decreases with elevation above sea-level, yet it is well known that the severest frosts occur locally at the bottom of valleys and hollow places. This is particularly noticeable in the sudden night frosts, characteristic of early autumn and late spring, which are so dangerous to vegetation ; it is usual to find the tenderer plants of our gardens, such as dahlias, cut down by frost on the lower levels long before the gardens on the hill are affected. Spring frosts, again, will often nip the early potatoes in the valleys when the higher lands are untouched. Fruit plantations should not be set in the valleys, for no crop suffers more from these unseasonable snaps of cold ; so clearly is this fact recognised, that in some fruit-growing districts only land above a certain elevation is regarded as suitable for fruit, and commands a higher rent in

consequence. Two causes co-operate in producing the excess of cold at the lower levels. The night frosts in question are always the result of excessive radiation when the sky is clear and the air still. The ground surface loses heat rapidly and cools the layer of air above; the cold air thus produced is denser, and proceeds to flow downhill and accumulate at the lower levels. There is thus a renewal of the air above the higher slopes, and the effect of radiation is mitigated by the inflow of warmer air; at the bottom no change of air is produced and the radiation proceeds to its full effect.

At the same time the vegetation in the valley is generally more susceptible to a frost; the greater warmth by day, together with the extra moisture and shelter, induce an earlier and a softer growth.

The other cause that operates to produce severer frosts in the valleys arises from the fact that frosts, and radiation weather generally, accompany the distribution of pressure known as an "anti-cyclone," during which there is always a gentle downdraught of cold air from the clear sky above. But the circulation of air in an anti-cyclone is always reversed at a certain elevation, so that as one ascends, the downdraught of cold air becomes less and eventually ceases; the mean temperature at the same time rises instead of falling with the elevation.

Observations of the minimum temperature on the grass made at two stations on a gentle slope of the downs at Wye, about a mile apart and differing in level by 100 feet, showed during a period of thirty-six days in February and March 1902 (which was exceptionally calm and mild), a mean difference of 1° in favour of the upper station; but on two occasions the lower thermometer fell to $24^{\circ}\cdot 5$ and $21^{\circ}\cdot 5$, when the upper thermometer was $30^{\circ}\cdot 5$ and $29^{\circ}\cdot 5$ respectively.

The accompanying curves (Fig. 14) show the daily maxima and minima of the air temperatures of 4 feet from the ground for a few days before and after the occurrence of a disastrous late spring frost in May 1902. One station, A, was in a river meadow about 100 feet above sea-level, the second, B, was on a terrace about 50 feet higher and half a mile away; the third, C, was on the flat summit of the down, 500 feet above sea-level and about $1\frac{1}{2}$ mile from the first station. It will be seen that the river-side station gave always the highest maxima during the period and the lowest minima, showing on the one occasion 11° of frost.

Early and Late Soils.

From all the considerations developed above it will be seen that an early soil is essentially a coarse-textured and well-drained one. Such a soil retains little water, thus possessing a low specific heat, and is easily warmed; at the same time the low water content gives rise to less evaporation at the surface, and this great cause of cooling is minimised. The dryness of the soil permits of early cultivation, which, by cutting off the access of subsoil water and diminishing the conduction of heat from the surface, quickens the warming up of the seed bed. The early aeration and warming of the soil promotes the nitrification which is also necessary to growth. If, further, the soil be stony, the conduction of heat from the surface layer into the soil is more rapid, solids being better conductors than powders. Such soils, again, are generally dark coloured, because on the comparatively small surface exposed by the coarse grains the same proportion of humus has a greater colouring effect.

These conditions are generally fulfilled by the alluvial soils bordering the larger rivers; in the




FIG. 14.—Temperatures (Maximum and Minimum) at Various Altitudes.

A = 100 feet. B = 150 feet. C = 500 feet.

neighbourhood of large towns, which are generally situated on a river, they form the typical market-gardening soils, especially as their natural poverty can be alleviated by the large supply of dung which is easily obtainable from the town.

At the same time these soils have their disadvantages; from both their nature and their situation they are subject to rapid changes of temperature; they suffer much from night frosts both in spring and autumn, and dry out easily in the summer, so that some crops do not come to their full growth. Autumn planted vegetables grow away rapidly, and are apt to become "winter proud" and killed by severe weather.

Of course, to ensure the maximum of earliness and freedom from spring frosts, the geographical situation and the climate must be considered as well as the nature of the soil. The neighbourhood of the sea or any large body of water has a great effect in equalising the temperatures and preventing severe frosts; in the British Islands, for example, the earliest potatoes are grown in Jersey, near Penzance, and on other light land along the southern coast of Cornwall, and again, a little later near the sea in Ayrshire. Light land round the coasts of Kent and Essex, which borders, and in some cases is almost surrounded by the sea, is also specially valued for the growth of early vegetables.

The soils naturally retentive of water are late, both because they dry slowly and are rarely fit to work early in the year, and because the high water content keeps their temperature down. Except in long-continued droughts they maintain a supply of water to the plant, their high specific heat keeps them at a comparatively equable temperature and prevents them from cooling down so soon when the summer heats are past. In consequence, the crop is neither forced early

to maturity nor is growth checked so soon in the autumn, the period of development is prolonged until in some cases the season becomes unsuitable for ripening. Many subtle differences may be noticed between the quality of produce grown upon early and late soils; for example, a comparison made by the author of the same variety of apple grown upon adjoining clay and sandy soils showed that the apples from the clay land were smaller and greener, but contained a greater proportion of sugar and acid, and possessed a higher aroma than the apples grown upon the lighter and earlier soil. Wheat grown on the clays is generally of better quality and "stronger" than that yielded by the lighter soils; whereas the lighter soils yield the finer barley, in which carbohydrates and not nitrogenous materials are characteristic of high quality. On a light soil, becoming both warm and dry early in the season, the plant ceases the sooner to draw nutrient material from the soil; assimilation, however, continues after the plant has ceased to feed; finally, maturation—the removal of the previously elaborated material into the seed—begins earlier and can be more thoroughly accomplished. Hence grain from an early soil is, on the whole, characterised by a higher proportion of carbohydrate to albuminoid, always provided that no excessive or premature drying-out has taken place, for that ripens off the grain before the transference of starch has been completed.

It is impossible, however, in the present state of our knowledge to disentangle the effects of the soil proper from the other factors of climate and environment. Thus in considering the composition and quality of grain, while the varying chemical composition of different soils, whether natural or due to manuring, have little effect upon the character of the grain, variations

in the water supply and the sequence of temperature produce potent changes in the product. For example, the wheats coming from regions possessing a "steppe" climate, with rainfall in the growing season followed by increasing desiccation and high temperatures, are generally hard and translucent and possess a high protein content. Typical examples are the Hungarian, Manitoban and some of the southern Russian wheats. On the other hand, wheats grown in climates possessing a winter rainfall, even if followed by a completely dry summer, are soft and mealy, possess a low protein content and yield flour of much lower "strength" from a baker's point of view.

Climate is more potent than any other factor in causing variations in the composition of wheat. Leclerc and Leavett grew the same varieties of wheat in three localities with widely differing climates, and in the next year grew on seed from each locality at all three places, with the following results as regards protein content:—

Year.	Origin of Seed.	Protein in Seed.	Protein in Product grown in		
			Kansas.	California	Texas.
1906	Kansas . . .	16.22	19.13	10.38	12.18
1907	Kansas . . .	19.13	22.23	11.00	16.97
1907	California . .	10.38	22.23	11.33	18.22
1907	Texas	12.18	22.81	11.37	18.21

Thus the seed of Kansas origin containing 19.13 per cent. of protein, when grown in California in 1907 yielded grain only containing 11.00 per cent. of protein; whereas in the same year seed from the same original stock, but grown in California in 1906 and only containing 10.38 per cent. protein, when moved back to Kansas yielded grain containing 22.23 per cent. of nitrogen.

CHAPTER VI

THE CHEMICAL ANALYSIS OF SOILS

Necessary Conventions as to the Material to be Analysed—
Methods Adopted—Interpretation of Results—Distinction
between Dormant and Available Plant Food—Analysis of
the Soil by the Plant—Determination of "Available" Phos-
phoric Acid and Potash by the Use of Weak Acid Solvents.

THE chemical analysis of a soil aims at ascertaining the amount which the soil contains of the various elements necessary to the nutrition of the plant, with a view of either making good the general deficiencies of the soil or of adjusting the supply of plant food to such special requirements of a particular crop as may have been indicated by previous experiment.

The analysis of plants grown under ordinary conditions shows that a comparatively limited number of elements enter into their composition; in the main they are composed of water and certain combustible compounds of carbon, hydrogen, nitrogen, and sulphur. In the mineral residue that is left after the combustible material has been burnt off, will be found potassium, sodium, calcium, magnesium, and a little iron among bases; and phosphorus, chlorine, sulphur, and silicon among non-metallic elements. Manganese in very small quantities occurs in nearly all plants: other elements like lithium, zinc, copper, are found in traces under

special conditions of soil. By pot cultures in the laboratory it can be shown that of the above elements, the carbon, hydrogen, and oxygen are drawn from the atmosphere or the water, and that nitrogen, chlorine, sulphur, phosphorus, among non-metals, and potassium, calcium, magnesium and iron, among metals, are elements indispensable to the plant, and are derived by way of the root from the soil. In view of the above facts it is clearly unnecessary to make an ultimate determination of all the elements present in the soil, which has already been shown to consist largely of sand and various silicates of alumina, etc. These materials constitute the medium in which the plant grows, but do not themselves supply it with any food; they need not, therefore, be estimated chemically.

The chemical analysis of a soil, then, resolves itself into determinations of the nitrogen, phosphorus, potassium, calcium, and (of less importance) of sodium, magnesium, iron, aluminium, chlorine, and sulphur. To these must be added the determination of the carbon compounds of the soil, which have already been touched on under the head of humus, and of the carbonates of calcium and magnesium, which in most soils constitute the bases available for neutralising any acids that may be produced. Having decided upon the elements to be determined it would then be possible to proceed as in an ordinary mineral analysis: the sample of soil would be reduced to such a state of division as would admit of drawing an accurate small sample, and then entirely disintegrated by some such reaction as fusion with ammonium fluoride. But results obtained in this way would give very imperfect information about the soil, for the procedure draws no distinction between material present in the unweathered interior of the stones and

coarser particles, which could not reach the plant for generations, and that which exists as very small particles or as a coating on the larger ones, and is therefore open to attack by the water in the soil. The nutrient material of the soil can only reach the plant in the dissolved state, and in dealing with slightly soluble substances such as constitute the soil, the amount which goes into solution is practically proportional to the surface exposed. But the surface exposed increases as the material is subdivided, one gram of soil in pieces 1 mm. in diameter would only expose one-thousandth of the surface exposed by the same amount of soil in particles 0.001 mm. in diameter, so that to all intents and purposes the stones and coarser particles contribute such a small proportion of the surface of the soil that the material dissolved from them can be neglected.

For these reasons—the small surface exposed by the larger particles and the unweathered nature of the compounds within them—the stones above a certain size are not included in the analysis, nor is any attempt made to bring into complete solution even the selected material. Hence it becomes necessary in soil analysis to accept certain “conventions” as to the preparation of the soil for analysis, the nature of the acid used for solution, and the duration and temperature of the attack; all of which factors so affect the mineral matter going into solution that results are only comparable when obtained in the same way. It must always be remembered that soil analysis is only a relative process, by which soils that are unknown can be compared with others whose fertility has been tested by experience; no means exist of directly translating the results into terms of the crop the soil will carry. The methods of analysis that are indicated

below are those adopted by the members of the Agricultural Education Association in this country: unfortunately, there is no uniformity in the methods pursued even among chemists in the same country, wide as are the variations introduced by the different processes in vogue. For example, an acid such as hydrochloric will dissolve very different amounts of potash from a given soil, according as the soil is treated directly with the acid or first ignited, nor is there any constant relation between the amount dissolved from ignited and from raw soil.

Method of Analysis.

The soil sample is taken, passed through the 3 mm. sieve, and air-dried, exactly as previously described for the mechanical analysis. From the large air-dried sample of "fine earth" a portion of about 100 grams is drawn, and either ground in a steel mill or broken in a steel mortar till it will all pass through a sieve with round holes 1 mm. in diameter. This is done to enable the analyst to draw a fair sample weighing only a few grams: if the "fine earth" which passes the 3 mm. sieve were itself used, it would be impossible to adjust the relative proportions of coarse and fine to correspond with the bulk. It is not uncommon to find coarse particles of carbonate of lime sparsely scattered through the soil when the land has been limed; only by grinding and mixing can this matter become evenly distributed through the soil. On the ground material the following determinations are made:—

- (1) Moisture lost at 100° C.
- (2) Loss on ignition.
- (3) Nitrogen.
- (4) Earthy carbonates.

- (5) Phosphoric acid and potash soluble in strong hydrochloric acid. If necessary, soda, lime, magnesia, oxides of iron, alumina, and sulphuric acid can be determined in the same solution.

(1) About 5 grams are weighed out into a platinum dish or porcelain basin and dried in the ordinary steam oven, the temperature of which is never quite 100° C. If the soil contains much organic matter, it will be difficult to bring it to a constant weight, the material will slowly lose water for weeks. An arbitrary limit of twenty-four hours' drying should be taken.

(2) The loss on ignition should represent the organic matter which is burnt to carbon dioxide and water when the soil is heated in the air, but it is impossible to avoid at the same time driving off some of the water of constitution in the zeolites, kaolinite, and similar hydrated silicates in the soil. It is difficult even to obtain consistent results, because of variations in the temperature and time of the operation. The best plan is to heat the soil, as dried in the previous operation, at as low a temperature as possible, to a barely visible redness, preferably in a platinum dish, for some hours with occasional stirring.

The loss on ignition is wanted as a measure of the organic matter of the soil, but we have no means of estimating the varying part, great with clay soils, that is played by the water of constitution. It is possible to get a better measure of the organic matter by estimating the total carbon in the soil and assuming that the organic matter of the original soil contained about 55 per cent. of carbon. The combustion of a soil by the ordinary method for determining carbon is rather a tedious process even in skilled hands; in dealing with soils it is convenient to effect the oxidation by means of

a mixture of sulphuric and chromic acids, taking care to interpose a tube of heated copper oxide between the flask containing the soil and acids and the apparatus used for absorbing the carbon dioxide, in order to complete the oxidation of some of the products formed. This process can be made to follow the determination of the carbon dioxide evolved by the action of acid alone, the same apparatus and the same portion of soil serving for both.

(3) The nitrogen in 10 to 20 grams of the ground "fine earth" is estimated by Kjeldahl's process. Though there is some nitrate present in the soil, no special precaution need be taken on its account, the proportion it bears to the total nitrogen is so small as to be negligible.

(4) The earthy carbonates of the soil are estimated from the quantity of carbon dioxide, which is evolved on treating the ground "fine earth" with an acid. When the proportion of calcium carbonate is high the determination can be made by the usual gravimetric methods. Scheibler's apparatus for measuring the volume of carbon dioxide evolved is suitable when the proportion of calcium carbonate does not fall below 1 per cent.; below that point some other method must be employed, because all the carbon dioxide evolved goes into solution in the reacting acid. The most exact and convenient method for determining calcium carbonate, especially when the quantity involved is very small, involves the treatment of the soil at room temperatures with dilute hydrochloric or phosphoric acid in a partial vacuum, carbon dioxide free air being afterwards drawn through the mixture in order to wash out the last traces of carbon dioxide (see *Hutchinson & MacLennan, Jour. Agri. Sci.*, 6, 1914, 324). The use of strong acids or heat is found to liberate carbon dioxide from some of

the organic constituents of the soil, especially in acid soils rich in humus. It is not sufficient in such cases to estimate the calcium dissolved by dilute acids from the soil, because there are always present other compounds of calcium, *e.g.*, silicates and sulphates, which are soluble in the acid and would be reckoned as calcium carbonate. The factor that is required is not the calcium, but the amount of carbonate which will serve as a base in the soil and combine with the acids liberated by decay, nitrification, or from some of the artificial manures. To this end it is not necessary to discriminate between the carbonates of calcium and magnesium, accordingly the carbon dioxide evolved is calculated back to calcium carbonate.

(5) For the determinations of soluble constituents 20 grams of the powdered soil are placed in a flask of Jena glass, covered with about 70 c.c. of strong hydrochloric acid, and boiled for a short time over a naked flame to bring it to constant strength. The acid will now contain about 20.2 per cent. of pure hydrogen chloride. The flask is loosely stoppered, placed on the water-bath, and the contents allowed to digest for about forty-eight hours. The solution is then cooled, diluted, and filtered. The washed residue is dried and weighed as the material insoluble in acids.

The solution is made up to 250 c.c. and aliquot portions are taken for the various determinations. The analytical operations are carried out in the usual manner, but special care must be taken to free the solution from silica and organic matter. For phosphoric acid a portion of the solution is evaporated to dryness and ignited at a dull red heat, with occasional stirring for quarter of an hour. The residue is taken up with hydrochloric acid, filtered, again evaporated to dryness, and heated in an air-bath for half an hour at

105°. This residue is then taken up with dilute nitric acid, filtered, and made up to about 50 c.c. Five grams of ammonium nitrate are added, and 50 c.c. of a solution of ammonium molybdate containing 60 grams molybdic acid per litre. The mixture is put aside in a warm place for twenty-four hours, the precipitate is filtered off, and, after washing with ammonium nitrate solution, is dissolved by ammonia into a tared porcelain basin, evaporated to dryness, and gently ignited over an Argand burner. The resulting material contains 3.794 per cent. of phosphoric acid. For the determination of potash the same procedure is followed, but the residue after the second evaporation is taken up with hot water, breaking up the residue with a glass rod during extraction. To the solution 25 c.c. of a solution of chloroplatinic acid containing 0.005 gram platinum per c.c. is added, and the whole gently evaporated over a water-bath till almost dry. It is then thrown on to a filter and washed with alcohol, then washed again with a solution of ammonium chloride which has been saturated with the double chloride of platinum and ammonium, and finally dissolved off the filter paper with a little hot water in a tared basin, evaporated, and weighed. A Gooch crucible is most convenient for handling both the phosphoric acid and potash precipitates. Instead of chloroplatinic, perchloric acid may be used, with equal, if not greater, accuracy (W. A. Davis). The solution in water from the second evaporation is evaporated nearly to dryness after adding 2.5 c.c. of 20 per cent. solution of perchloric acid, the process being carried to the point of evolution of vigorous white fumes. The soluble perchlorates are now taken up by stirring with 20 c.c. of 95 to 96 per cent. alcohol, and after settling the clear solution is poured through a 9 cm.

filter paper, which has been dried at 100° to a constant weight. Ten c.c. of 95 per cent. alcohol containing 0.2 per cent. of perchloric acid is now added, and the insoluble potassium perchlorate transferred by means of it to the weighed filter paper. In washing the last traces of precipitate on to the filter another 20 or 30 c.c. of the alcohol containing perchloric acid are used, and finally the perchloric acid itself is washed out of the filter paper by using a minimum of 95 per cent. alcohol, until the washings do not react with sensitive litmus paper. On weighing, each gram of the perchlorate = 0.3401 K_2O .

The other determinations which may be made in this solution consist of soda, lime, magnesia, iron, alumina, manganese, and sulphuric acid, but in most cases these may be omitted. It is occasionally desirable to examine the soluble salts in the soil; about 200 grams of the fine earth should be successively washed with small portions of hot water by the aid of a filter-pump. In the solution the total solids are determined; they consist, in the main, of the nitrates, sulphates, and chlorides of sodium, potassium, magnesium, and calcium, which can be determined by the usual methods. Of course, the amount of soluble salts to be found in the surface soil at any time is largely regulated by the previous weather; after considerable rainfall the soluble salts are washed down into the subsoil, after long evaporation they are concentrated in the surface layers. The amount of nitrates that is present is further affected by the previous cropping, temperature, and working of the soil, and by the manipulation the soil receives after it reaches the laboratory. Thus the determination of the soil constituents that are soluble in water does not enter into the ordinary routine of analysis, their presence

is affected by so many temporary factors which prevent the comparison of one soil with another.

As, however, the determination of the amount of nitrate present in a soil is often required for other purposes, it will be convenient here to indicate the method to be followed. In the first place, the soil must be analysed either immediately after it has been sampled or after rapid drying with the aid of heat, for the manipulation a soil sample usually receives in the drying, sifting, and other preliminary operations, will cause the production of large quantities of nitrates in soils containing moisture.

A funnel with a large filtering surface, at least 2 inches in diameter, must be taken; Warington originally made use of the inverted upper portion of a Winchester quart bottle with a disc of copper gauze, 2 inches in diameter resting in the neck, but this may be replaced advantageously by a Buchner funnel 6 inches in diameter. In either case the funnel is connected with an exhaust-pump, the disc is covered with a good filter paper wetted, then at least 500 grams of the soil are packed carefully into the funnel and pressed down a little, care being taken to avoid plastering if the soil is clayey. The soil sample as it comes from the field is spread out, roughly crumbled, and mixed; from this the 500 grams or so are taken and weighed before putting on the funnel. Another portion is weighed out and dried in the steam oven, to ascertain the proportion of water in the sample. 50 c.c. of hot distilled water are now poured on the soil, allowed to stand a few minutes, and the pump started. When the liquid has been drawn through, successive small portions of hot water are put on, and the pump started afresh; it will be found possible to wash out practically the whole of the nitrate with 100 c.c. of water.

If the liquid shows any tendency to come through the filter turbid, this can be obviated by adding a few drops of sulphuric acid to the water. In the filtered liquid the nitrates may be determined by reducing with the zinc-copper couple, distilling off the ammonia and determining it either by Nesslerising or by titration, according to its amount. The couple is prepared by dipping half a dozen strips of thin sheet zinc, 6 inches long by $1\frac{1}{2}$ broad, successively into dilute caustic soda, very dilute sulphuric acid, and then into a 3 per cent. solution of copper sulphate, in which they are allowed to remain until they have acquired a good black deposit of copper. They are washed by immersion in water, and finally in ammonia-free distilled water, and placed in a bottle with 200 c.c. of the soil extract and a crystal of oxalic acid. The bottle is kept in a warm place or an incubator at 25° for twenty-four hours before distilling off the ammonia.

The table (Appendix I.) shows the analyses by the method above described of a few typical soils.

It will be seen, as a rule, that the water retained by the soil when air dry, the loss on ignition, and the nitrogen, rise and fall together, because the humus which contains the nitrogen is the most hygroscopic constituent of soils. Clay soils which tend to conserve humus also contain the most constitutional water; this further tends to increase the loss on ignition in their case.

The proportion of nitrogen found ranges from 0.5 per cent. in very rich pasture soils down to below 0.1 per cent. on light arable soils, it is rarely up to 0.2 per cent. in arable soils, and the warmer, the more open, and more worked the soil is, the less will be the proportion of nitrogen. In the fertile hop-gardens of East Kent the percentage of nitrogen is rarely as much as 0.2 per cent., despite the great dressings of nitrogenous manure that are annually applied.

The proportion of phosphoric acid in soils is not so variable as the proportion of nitrogen; it ranges from about 0.06 per cent. to 0.2 per cent.; the lower amounts occur generally on the sands and clays, the higher on loams and soils well provided with calcium carbonate.

The proportion of potash shows extreme variations, a clay soil may yield one per cent. of potash to strong hydrochloric acid, a sand only one-tenth as much. It has already been pointed out that "clay" is chiefly the result of the weathering of feldspars and kindred minerals containing potash; this weathering is never chemically complete, so that all soils containing any considerable admixture of clay are necessarily rich in potash. The amount dissolved out by hydrochloric acid is also somewhat of an accidental figure, as it depends very much on how far the previous treatment of the soil has forwarded the weathering process, for there remains in all soils rich in potash much material that will not yield potash to strong hydrochloric acid even after forty-eight hours' digestion. For example, the soil from one of the plots in the Broadbalk wheat-field at Rothamsted only yielded 0.5 per cent. of potash to hydrochloric acid, but when completely broken up by ammonium fluoride it was found to contain 2.26 per cent. of potash.

Of all the soil constituents calcium carbonate shows the widest fluctuations; it may constitute 40 or 50 per cent. of some of the thin soils resting on the chalk, or it may sink on some of the sands and clays to such small proportions as only to be detected by the most refined analysis.

The importance of the calcium carbonate lies not in the calcium that it supplies for the nutrition of plants, but in that it acts as the chief base, maintaining the neutrality of the soil. Many plant diseases,

like the slime fungus which causes "finger-and-toe" in turnips, etc., are only prevalent when the soil is losing its neutral condition, and are not found when a sufficiency of calcium carbonate is present. The normal changes in a soil are brought about by bacteria, which only flourish when the medium is neutral or very faintly alkaline; as soon as the soil becomes acid the bacterial actions are largely suspended, and in their place moulds and other micro-fungi become predominant. For reasons already stated (p. 50), it is impossible to determine whether a soil is really acid or not by its reaction to litmus paper. When, however, the filtered extract from a soil turns blue litmus red the soil may be regarded as acid. Many soils, however, which fail to give a certain acid indication are in need of lime, and Hutchinson and MacLennan have devised a method for determining these lime requirements which appears to agree very well with the behaviour of the soils in the field (*Jour. Agric. Sci.*, 7, 1915, 75). The soil is shaken with a solution of calcium bicarbonate of approximately N/50 strength for three hours and the amount of calcium carbonate absorbed is measured by titration. The amount of lime thus absorbed, calculated with respect to the weight of soil used, gives the optimum dressing of lime which should be applied to the land and will there bring about neutrality. An excess of caustic lime may cause harm, inducing certain effects of partial sterilisation and a too rapid exhaustion of the reserves in the soil to the detriment of succeeding crops, but this action does not take place if an excess of lime in the form of carbonate is supplied.

Interpretation of the Results of a Soil Analysis.

Though much may doubtless be learnt by a comparison of the analysis of a given soil with the analysis

of others whose fertility has been proved by experience or by actual manurial experiments, there are yet many considerations which prevent much weight being attached to the results thus obtained.

A comparison of the total amount of any of the elements of plant food in the soil with the amount that is withdrawn by an ordinary crop shows at once that even in the poorest soils there is sufficient material for something like a hundred average crops.

The density of the surface soil has already been discussed; it will be sufficiently accurate for our purpose if we consider that the top 9 inches of one acre of an ordinary arable field weighs 2,500,000 lbs. On this basis, and without taking into account the fact that the roots of most cultivated plants range far deeper than 9 inches, there is yet present about 2500 lbs. per acre of nitrogen, potash, and phosphoric acid in a soil containing only 0.1 per cent. of these constituents, which is about the lower limit usually found. The following table shows the amounts of these food materials—nitrogen, phosphoric acid, and potash—which are taken from the soil by an average crop grown in rotation:—

Lbs. per acre.	Wheat.	Swedes.	Barley.	Clover.
Nitrogen	41.7	94.0	49.0	159.3*
Phosphoric Acid .	20.5	24.1	20.7	28.2
Potash	3.56	93.5	35.7	102.4

* Partly derived from the atmosphere.

It is clear from a comparison of this table with the quantities previously specified, that even the poorest soil contains the nutrient material required by any ordinary crop many times over, yet we know that crops respond vigorously to dressings of manure which only add a fraction to the plant food already stored in the soil.

For example, a wheat crop on poor soil would often be doubled by the use of 2 cwt. of nitrate of soda per acre, *i.e.*, by the addition of 35 lbs. of nitrogen in nitrate of soda to a soil that already contained in the top 9 inches more than 2000 lbs. per acre. Again, 4 cwt. per acre of superphosphate, containing about 60 lbs. of phosphoric acid, will be necessary in the usual rotation to secure a good swede crop, though there may be already 2000 to 3000 lbs. of phosphoric acid in the soil. We are then driven to conclude that the nitrogen, potash, and phosphoric acid are present in the soil in some other mode of combination than the form in which they exist in manures: so that although they may be in the soil they are in such a state as to be very partially of service to the growing plant. Further evidence of the enormous stores of plant food in the soil and the comparative slowness with which they can be utilised may be obtained by considering the results obtained at Rothamsted, where on one plot wheat has been grown continuously without manure for sixty-four years (to 1907). The average yield from this plot was for the first twenty years, 1844-63, 16.3 bushels of grain and 15.1 cwt. of straw; 11.6 bushels of grain and 9.3 cwt. of straw for the next twenty years, 1864-83; and 12.3 bushels of grain and 8.7 cwt. of straw for the third period of twenty years, 1884-1903. It is calculated that during the last fifty years there have been removed from this plot about 900 lbs. per acre of nitrogen, 470 of phosphoric acid, and 760 of potash, *i.e.*, about 18, 9, and 15 lbs. per acre per annum respectively; yet from analyses of a sample taken in 1893 the surface soil to a depth of 9 inches still contained 0.11 per cent. of nitrogen, 0.114 per cent. of phosphoric acid, and 0.38 per cent. of potash soluble in strong hydrochloric acid, or 2750, 2850, and 9500 lbs. per acre respectively. The soil must therefore be re

garded as possessing most of its plant food in states of combination that cannot be utilised by the plant, and these forms slowly pass, by weathering and other changes, into material which is available for the crop. The plant food of the soil represents so much capital, and, as in many another business, but a small proportion of the capital is liquid at any given time: it is largely the object of cultivation to effect such a turnover of the capital as will liquidate some of it in a form available for the nutrition of the crop.

In the old systems of agriculture, before the land was enclosed, the whole crop was grown out of capital, nothing but labour was put into the soil: in which connection it is interesting to note that the original meaning of manure was to work by hand.*

It becomes important, then, to attempt to discriminate between the various forms in which the nitrogen, potash, and phosphoric acid may be present in the soil, according as they are soluble, or likely in a short time to become sufficiently soluble to reach the crop. In the case of nitrogen we know that of the various compounds such as proteins and protein residues, amides, ammonia salts, and nitrates which can be detected in the soil, only the two latter enter the plant, but that, by processes of fermentation, all of the other compounds will eventually pass into the state of nitrate. Of the immediately soluble nitrogen compounds—nitrates, nitrites, and ammonia—a very small amount, varying from 5 to 200 lbs. per acre, is ever present in the soil at any given time, though it is constantly being renewed by fermentation processes.

Phosphoric acid also exists in the soil in many distinct compounds: in combination with carbon, etc.,

* Cf. Defoe, *Robinson Crusoe* (1719)—“The ground that I had manured or dug up for them was not great.”

is found in nuclein and lecithin, which in a more or less humified condition are found among the plant and animal residues: it also occurs as phosphate of the sesquioxides of iron and alumina; as tribasic, and probably also as dibasic phosphate of lime. Of these compounds the latter are undoubtedly the most soluble in either pure water or the carbonic-acid-charged water of the soil, but much must depend on the physical condition, as well as on the chemical combination, in which the material exists. For example, when using tribasic phosphate of lime as a manure, the softer phosphates, such as leamed bone flour, are more effective than the chemically milar but harder material in ground rock phosphate. Almost invariably phosphoric acid is less abundant in the subsoil than in the surface, where it has been accumulated as a residue from the decay of previous vegetation.

It is not so easy to classify the various compounds of potash existing in the soil: we know that as felspar passes into kaolinite there are intermediate stages of weathering in which the potash is gradually becoming more soluble in soil water, but it is impossible to isolate or classify the various hydrated silicates containing potash that must exist. Potash, again, which has once been dissolved, is caught and retained by the soil in various ill-defined compounds, some of which must reach the crop more rapidly than others. The amount of potash found bears a fairly close relationship to the amount of the clay fraction and the proportion of alumina obtainable from the soil. As already shown (p. 42), the percentage of potash increases rapidly in the finest fractions of the soil, which would seem to show that the clay contains a definite group of silicates attacked by the acid. There is, however, always potash in the soil that is not extracted by the strong hydro-

chloric acid used in analysis, but is only liberated when the soil is completely brought into solution by fusion with other alkalis or by treatment with hydrofluoric acid. As a rule the analysis extracts more potash from the subsoil than from the surface soil, whence it has to some extent been removed by greater weathering and solution.

The work, then, of soil analysis must be extended to include some investigation of the condition of the plant food in the soil, as well as its absolute quantity: it is not enough to determine what constituents are present with the view of making good the deficiencies, because there is always more than enough for many crops; inquiry must be rather directed towards finding how much is likely to reach the crop. The attempt to discriminate between the total and what may be termed the available plant food in the soil, *i.e.*, that which is in a form the crop can immediately utilise, has been made in two ways—by using the growing plant as an analytical agent, or by attacking the soil with very dilute acids, whose action is akin to the natural solvent agencies at work when the plant is growing. The former process proceeds upon the assumption that any given plant has a certain average composition which it will acquire when freely supplied with all the elements of nutrition; if this plant be grown upon a soil deficient in one particular, that deficiency will be reflected in the analysis of the plant when fully grown. It is thus necessary to select a standard plant and grow it under normal conditions of manuring to ascertain the proportion that nitrogen, phosphoric acid, and potash usually bear to the ash. The selected plant is then grown upon the soil in question, gathered at the appropriate stage and analysed, when the composition of the ash, as compared

with its composition under normal conditions, should give indications of the state of the soil. Various disturbing factors come into play; for example, the presence in the soil of large quantities of a non-essential material like calcium sulphate or sodium chloride lowers the proportion that potash bears to the total ash without necessarily indicating any want of potash; again, a deficiency of nitrogen is more seen in a general stunting of the whole development of the plant than in a comparative poverty of nitrogen in the final growth. But by selecting suitable test plants, valuable indications can be obtained as to the need or otherwise for specific manuring. As a rule, cereals are unsuitable test plants, since they are well able to satisfy their requirements for mineral nutrients from comparatively impoverished soils; the straw of barley, however, shows considerable variations from which the condition of the soil as regards its supply of phosphoric acid and potash can be interpreted. The phosphoric acid in the ash of barley straw will vary between 2 and 4 per cent. and the potash between 6 and 24 per cent., and as the straw of barley grown without special manuring can readily be obtained, it forms a convenient test plant. The most sensitive test plants are provided by roots—swedes for estimating the phosphoric acid, and mangolds for estimating the potash in the soils on which they have been grown. The phosphoric acid in the ash of swedes has been found as low as 9 per cent. when the soil was one that responded readily to phosphatic manures, rising to 16 per cent. when the soil was one that required no phosphatic manure. Similarly, the potash in the ash of mangolds will vary between 12 and 40 per cent.

The method which is now very largely employed to determine the mineral plant food in the soil that may be regarded as immediately "available" for the

crop, consists in attacking the soil with a very dilute acid, whose action shall be comparable with the natural solution processes bringing nutriment to the plant. The mineral matter finds its way by osmosis into the plant in two ways: either from the natural soil water, or from the more concentrated solution formed in immediate proximity to the root-hairs by the attack of the excreted carbon dioxide upon the soil particles.

The natural soil water is constantly dissolving small quantities of phosphoric acid, potash, and other materials, in which it is aided by the carbonic acid it also contains; as this water passes by osmosis into the root-hairs it will carry with it the dissolved material, with the exception of any particular ion or radicle which has already attained in the cell sap a higher concentration than it possesses in the external soil solution. But if the soil water alone brought the mineral matter with it, not enough enters the plant to account for the observed facts. For example, the growth of a crop of a ton and a half of clover hay requires the transpiration through the leaves, and therefore the absorption at the root, of about 400 tons of water (see p. 101); the same crop would also contain about 50 lbs. of potash. If, then, the crop derived all its mineral matter by the simple inflow of the soil water into the root, the 50 lbs. of potash must have been originally dissolved in the 400 tons of water that passed through the crop, which means that the soil water contained as much as 0.006 per cent. of potash, a greater concentration than is observed in humid climates. In fact, the particular ions or radicles concerned in nutrition enter the root faster than the water does; they diffuse through the cell-wall because the sap within is maintained in a less concentrated state as far as they are concerned than the external

soil water, because they are constantly being withdrawn from solution by the living protoplasm of the cells.

It has been supposed that solvent action of the soil water is also assisted by the cell sap of the root-hairs, which is always distinctly acid in its reaction; these root-hairs are always very closely in contact with soil particles, and some of the acid has been supposed to diffuse outwards through the cell-wall. Sachs has shown that a polished slab of marble is etched wherever the fine roots of a plant came in contact with it, and on the strength of this and similar experiments, the cell sap has been regarded as a factor in bringing the minerals of the soil into solution for the plant. All the solvent actions, however attributed to the cell sap, can be brought about by the carbon dioxide which is always being excreted by the root, and more critical experiments seem to negative the opinion that any fixed acids pass outwards through the cell-wall of a living plant, at any rate after it has passed the seedling stage.

The soil solution existing in the films of water surrounding the soil particles is thus the nutrient medium upon which the plant feeds, and if it could be readily extracted from the soil it would probably provide the best analysis of the soil as a means of determining its richness or otherwise in available plant food. But it is difficult to obtain by pressure or other mechanical means the true soil solution from the soil, and any extraction by water or otherwise will at once upset the equilibrium existing between the normal soil solution and the absorptive soil colloids with which it is in contact. Still, an extract of the soil with pure water does show such a variation in its content in phosphoric acid and potash as would be expected from the known character of the soil. For example, a series of extracts was made from certain

of the Rothamsted soils, the soil in its undried state being worked up with water in the proportions of 20 soil and 35 water. The solutions obtained showed the following compositions, the amounts extracted by dilute and strong acid being appended for comparison.

Field and plot.	Phosphoric Acid.				Potash.			
	Annual supply as manure, 68 years.	In soil extract.	Dissolved by strong acid.	Dissolved by 1% citric acid.	Annual supply as manure, 68 years.	In soil extract.	Dissolved by strong acid.	Dissolved by 1% citric acid.
Wheat.	lb.	Per million.	Per cent.	Per cent.	lb.	Per million.	Per cent.	Per cent.
3	0	0.656	0.114	0.0078	0	3.64	0.220	0.0032
10	0	0.881	0.123	0.0074	0	3.55	0.240	0.0032
11	60	3.839	0.197	0.0405	0	3.88	0.197	0.0032
7	60	3.938	0.195	0.0547	100	26.22	0.262	0.0232
2	46	4.838	0.215	0.0560	60	29.85	0.285	0.0384
Barley.								
10	0	0.525	0.099	0.0055	0	3.40	0.183	0.0036
2A	60	3.900	0.173	0.0425	0	3.88	0.248	0.0023
3A	0	0.808	0.102	0.0081	100	30.33	0.257	0.0407
4A	60	4.025	0.182	0.0500	100	24.03	0.326	0.0298
7/2	46	4.463	0.176	0.0447	60	26.45	0.167	0.0321

Whatever the theories which have been formed as to the manner in which the mineral constituents of the soil pass into solution for the plant, it is improbable that the conditions can be reproduced in the laboratory, and for the practical purposes of analysis the desideratum is a solvent that will dissolve the class of material which is found by experience to reach the immediate crop, but which will not touch the same material should its state of combination or physical condition be such as to render it unavailable for the plant. Various solvents have been proposed: for example, Dehérain showed that dilute acetic acid, while dissolving some phosphoric acid from

ordinary soils, was incapable of extracting any from a particular soil which yielded very poor crops unless manured with superphosphate, though it contained 0.1 per cent. of phosphoric acid soluble in strong hydrochloric acid. Hence he concluded that dilute acetic acid forms a solvent only capable of attacking the available phosphoric acid. A solution of carbonic acid has been suggested as akin to the natural soil water; other solutions have been employed because they will dissolve certain of the compounds of phosphoric acid in the soil, but not all—the calcium phosphates, for example, but not the phosphates of iron and aluminium; other solvents, again, are recommended as akin to the acid cell sap. Analysts in this country have, however, generally agreed to use the 1 per cent. solution of citric acid proposed by Dyer in 1914, which gives results capable of interpretation in accord with what is known of the soil, either from its past history or by cropping experiments.

The method of conducting the analysis is as follows:—200 grams of the "fine earth" that has passed the 3 mm. sieve, in its air-dried state, is placed without any further grinding in a dry Winchester quart bottle with 20 grams of pure crystallised citric acid and 2 litres of water. The bottle should either be one previously used for the storage of strong acids or should have a preliminary soaking in dilute hydrochloric acid. The mixture of soil and dilute acid is thoroughly shaken from time to time, as often as may be convenient, during the seven days the solvent action is allowed to proceed. After seven days the solution is filtered, and two aliquot portions of 500 c.c. each are evaporated to dryness and ignited to get rid of the citric acid and other organic matter. The residues are dissolved in hydrochloric acid, again evaporated, and heated for a time to 105° C. to

render all the silica insoluble. In one portion the phosphoric acid, and in the other the potash, are determined by the processes previously described. The time of extraction may be shortened to twenty-four hours if the bottle be put in a good end-over-end shaking machine which will keep the soil and the solvent thoroughly agitated.

An examination of the citric acid solution shows that all the compounds of phosphoric acid that have been indicated as existing in the soil are more or less attacked; at any rate, the resulting solution contains organic matter and salts of aluminium and iron, in addition to calcium. It has been suggested that the varying amounts of calcium carbonate contained by soils will much affect the material dissolved by the citric acid, some of which becomes neutralised by the calcium carbonate. But though the amount of phosphoric acid dissolved from a given soil by the citric acid solution will be diminished if the calcium carbonate in the soil is increased, a very similar reduction will be effected in the natural processes of solution of the soil phosphates under field conditions. No attempt should be made to add an extra amount of citric acid to combine with the calcium carbonate; secondary solvent actions are set up both by the carbon dioxide evolved and by the calcium citrate formed, whereby the real comparative basis of the method of analysis is destroyed.

It must not be supposed that the citric acid solution, nor indeed any of the dilute acid solvents that have been proposed for this purpose, are real differential solvents, which extract the material in the soil which is available for the plant and leave untouched whatever is combined in some other form. In reality, as soon as the acid has been for a sufficient time in contact with the soil a state of equilibrium is attained between the phosphoric acid,

for example, that remains in solution and that which has been reabsorbed by the soil. All acids begin by dissolving the same amount of phosphoric acid, the amount depending upon their strength and the nature of the phosphoric acid compounds in the soil, but the precise equilibrium that is afterwards attained is determined by the absorptive power of the soil for phosphoric acid in the presence of the particular acid employed. If the citric acid solution is filtered off after it has extracted all the phosphoric acid it can, and a second portion of solution is added and the soil extracted afresh, then more phosphoric acid will go into solution, the amount being smaller than before but still considerable. A third, a fourth, and even a fifth extraction does not remove from the soil all the phosphoric acid that will go into solution in the dilute citric acid solution. Thus it is impossible to say that the dilute citric or any other acid dissolves out and measures the "available" phosphoric acid or potash; it does, however, provide a figure indicating the comparative rate at which the soil is likely to yield up its nutrient constituents to the normal solvent actions going on in the soil. The results, then, of this method of analysis are not to be regarded as absolute amounts, but as empirically obtained figures which must be interpreted in the light of experience. The type of the soil plays a part; for example, a quantity of citric acid soluble phosphoric acid that would indicate poverty in a strong loam or in a soil rich in organic matter like an old pasture, would be ample for ordinary crop purposes if the soil were light and sandy. Again, the crop must be taken into account; a percentage indicating enough available phosphoric acid in the soil for wheat or man-golds would indicate deficiency when the swede crop came round.

In certain cases, by continuing the extraction with citric acid until the amount going into solution at each extraction becomes approximately constant at some low figure, it is possible to differentiate between the phosphates in the soil that are easily soluble and may therefore be termed "available" because they possess a comparatively high solubility factor, and other phosphates which would yield, under natural conditions, solutions too dilute to nourish the crop efficiently.

For example, the following table shows the amounts of phosphoric acid dissolved by successive extractions of certain Rothamsted soils with 1 per cent. citric acid solution, from which it will be seen that at about the fifth extraction the quantity dissolved begins to approach a constant.

PHOSPHORIC ACID, MGMS. PER 100 GRAMS SOIL.

Field.	Plot.	Treatment each Year.	EXTRACTION.					
			1st.	2nd.	3rd.	4th.	5th.	6th.
Broadbalk	3	Unmanured	6.4	6.8	3.9	3.0	2.5	...
"	5	64 lbs. P_2O_5 , no Nitrogen	69.0	28.0	11.3	7.3	4.5	2.3
"	7	64 lbs. P_2O_5 , 86 lbs. N. .	56.1	22.8	8.9	6.5	4.4	4.4
"	8	64 lbs. P_2O_5 , 129 lbs. N. .	46.3	18.9	7.8	5.3	4.0	3.0
"	10	86 lbs. N. only . . .	7.7	5.2	3.3	2.7	2.7	2.7
"	2	Dunged	49.3	15.3	7.5	6.0	4.4	...
Hoos	1AA	43 lbs. N. only . . .	6.3	3.5	2.2	1.9	2.0	1.2
"	2AA	64 lbs. P_2O_5 , 43 lbs. N. .	52.2	21.2	8.9	6.5	3.8	2.9
"	3AA	43 lbs. N. and Potash .	6.3	2.7	2.3	2.1	1.9	1.5
"	4AA	64 lbs. P_2O_5 , 43 lbs. N., Potash	53.5	10.6	6.4	4.9	4.5	3.8

The successive amounts going into solution in the first four or five extractions of the soil from the plots which had received soluble phosphoric acid every year are found to be decreasing in a logarithmic series, and this may be supposed to indicate that the solvent is

dealing with only one class of material, which is entirely removed at about the fifth extraction. After the fifth extraction there only remains the more insoluble classes of phosphates which form the main stock in the soil. The unmanured plot and that which has received dung do not show the same regular decrement, indicating that the solvent is each time dealing with a more complex mixture of phosphates successively going into solution. This conclusion is strengthened when the total amount of phosphoric acid dissolved in five extractions is compared with the amount known to have been applied to the land during the period the plots have been under experiment, after deduction has been made of that which is also known to have been removed in the crop.

PHOSPHORIC ACID IN ROTHAMSTED SOILS.

Field.	Plot.	DISSOLVED IN FIVE EXTRACTIONS.		Supplied in Manure.	Removed in Crop.	Surplus.
		Per cent.	Lbs. per acre.			
Broadbalk	3	0.0226	565	0	550	- 550
"	5	0.1201	3000	3960	790	3170
"	7	0.0987	2470	3810	1370	2440
"	8	0.0823	2055	3810	1520*	2290
"	2	0.0825	2060	4780	1650	3130
Hoos	1AA	0.0159	400	0	555	- 555
"	2AA	0.0926	2315	3390	1200	2190
"	4AA	0.0799	2000	3390	1240	2150

* Approximate estimate, since the crop has rarely been analysed.

It will be seen from the above table that the amount of phosphoric acid dissolved by the five extractions agrees closely with the surplus left by the manuring in all the cases where the phosphoric acid has been put on as soluble mineral superphosphate. This is not the

case, however, for the plot manured with dung, which contains a considerable proportion of difficultly soluble phosphate.

It should not be supposed that the whole of the so-called "available" phosphoric acid or potash will be removed by the crop; even the minimum of 0.01 per cent., soluble in citric acid, which has been suggested as marking the limit of fertility, means about 250 lbs. per acre in the surface layer 9 inches deep: and few crops will take away as much as 50 lbs. per acre of phosphoric acid or 150 lbs. per acre of potash. No crop searches the soil so thoroughly for food as does the solvent acid: if we assume that the roots themselves by their excretion of carbon dioxide effect some of the solution, it is obvious that they come in contact with but a small proportion of the soil particles; nor can the soil water, limited in amount and moving slowly, attack the soil with the vigour displayed by an acid which is continuously shaken with a comparatively small proportion of soil. Even in the case of material so essentially "available" as a manure soluble in water, the whole of the manure applied is never recovered in the crop; *e.g.*, in the experiments with wheat at Rothamsted, only 73 per cent., and with mangolds 78 per cent., of the nitrogen supplied as nitrate of soda has been recovered in the crop, though there was an abundant supply of the other manurial constituents. In the same way, on the plot with an excess of nitrogen, there was recovered only 36 per cent. of the phosphoric acid supplied as superphosphate, and 50 per cent. of potash supplied as sulphate of potash.

In other words, the "available" plant food in the soil represents not that which the succeeding crop will remove, but that which it can draw upon: how much it will acquire will depend on a variety of factors, such

as the nature of the plant, the texture of the soil, the supply of water, and other necessities of nutrition.

No method akin to solution in dilute citric acid has yet been devised for determining what proportion of the nitrogen reserves in the soil is likely to be available. The conversion of the nitrogenous matter of the soil into soluble nitrates, in which form nitrogen enters the plant, is a biological process which is influenced by a number of conditions, such as temperature, degree of moisture and aeration of the soil, the mechanical treatment it receives, all impossible to predict.

Some idea of the condition of the organic matter and the readiness with which it is likely to change, may be obtained by a determination of the humus soluble in dilute ammonia and the percentage of nitrogen in this humus, or again by a study of the ratio of carbon to nitrogen in the organic matter as previously indicated (p. 51). In order to determine the soluble humus, 20 grams of the soil are digested with enough 1 per cent. hydrochloric acid to dissolve all the calcium carbonate, thrown upon a filter, washed with a little more of the hydrochloric acid and then with water until neutral. The soil is then washed off the filter into a bottle with a 4 per cent. solution of ammonia and shaken for twenty-four hours, after which the bottle is left to stand until the bulk of the inorganic matter of the soil has settled, 150 c.c. are pipetted off and evaporated to dryness over the water-bath, weighed and ignited, a deduction being made of the inorganic matter remaining after ignition.

To determine the nitrogen content of the humus a second 150 c.c. are placed in a Kjeldahl flask. Two or three grams of magnesia are added and the whole evaporated to dryness to get rid of the ammonia in the solution, after which the contents of the flask are digested with sulphuric acid in the usual manner.

Valuable as these determinations may become in judging a soil, a sufficient body of data do not as yet exist to enable them to be interpreted with precision.

In the analysis of a soil, without doubt the most important figure is the proportion of calcium carbonate, for on that must be based the decision not only of whether liming is necessary, but what class of artificial manures should be employed. Where the calcium carbonate is scanty, manures like superphosphate and sulphate of ammonia should never be employed, but basic slag or some neutral phosphate on the one hand, and nitrate of soda as a source of rapidly acting nitrogen on the other. The texture of the soil, the rapidity with which decay and nitrification of organic matter take place, freedom from fungoid diseases, all depend on an adequate proportion of calcium carbonate in the soil, say from half to one per cent.; so that of all the determinations this is the most important.

The determinations of the loss on ignition, the nitrogen, and possibly the humus, give the analyst an idea of the reserves of organic matter in the soil; judged in conjunction with the mechanical analysis and the proportion of calcium carbonate, an opinion can be formed as to the condition of the soil and how far these reserves are likely to be brought into play by cultivation. An opinion may, again, be formed as to the need for organic manures to increase the humus content of the soil, or whether fertility is likely to be maintained with purely mineral manures.

A consideration of the available phosphoric acid and potash will give the analyst an idea of the immediate need or otherwise of mineral manuring; the proportions these bear to the "total" phosphoric acid and potash give him grounds for deciding whether the lack is only temporary or real. In the former case measures may

be taken to liberate some of the reserves, as by the judicious use of lime or of organic manures which will generate carbonic and other acids within the soil.

Rainfall and water supply are important factors in determining the choice of phosphates; basic slag proves less useful than superphosphates on dry soils; but at least as useful on moister soils or under higher rainfall. The amount of calcium carbonate in the soil is not the determining factor, but the water supply; if, as often happens, a chalky soil is dry, superphosphate will prove the more useful; where the rainfall is greater, basic slag is as good. In all cases where much purchased food is fed upon the land, phosphates are of advantage to the succeeding crop, and on all wet cold soils, a free supply of phosphates aids in the early maturity and ripening of the crop.

The need of soils for potash depends even more upon the water supply. On a dry soil crops are likely to cease growing, and ripen much faster than in a moister district. Now, potash manures tend to prolong the vegetative development of a plant, and in a dry district, or on a dry soil, will keep it growing after it would otherwise have stopped; in consequence, they give increased, if later, crops. Other things being equal, dry soils are more likely to respond to potassic manuring than others better supplied with moisture, but no richer in available potash. In reclaiming the very dry heaths of the Eastern Counties, the production of profitable crops depends upon a liberal and regular use of potash manures.

No sequence has ever been traced between the content of the soil in oxide of iron and its fertility. The red soils of Great Britain, which are often of high repute, may show less than the usual proportion of

ferric oxide on analysis; they owe their good qualities to their physical constitution and texture.

Such further questions as the presence of harmful substances, or even of an excess of more normal constituents of the soil, must be considered by the analyst, but will be dealt with in a later section.

In some cases it will be possible by a chemical analysis to pronounce a given soil to be unsuited to a particular crop: as a rule, however, it is not its chemical composition which fits the land for a particular crop, but its mechanical texture, water-bearing power, drainage, etc. In most cases the soil can be adjusted to the crop by manure, though the process may be unsound from an economic standpoint, but no expenditure can ever rectify unsatisfactory texture, *e.g.*, convert a light sand into good wheat land.

Even in considering the chemical analysis of a soil, no hard-and-fast rules can be laid down, the judgment and experience of the analyst must come into play in deciding how far the deficiency or excess of one constituent is likely to affect the action of some of the others: and again, how far the texture, the aspect, and other factors that can only be ascertained *in situ*, will exercise an influence upon the enormous reserves of plant food contained in every soil. In any case the chemical analysis of a single soil is of very little value as a guide to the treatment of the soil in practice. Exceptional deficiencies may be revealed, particularly as regards calcium carbonate or sometimes as regards phosphoric acid, but, as a rule, the figures obtained are among the middle values which of themselves possess no significance. What the analyst requires is a series of analyses which characterise the soil type and indicate the limits within which the natural variations fall. If, further, the normal behaviour of the soil type towards

cultivation and its response to particular fertilisers is known, then deductions can be drawn from the departures from type of the particular soil. Thus the chemical, as indeed the mechanical analysis of soil, must begin by studying and establishing the soil types, by a soil survey in fact, in which the collected analyses are correlated with the observed behaviour of the soils in the field and under experiment, before much information can be extracted from the analysis of a particular soil. Soil analysis is in fact a method for the expert engaged in studying soils in general rather than a means at present for answering questions about his soil which may be asked by the individual farmer.

CHAPTER VII

THE LIVING ORGANISMS OF THE SOIL

Decay and Humification of Organic Matter in the Soil—Alinit—
The Fixation of Free Nitrogen by Bacteria living in Sym-
biosis with Leguminous Plants—Soil Inoculation with Nodule
Organisms—Fixation of Nitrogen by Bacteria living free in the
Soil—Nitrification—Denitrification—Protozoa—Iron Bacteria—Fungi of Importance in the Soil: Mycorrhiza, and the
Slime Fungus of "Finger-and-Toe."

THE soil is the seat of a number of slow chemical changes affecting the organic material it receives: residues of an animal or vegetable nature, when applied to the soil, are converted into the dark-coloured complex known as "humus," which becomes eventually oxidised to carbonic acid, water, nitric acid, and other simple substances serving as food for plants. These changes, at one time regarded as purely chemical, are now recognised as dependent upon the vital processes of certain minute organisms, universally distributed throughout cultivated soil, and subject to the same laws of nutrition, multiplication, life and death, as hold for the higher organisms with which we are more generally familiar.

The microscopic life of the soil, roughly classed as protozoa, fungi and bacteria, is vast, and has been very inadequately explored as yet: certain types of change

in the soil materials have, however, been associated with particular organisms or groups of organisms, and many of these changes are of fundamental importance in the ordinary nutrition of plants. The organisms in the soil which so far have received the chief attention are those concerned with the supply of nitrogen to the plant. Certain organic compounds of nitrogen, chiefly of a protein nature, become gradually broken down by the action of soil bacteria into simpler compounds, *e.g.*, into amino-acids, and then into ammonia, which latter substance is seized upon by other organisms and oxidised successively to nitrous and nitric acid. As nitric acid is generally the form in which the higher plants obtain the nitrogen they require, the fertility of the soil is wholly bound up in the maintenance of this cycle of change. Under certain conditions the work of other organisms intervenes, and the nitrogen compounds, instead of becoming nitric acid, are converted into free nitrogen gas, and are lost to the soil. *Per contra*, another group of organisms possesses the power of "fixing" free nitrogen, *i.e.*, of taking the gaseous element nitrogen and combining it with carbon, hydrogen, oxygen, etc., into forms available for the higher plants. Such organisms sometimes act when living in "symbiosis" with plants possessing green carbon-assimilating tissue: the two form a kind of association for mutual support, the bacteria deriving the carbohydrate which they must consume from the higher plant supplied by them with combined nitrogen.

Other symbiotic processes have been traced in the soil, and may yet be made to play an important part in the nutrition of field crops. Indeed, a number of tentative trials have already been made with the view of increasing the productiveness of the soil by introducing either useful organisms that were wanting, or

improved types to replace already existing kinds of less effective character.

Lastly, Russell and Hutchinson have shown that the numbers of bacteria in the soil are limited by the presence of certain higher organisms—protozoa which feed upon the bacteria. If these protozoa are killed off the bacteria multiply exceedingly; there is a corresponding speeding up of the processes of breaking down the organic residues to ammonia and nitrates, and with the greater amount of available nitrogen thus set free a temporary increase in the fertility of the soil results.

The Changes of Organic Matter in the Soil.

The surface layer of soil is constantly receiving additions of organic matter, either leaves and other débris of vegetation covering the ground, together with the droppings of animals consuming that vegetation, or dung and other animal and vegetable residues which are supplied as manures to cultivated land. These materials rapidly change in ordinary soil, losing almost immediately any structure they possess, becoming dark-coloured humic bodies, or even burning away as thoroughly as if placed in a furnace. That these changes are due to micro-organisms is seen by their immediate cessation if the soil be treated with anti-septics like chloroform or mercuric chloride: or if the mixture of soil and organic matter be sterilised by heating. Attempts have been made to estimate the number of bacteria contained in the soil: the prodigious numbers obtained, 2 up to 50 millions or more per cubic centimetre of the upper soil, show little beyond the fact that the soil is tenanted much as any other decaying organic material would be. The soil bacteria are always associated with a certain number of fungi and yeasts,

especially when the reaction of the medium is at all acid: the organisms are most numerous in the surface layer, though they are still to be found in the deepest subsoils. Below a certain depth they must disappear, because deep well water often comes to the surface in an absolutely sterile condition. The changes which organic materials undergo in the soil may be roughly grouped into two classes; according as there is free access of oxygen or not, either decay (*eremacausis*) with eventual resolution into the simplest inorganic oxidised compounds, or "humification" will set in. These changes can be illustrated by the fate of a dead branch when it falls either upon the ground, or into a pond or swamp where it becomes buried in the mud at the bottom. In the latter case the fermentation changes cause the wood to darken even to blackness; gases like carbonic acid and marsh gas are split off, so that the material becomes proportionally richer in carbon and poorer in oxygen. Eventually, however, the process slackens, the losses practically cease, and a large proportion of the original material persists. On the other hand, the branch exposed to the air, without darkening very much, becomes slowly resolved by the action of fungi and bacteria into carbonic acid and water, ammonia, nitrogen gas, and mineral salts, with much the same final result as though it had been placed in a furnace. In soil, both these types of change may go on, and the conditions of the soil as regards aeration, drainage, temperature, and cultivation, determine which will predominate.

Practically, the whole group of aerobic bacteria, *i.e.*, those which require free oxygen for their development, and fungi are capable of bringing about the oxidation changes which result in the production of carbonic acid, the combustion of some carbohydrate being

essentially the means by which they derive their energy. As an intermediate step between the carbohydrate and the carbonic acid, a certain amount of humus is produced—"mould," or the "mild humus" of the German writers. Examples of this material can be seen in the leaf-mould collected by gardeners from woods, or the fine, brown powder which can be scraped out of the inside of a hollow tree, particularly of a willow; this mould differs from the peaty humus, to be described later, in its neutral reaction and in the readiness with which it can be further oxidised. Neutral in its reaction, it yields but little soluble "humic acid" to the attack of an alkali.

Besides carbohydrates, most aerobic bacteria require some carbon compound of nitrogen, and will begin to break down protein and other nitrogen-containing materials. The products of their attack are successively peptones, bodies like leucin and tyrosin, eventually ammonia, and probably free nitrogen, but the ultimate production of ammonia is perhaps the most characteristic feature of the aerobic fermentation of protein bodies. Other amides are also resolved into ammonia, of which a characteristic example is afforded by the change of urea into ammonium carbonate. This process [which is one of hydrolysis, not of oxidation, being represented in the gross by the equation $\text{CO}_2(\text{NH}_2)_2 + 2\text{H}_2\text{O} = (\text{NH}_4)_2\text{CO}_3$] is brought about by more than one organism, universally distributed and abundant in such places as stables and cattle stalls. In warm weather the conversion of the urea of the urine into ammonium carbonate is very rapid, and as the resulting product dissociates into gaseous ammonia and carbonic acid, to this cause is due the smell of ammonia which is always to be noticed in such places. These changes to ammonia are the necessary prelim-

inaries to the final oxidation process or nitrification, which, as the means by which the higher plants receive their supplies of nitrogen, will be discussed separately. The various oxidation processes in the soil are, like all other bacterial actions, promoted by a certain warmth, the optimum temperature being about 25° - 30° , by a sufficiency of moisture, and by the presence of mineral food, like phosphates and potash salts. In any great quantity, however, salts are harmful, particularly sodium chloride; an acid reaction also diminishes considerably the rate of decay. Speaking generally, bacteria do not thrive as soon as the medium passes the neutral point, and all the decay processes are carried out by the development of fungi when the medium is acid.

In the soil of certain of the Rothamsted grass plots which have become acid through the long-continued application of ammonium salts, bacterial actions are very much reduced or even brought to a standstill, the bacteria of nitrification, for example, are absent. The decay of the grass roots and stubble is brought about by microscopic fungi which abound, and proceeds to such a slight extent that a layer of peaty material has formed on the surface. The formation of peat must always be associated with this acid reaction of the surface soil. In this way we may account for the fact that tree remains are generally found at the bottom of any peat bog and that evidence of forest growth is apparent on the soil surface of places like the Welsh hills or Dartmoor, now covered with a thin peaty vegetation but where no indigenous trees grow. When the soil first became clothed with vegetation after the glacial epoch a forest developed, but as the soil became acid through the accumulation of organic residues and its initial lack of carbonate of lime the trees died, and

can only be replaced by others which are tolerant of acid conditions. The presence of chalk, or any form of carbonate of lime, by neutralising any acids as fast as they are formed, promotes the destruction of organic matter. Wollny has also shown that calcium humate will oxidise much more rapidly than uncombined humic acid placed under similar conditions. Portions of the acid grass plots at Rothamsted have been limed, whereupon the peaty surface accumulation rapidly disappears. To the absence of carbonate of lime and mineral salts generally, may be ascribed the tendency of humus to accumulate and persist on the very light, sandy heaths, where the soil is dry and hot in summer, and also well aerated. It has already been indicated, in treating of humus, that the various organic compounds of nitrogen show very different susceptibility to the breaking-down process which eventually renders the nitrogen available for the crop—amongst the most resistant substances being the nucleo-proteins in the undigested portions of food which form dung, and the humus residues from poor, cropped-out land. As in all cases much of the nitrogen of both soil and manure seems to pass into obstinately persistent compounds yielding slowly, if at all, to oxidation, and hence wasted to the farmer, an attempt has been made to increase the preliminary breaking down of nitrogen compounds in the soil by the introduction of certain very active bacteria. Stoklasa has shown that various organisms—*B. megatherium*, *B. fluorescens*, etc.—when seeded into soil manured with bone-meal or similar materials, increase both the nitrogen and the phosphoric acid obtained by the plant. A pure cultivation of some such organism, *B. Ellenbachensis*, was for a time sold commercially under the name of *alinit*, and though the power of fixing nitrogen was claimed for it, its chief action was

probably such as was described above. *It has been found to cause increased crop returns on peaty or other soils rich in humus, or where slow-acting nitrogenous manures have been applied.

The fermentation which goes on in absence of oxygen, is brought about by a large number of bacteria, some of which are only active in the absence of oxygen, others are aerobic, but will continue their work when deprived of free oxygen. Carbohydrates are decomposed with formation of carbonic acid and other gases like hydrogen and marsh gas, butyric and other fatty acids, a residue of humus being always produced at the same time. The protein bodies readily undergo putrefactive change, with the production of tyrosin and various amino-acids, fatty acids, ammonia, phenol, and other bodies containing an aromatic nucleus, gaseous compounds of sulphur, etc. In the main, however, the changes of organic material in the soil fall upon the cellulose; it loses carbonic acid, marsh gas, hydrogen, etc., and becomes humus with a gradually increasing proportion of carbon; the nitrogenous materials resist attack more than the carbohydrates, and hence tend to accumulate, so that an old sample of deep-seated peat is richer in nitrogen than a more recent sample taken from nearer the surface. Finally the humus thus produced, which may be called peat, is essentially an acid product, and even when aerated and supplied with mineral materials will oxidise with extreme slowness.

The Fixation of Free Nitrogen.

In the earliest theories regarding the nutrition of the plant which were accepted after chemistry had become an exact science, it was considered that the plant derived its nitrogen from the humus of the soil, as, for example, in de Saussure's statement that "Plants

receive their nitrogen almost entirely by the absorption of the soluble organic substances." This view was displaced by the so-called "mineral theory" of Liebig, who, in laying down the broad principle that the plant only derived certain necessary mineral constituents, its "ash," from the soil, but the whole of its carbon compounds from the atmosphere, was led to regard the nitrogen as well as the other combustible matters of the plant as due to the atmosphere, largely because of the exaggerated estimate which then prevailed as to the amount of ammonia from the air that was brought down in the rain. Boussingault had already shown, by weighing and analysing the crops on his own farm for six separate courses of rotation, that from one-third to one-half more nitrogen was removed in the produce than was supplied in the manure. The gain of nitrogen was little or nothing when cereal crops only were grown, but became large when leguminous crops were introduced into the rotation. Liebig, however, considered that cereals, as well as the other plants, were able to draw their ammonia from the atmosphere, and that, provided sufficient mineral plant food were forthcoming, there was no need of ammonia compounds in the manure.

This view of Liebig's, though modified later, when he admitted that cereals must obtain their nitrogen from a manurial source in the soil, led to considerable investigation of the source of the nitrogen in the plant. Boussingault himself carried out a long series of laboratory experiments, in which weighed seeds containing a known proportion of nitrogen were grown in artificial soils containing no nitrogen, but supplied with the ash constituents of the plant. Care was taken to remove all ammonia from the air in which the plants were grown, and from the water and

carbonic acid supplied to them; finally, after growth had ceased, the amount of nitrogen in the plant and in the soil was determined. In some cases a known quantity of nitrogenous compounds was supplied as manure; but all the results went to show that there was no gain of combined nitrogen during growth; the seed and manure at starting contained as much nitrogen as was found in the plant and soil at the end.

Similar experiments were carried out with the utmost precautions by the Rothamsted investigators, who likewise found no gain of nitrogen by the plant from the atmosphere. The following results, obtained by Lawes and Gilbert in 1858, will serve to show the agreement between the nitrogen supplied and recovered:—

	Nitrogen in Seed (Grams).	Nitrogen in Soil and Plants.	Gain or Loss.	Nitrogen in Seed and Manure.	Nitrogen in Soil and Plants.	Gain or Loss.
Wheat .	0.0078	0.0081	+0.0003	0.0548	0.0536	-0.0012
Barley .	0.0057	0.0058	+0.0001	0.0496	0.0464	-0.0032
Oats .	0.0063	0.0056	-0.0007	0.0312	0.0216	-0.0096
Beans .	0.0750	0.0757	+0.0007	0.0711	0.0655	-0.0056
Peas .	0.0188	0.0167	-0.0021	0.0227	0.0211	-0.0016
Clover	0.0712	0.0665	-0.0047
Buckwheat	0.0200	0.0182	-0.0018	0.0308	0.0292	-0.0016

It has sometimes been objected that the plants in these experiments made such a poor growth as compared with their normal development in the open air that they never attained their usual power of fixing nitrogen. However, Hellriegel's experiments on plants which were supplied with limited amounts of nitrogen showed that growth is practically proportional to the supply of nitrogen as long as that is below the maximum required by the plant. Field experiments at Rothamsted with

leafy crops like mangolds, to which a very small amount of nitrogen was supplied in order to give them a start, showed that the increase thus produced was only proportional to the nitrogen supplied, so that there is no evidence that even a plant which has begun to grow vigorously can then continue its development by taking nitrogen from the atmosphere.

From all these experiments the conclusion was drawn that cultivated plants are unable to "fix" atmospheric nitrogen, but obtain this indispensable element in a combined state from the soil together with the ash constituents; and such was the opinion that prevailed for something like thirty years.

Notwithstanding the conclusive nature of all the laboratory experiments, there was still a residuum of facts obtained under field conditions which were inexplicable on the theory of the non-fixation of nitrogen, and these facts were chiefly connected with the growth of leguminous crops.

Boussingault's crop statistics have already been referred to; the following table gives a short summary of the kind of results he obtained :—

Rotation.	NITROGEN. Kilos per hectare.	
	Supplied in Manure.	Removed in Crop.
Wheat, Wheat, Fallow	87.2	82.8
Potatoes, Wheat, Clover, Wheat or Turnips, Oats	202.2	268.5
Potatoes, Wheat, Clover, Wheat	182	339
Lucerne, 5 years	1035

The amount of nitrogen removed was equal to that supplied only when wheat was grown, but became

progressively greater the more frequently leguminous crops occupied the ground.

At Rothamsted the following average quantities of nitrogen were removed per acre per annum in the crop, when mineral manures only were applied:—

Wheat (24 years)	22.1
Barley (24 years)	22.4
Roots (30 years)	16.4
Beans (24 years, only 21 years in Beans)	45.5
Red Clover (22 years, only 6 years Clover)	39.8

In this case also the amount of nitrogen in the produce was much increased when a leguminous crop was grown.

Another of the Rothamsted experiments showed still more strikingly the accumulation of nitrogen by a leguminous crop. A piece of land which had been cropped for five years by cereals, without any nitrogenous manure, was divided into two portions in 1872, one being sown with barley alone, and the other with clover in the barley. In 1873 barley was again grown on the one portion, but the clover on the other, three cuttings of clover being obtained. Finally, in 1874, barley was grown on both portions. The quantities of nitrogen removed in the crops of 1873 and 1874 are shown in the table.

NITROGEN IN CROP—LBS. PER ACRE.

1873	Barley	.	37.3	1874	Barley	.	39.1
1873	Clover	.	151.3	1874	Barley	.	69.4

Thus, the barley which followed clover obtained 30.3 lbs. more nitrogen than the barley following barley, though the previous clover crop had removed 114 lbs. more nitrogen than the first barley crop. An analysis of the soil was made in 1873, after the clover and barley

had been removed; this showed down to the depth of 9 inches an excess of nitrogen in the clover land, despite the larger amount which had been removed in the crop.

In Soil after Barley	.	0.1416	per cent. Nitrogen.
In Soil after Clover	.	0.1566	" "

In another experiment, land which had previously grown beans and then been fallow for five years, was sown with barley and clover in 1883, the clover being allowed to stand in 1884 and 1885. At starting the soil was analysed; the surface 9 inches contained on an average 2657 lbs. per acre of nitrogen, while of nitrogen as nitric acid the soil only contained 24.7 lbs. per acre down to a depth of 6 feet. As a result of the three years' cropping with barley and clover, and then with clover only, an average amount of 319.5 lbs. of nitrogen was removed, yet the soil contained, on analysis at the end of the experiment, 2832 lbs. of nitrogen per acre in the top 9 inches, or a gain of 175 lbs. per acre in the three years, making a total, with the crop removed, of nearly 500 lbs. of nitrogen per acre to be accounted for.

The consideration of field trials of this description led many observers to think that there still might be some fixation of free nitrogen, particularly by leguminous plants. Voelcker, in England, when discussing the power of a clover crop to accumulate nitrogen, expressed the opinion that the atmosphere furnishes nitrogenous food to that plant; in France, it was maintained by Ville; Berthelot also brought evidence to show that the soil itself, by the aid of its microscopic vegetation, assimilated some free nitrogen. Even in the laboratory experiments, some of Boussingault's results, and others of Atwater, in America, showed a gain of nitrogen. But the clearing up of the whole

subject came with the publication, in 1886, of the researches of Hellriegel and Wilfarth. These investigators found that when plants were grown in sand and fed with nutrient solutions, the Gramineæ, the Cruciferae, the Chenopodiaceæ, the Polygonaceæ, grew almost proportionally to the amount of combined nitrogen supplied; and, if this were absent, nitrogen starvation set in as soon as the nitrogen of the seed was exhausted. With the Leguminosæ, however, a plant was observed sometimes to recover from the stage of nitrogen starvation, and begin a luxurious growth which lasted until maturity, though no combined nitrogen was supplied. In such cases the root of the plant was always found to be set with the little nodules characteristic of the roots of leguminous plants when growing under natural conditions. Further experiments were made in which the plants were grown in sterile sand, but as soon as the stage of nitrogen hunger was reached, a small portion of a watery extract of ordinary cultivated soil was added; whereupon, the plants receiving the extract recovered from their nitrogen starvation and grew to maturity, assimilating considerable quantities of nitrogen. The renewed growth and the assimilation of nitrogen were always found to be attendant upon the production of nodules on the roots. The nodules were found to be full of bacteria, to which the name of *Pseudomonas radicola* has been given. They could only be produced by previous infection either by an extract of the crushed nodules or of a cultivated soil; in some cases (lupins, serradella) only by soil which had previously carried the same crop.

These results, though not at first accepted by Lawes and Gilbert, led to a repetition of the experiments, which brought out the fact that in their earlier trials with leguminous plants the necessary inocula-

tion had always been wanting because of the great care that had been taken to prevent the entry of any accidental impurity. Eventually, both at Rothamsted and by other investigators, the conclusions of Hellriegel and Wilfarth were confirmed, that when leguminous plants are grown under sterile conditions, without a supply of combined nitrogen there is very limited growth, no formation of nodules, and no gain of nitrogen. But when the culture is seeded with soil extract there is luxuriant growth, abundant nodule formation, and coincidentally, great gain of nitrogen, many times as much in the products of growth as in the seed sown. Gilbert also showed that there is a gradual accumulation and then withdrawal of nitrogen from the nodules. Lastly, Schloesing *fil*s and Laurent, by growing Leguminosæ in closed vessels, and analysing the air before and after growth, found an actual disappearance of nitrogen gas, agreeing with the amount gained by the plant during growth. Thus, a conclusion was reached that the leguminous plants can assimilate and fix the free nitrogen of the atmosphere by the aid of bacteria living symbiotically in the root nodules—a conclusion which served to explain, not only the discrepancies in the previous experiments, but the long-accumulated experience of farmers that crops like clover and lucerne enrich the soil, and form the best preparation for cereals like wheat, which are particularly dependent on an external supply of nitrogen. The mechanism of the fixation of free nitrogen is still incompletely understood. It has been found possible to grow these bacteria apart from the leguminous plants, if they are cultivated on a medium containing only a trace of nitrogen but supplied with the ash constituents of the plant and also with some carbohydrate like dextrose or maltose. The quantities of nitrogen fixed in this way are always,

however, very much smaller than are fixed by a leguminous plant on whose root the nodules are well developed. To fix the nitrogen, some expenditure of energy is required, and this is derived from the combustion of carbohydrate supplied to the bacteria by the higher plant; indeed it has been observed that the nitrogen fixation and general growth of the Leguminosæ is stimulated by a supply of sugar or other carbohydrate to the soil. The organism, *Pseudomonas radicicola*, appears to be capable of considerable modifications; in the nodules it forms rather large rod or Y-shaped organisms, but if an active subculture be obtained by inoculation from a nodule into a non-nitrogenous medium as described above, excessively minute rod-shaped organisms appear, generally in rapid motion. It is in this minute unspecialised form that they exist free in the soil, and it has been shown that they infect the leguminous host by getting through the thin walls of the root-hairs. The characteristic Y forms have also been obtained in artificial cultivations by introducing certain substances into the medium. Much investigation has also been applied to the question of whether there is only one kind of bacterium living in symbiosis with all the Leguminosæ, or whether there is not a definite race appropriate to each species of leguminous plant, with which it alone can bring about nitrogen fixation to the full extent. The earliest investigations had already shown that lupins and serradella did not develop nodules when infected with an ordinary garden soil, but only when an extract was added from a sandy soil on which these plants had been previously grown; and Nobbe brought further evidence to show that, though there is very widely distributed in the soil an organism which will cause some nodule formation and fixation of nitrogen,

yet it becomes so modified by growing in symbiosis with the different leguminous plants, that the best results are only obtained when each species is directly infected from nodules taken from the same kind of plant.

Accordingly, he proceeded to the introduction, on a commercial scale, of pure cultivations on a gelatine medium of the races of bacteria appropriate to each of the leguminous plants grown as field crops. The jelly, which was called "Nitragin," was to be dissolved in a large bulk of water and sprinkled over the seed before sowing; thus ensuring inoculation with the appropriate organism, which might not happen to be present in the soil. Nitragin failed to fulfil the expectations which were formed at its introduction, partly because of the nitrogenous character of the medium, in consequence of which the organisms possessed very little vitality or power of fixing nitrogen. Since that time, however, several other methods of cultivating the organism for inoculation purposes have been introduced, either by growing it on an agar jelly, which contains practically no nitrogen (Hiltner), by drying up cotton wool which has been soaked in an active liquid culture (Moore), or by drying soil which has been treated in the same way. Active liquid cultures can now be obtained from most laboratories. The culture thus obtained is added to a large bulk of water, containing a little separated milk to protect the organisms from substances excreted during germination, and the seed is dipped into it and allowed to dry before sowing. The culture may also be sprayed over the ground or absorbed by a large quantity of earth which is afterwards sown. The results of such inoculation are very conflicting; where the land has been regularly under cultivation and has carried the leguminous crop in question many times previously, nodules are practically always formed whether the seed

be inoculated or not. In such cases inoculation can only be beneficial if the bacteria introduced either belong to a more vigorous race of nitrogen fixers than those normally present in the soil or are more specifically adapted to that particular crop. It has not as yet been conclusively demonstrated that such improved races can be cultivated in the laboratory, or that they can maintain themselves in the soil in competition with the kindred organisms already present. It should, moreover, be borne in mind that even if such improved races of the nodule-forming organism can be introduced to the plant, the improvement they can produce in the yield is likely to be something of the order of a ten per cent. increase, a gain which is only really perceptible after careful and continued field experiments, and one not to be detected by the ordinary farmer's eye. Of a very different order are the results attained by inoculation when the land contains none of the appropriate organisms; inoculation will then change a stunted, sickly-looking growth into a profitable crop. It is only in special cases that land devoid of the nodule organisms is to be met with, most commonly when land is being brought under cultivation for the first time, as in breaking up a virgin soil or in reclaiming heath and bog land. Such peaty and heathy soils, which are devoid of carbonate of lime, rarely carry any leguminous plants the nodules of which could supply the necessary bacteria to farm crops like clover and lucerne; when such land has been reclaimed and limed an inoculation is advisable before sowing a leguminous crop.

Similarly when the cultivation of such leguminous crops as lucerne or even sainfoin is being extended into districts where they have not been grown previously, an inoculation is often necessary before the roots will nodulate freely and the plant make its proper growth. Lucerne

grown for the first time on heavy land in a new district has been observed to fail completely, the failure being attended by a complete absence of nodules from the roots. Success does not, however, invariably follow inoculation. In the first place, it may be necessary to bring the soil itself into the proper condition for the growth of both crop and the bacteria, the natural absence of which is of itself evidence that the soil is unsuited to their maintenance. Liming and dressings of basic slag and potash salts are generally the necessary preliminaries to any satisfactory growth of leguminous crops on indifferent soils. Even then the first inoculation may show comparatively little effect, the plant still remaining weakly, though most of the individuals may show nodules. The inoculation only supplies a very limited number of bacteria compared with the population in a normal soil. It is only when the crop comes to be sown a second time that vigorous growth is obtained. It is within the author's experience that a first sowing of lucerne on land that had never carried the crop before gave weakly, unnodulated plants. A culture of nodule organisms was sprayed over in early spring without benefit, whereupon the crop was ploughed up and resown, the seed being inoculated before sowing. The plant was still poor, though generally nodulated; accordingly it was again ploughed up and resown, with the result that a good crop of lucerne was established.

Inoculation with soil from a field which has previously grown the crop about to be sown has often proved a signal success in reclaiming the poor heath lands of East Prussia, by the system of green manuring worked out by Dr Schultz at Lupitz. Very large areas of barren sandy heath land have been reclaimed and rendered fit for the cultivation of the ordinary crop by a system of growing lupins and

ploughing in the green crop. Mineral manures alone are employed, latterly basic slag and the Stassfurt potash salts; the lupins accumulate nitrogen from the atmosphere, thus gradually there is built up both humus to bind together the loose sand and make it retentive of moisture, and also a store of nitrogen for the nutrition of succeeding crops. The soil of a field growing lupins every year from 1865 was found in 1880 to contain 0.087 per cent. of nitrogen in the surface 8 inches, as compared with 0.027 per cent. in an adjoining pasture. By 1891 the proportion of nitrogen had increased to 0.177 per cent., despite the annual removal of the lupin crop and the fact that the manuring had been with phosphates and potash only. It is in reclaiming these heath lands which have not previously been under cultivation, nor, in many cases, carried any leguminous vegetation whatever, that soil inoculation from land previously cultivated has given successful results. Dr Salfeld of Hanover has recorded several cases of the successful cultivation on a large scale of various leguminous plants, beans, clover, serradella, lupins, only after previous inoculation with soil. The experiments were made on both peaty (moor) and sandy soils, on which, without inoculation, leguminous plants made but little growth and developed no nodules. Success followed when about 8 cwt. per acre of soil from a field which had previously carried the crop in question were sown broadcast over the land in April, and harrowed in just before seeding. In one case, over 7 tons per acre of green serradella were grown where the land had been treated with 8 cwt. of soil from an old serradella field, whereas the crop failed after germination where no inoculation had been practised.

Fixation of Free Nitrogen by the Soil.

As already indicated, Berthelot attributed to the soil itself the power of fixing a small quantity of atmospheric nitrogen, a power which was lost when the soil was sterilised and maintained under conditions preventing infection. This gain of nitrogen was independent of the small amount of ammonia absorbed by soil from ordinary air, which always contains a trace of ammonia; and at first it was attributed to the microscopic green algæ which clothe the surface of ordinary moist soil. The experiments of Kossowitsch, and of Krüger and Schneidewind, have, however, shown that the growth of pure cultures of these algæ is dependent on a supply of combined nitrogen, and that no fixation of free nitrogen takes place whether the algal growth be small or large. It is possible, however, that they may live in symbiosis with nitrogen-fixing bacteria and supply the carbohydrate, by the combustion of which the energy needed for the fixation of nitrogen by the bacteria is obtained. More recently, however, several organisms have been isolated from the soil, which are capable, when growing in a free state, of fixing nitrogen drawn from the atmosphere, and it is to these that the gains of nitrogen observed by Berthelot must be attributed. Winogradsky was the first to isolate an organism of this type, which, when grown under anaerobic conditions and supplied with soluble carbohydrate, breaks the latter down with the formation of butyric and other acids, and at the same time draws some of the gaseous nitrogen present into combination. This particular organism *Clostridium Pastorianum* is very widely diffused and can readily be isolated from pond mud and similar material, where organic matter is decaying under comparatively anaerobic conditions. The extent of the nitrogen fixation is, however, small;

in the laboratory not more than 2 to 3 mg. of nitrogen are brought into combination for each gram of carbohydrate oxidised. By far the most effective of the nitrogen-fixing bacteria that are free in the soil is a large organism, named by its discoverer, Beijerinck, *Azotobacter chroococcum*. It may be easily isolated from most soils by adding a small portion of soil to 50 c.c. of a culture medium containing per litre 10 grams of mannite or glucose, 0.2 gram each of potassium phosphate, magnesium sulphate, and sodium chloride, and 0.1 gram of calcium sulphate, half a gram of calcium carbonate being also added to each flask. The solution and its flask and plug of cotton wool are previously sterilised by heat. After inoculation, the flask is placed in an incubator, and after a week's time a considerable fermentation will be observed to have taken place, attended by the evolution of gas and the formation of a brown scum upon the surface. By making a subculture in a similar medium, inoculated with a trace of the brown scum, a fairly pure growth of the *Azotobacter* can be obtained for examination, or the amount of nitrogen fixed may be determined by Kjeldahling the contents of the flask.

Azotobacter chroococcum is a large oval organism, 4 to 5 μ in length and 3 μ in width, which differs from most bacteria in containing glycogen, so that it stains a deep brown colour with a solution of iodine, a method which is convenient for the observation of the organism. It is aerobic, and is, in fact, a strong oxidising agent, the dextrose or other carbohydrate which it requires being converted by it into carbon dioxide and water, together with small quantities of lactic and acetic acids, alcohol, and sometimes butyric acid.

A very characteristic by-product is the dark brown or black pigment from which the organism derives its

the small supply of nitrogen available to the crop. Possibly, too, some of the products of their action on the carbohydrate were injurious. But with an autumn application in the still warm soil, nitrogen fixation goes on actively, and some of the material thus absorbed from the air becomes available for the crop in the following spring.

To the *Azotobacter* and kindred organisms must certainly be ascribed a large part in preparing and maintaining the world's stock of combined nitrogen. It is customary to regard such virgin soils as the black soils of the Russian Steppes, of Manitoba, and of the Argentina, as rich in nitrogen because of the accumulation of the vegetable débris of many epochs; but since plants other than the Leguminosæ do not fix nitrogen themselves, there could in this way be no addition to the original stock, which would only circulate from the soil to the plant and back to the soil again. Under such conditions, however, there is a continual addition to the soil of the carbon compounds which the plant derives from the atmosphere, and this is material which the *Azotobacter* can oxidise, and so derive the energy required for the fixation of nitrogen. It is the constant return to the soil of oxidisable organic matter which differentiates the wild from the cultivated land, and renders possible the long-continued storing up of nitrogen in the virgin soils.

Interesting evidence on this point may be derived from the Rothamsted experiments; on the Broadbalk wheatfield the unmanured plot has, during the fifty years 1844-93 yielded a crop containing on the average 17 lbs. of nitrogen per acre per annum. Analyses of the soil at the beginning and end of the period showed a decline in the amount of nitrogen equivalent to a removal of 12 lbs. per acre per annum, and the rainfall is known to bring down between 4 and 5 lbs. per acre

per annum. The annual withdrawal in the crop would thus be closely balanced by the loss experienced by the soil and the additions, were there not other unknown withdrawals in the weeds which are removed from the plot, and in the nitrates which are washed down into the subsoil and the drains. Doubtless, neither of these two withdrawals are large, but because of their existence, unbalanced by any corresponding falling off in the nitrogen content of the soil, it must be concluded that even on the arable land some small restorative action is going on. A portion, however, of the same field has been covered with a wild vegetation of weeds and grasses for the last twenty-five years, and this is never cut or harvested, so that all the débris fall back on the land just as it would on a virgin soil. Analysis of samples of this soil taken in 1881, when it ceased to be under cultivation, and in 1904, showed an annual accumulation of nitrogen of more than 100 lbs. per acre. The enormous difference in the fixation on this plot as compared with the unmanured plot carrying wheat, must be set down to the difference in the supply of non-nitrogenous carbon compounds to the two plots; in the one case the wheat is all removed except a small portion of root and stubble; in the other the whole of the vegetable growth falls back on the land. The wild vegetation on this plot did include a considerable proportion of leguminous plants, but a similar, though smaller accumulation of nitrogen was observed in another plot of land which had been allowed to run wild in the same manner, but which carried no leguminous vegetation in consequence of the small amount of calcium carbonate in the soil. These two plots present a very close parallel to the actions which must have been taking place in all virgin soils where the soil similarly contains the *Asotobacter* organism. Doubtless also some of the value of laying down land to temporary

pasture must be due to the accumulation of nitrogen by the same agency, because we know that land under grass accumulates carbon compounds from the roots and stubble that is not removed during grazing.

Nitrification.

It has long been known that when any organic compound of nitrogen is applied to the soil it becomes eventually oxidised to a nitrate, which is, as a rule, the compound of nitrogen taken up by cultivated plants, the Leguminosæ excepted. The potassium nitrate collected from Indian soils, the calcium nitrate made artificially in nitre beds in Europe, owe their origin to this oxidation of organic compounds of nitrogen. That the process was a biological one was first indicated by Müller in 1873, but any widespread recognition of the fact did not take place before the work of Schloesing and Muntz in 1877. These investigators showed that the formation of nitrates in the soil ceased at temperatures below 5° and above 55° C., that it could be stopped by chloroform vapour and similar antiseptics, and that the soil lost entirely its power of nitrification if it were heated to the temperature of boiling water. The investigations of Warington confirmed these results, and brought to light the further fact that there were two stages in the oxidation process, one being the formation of a nitrite, followed by the conversion of this nitrite into the completely oxidised product. It was found possible to obtain cultures which would only push the oxidation to the nitrite stage, thus indicating that there must be at least two organisms concerned in the complete nitrification process. The further study of the organisms was for a long time hindered by the fact that they could not be got to grow upon the gelatinous media employed in the ordinary methods of isolating specific bacteria; and

though P. F. Frankland, by a dilution method, succeeded in isolating and describing a nitrifying bacterium, it was not until 1890 that Winogradsky cleared up the problem. He prepared a solid nutritive medium containing no organic matter but with silica in its gelatinous form as a basis, and thus was able to separate nitrifying bacteria from the large number of other species simultaneously present in the soil. Winogradsky was able to isolate two species of bacteria capable of transforming ammonia compounds into nitrites. One of these, termed *Nitrosomonas europæa*, was obtained from all the soils of the old world he examined; the other, ascribed to the genus *Nitrococcus*, was peculiar to the soils of America and Australia. The former occurs both as a single, free-swimming form, and clustered together in a colony or zooglœa state.

Finally, there appears to be one type of organism only, included in the genus *Nitrobacter*, which oxidises the nitrites to nitrates. Winogradsky and other observers have worked out the conditions of life of these nitrifying organisms—the limits of temperature for their growth, 5° and 55° C., have already been given, the optimum temperature is about 37° C. Their action is much restrained by the presence of organic matter, or any quantity of alkaline carbonates or chlorides; at the same time, some base* must be present to combine with the nitrous or nitric acids produced, for nitrification ceases as soon as the medium becomes at all acid. While calcium carbonate is the substance which, as a rule, is effective to this end, many organic salts will also supply the necessary base. Ammonium salts of

* Instruction sur la fabrication du nitre :—Par les régisseurs généraux des poudres et salt pêtres, 1777, "Elles doivent l'être toujours avec une addition de terre calcaire qui puisse servir de base à l'acide nitreux."

the strong acids will not nitrify directly in the absence of a base, and the function of the calcium or magnesium carbonate usually added is to form, by double decomposition, ammonium carbonate, which the nitrifying organisms can attack. The complex salts formed by the interaction of the zeolites of clay with ammonium salts can be nitrified directly, but not, however, the ammonium humate formed by the corresponding interaction of ammonium salts and humus. Humus itself does not inhibit nitrification, and, indeed, the organisms can be brought to tolerate considerable quantities of other organic matter, by transferring them into successively stronger solutions. The organisms are able to obtain the carbon necessary to their growth from carbonates in the culture medium or carbonic acid in the air; the energy necessary to decompose the carbon dioxide and fix the carbon is derived from the oxidation of the ammonia, about 35 parts of nitrogen being oxidised for each part of carbon that is fixed. The nitrifying organisms are chiefly confined to the cultivated surface layer of the soil. Warington found that, in the close-textured Rothamsted soil they were by no means uniformly distributed below the top 9 inches, and that they were never present, except accidentally, in the subsoil below a depth of 2 feet. It has also been shown that they are entirely absent from many heath and moor soils, even in the surface layer. They are abundantly found in the water of shallow wells and rivers.

Further investigations show that though nitrate production is the normal end process in the breakdown of nitrogenous substances into plant food, from which it follows that the rate of production of nitrates is some measure of the fertility of the soil, yet the nitrate-producing bacteria are, as a rule, able to convert the

ammonia immediately it is presented to them, and the real limiting factor in nitrate production is the activity of the ammonia-producing organisms. The amount of free ammonia in neutral soils is always very small, one to two per million, whereas the nitrate may amount to 50 to 100 parts per million. This is because the ammonia is transformed as fast as it is produced, and nitrification organisms are always able to keep pace with the output of ammonia if by any means that can be stimulated. In acid soils where nitrification is slowed down or at a standstill, the higher plants doubtless take in the nitrogen they require as ammonia; indeed certain modifications in the colour of the crop and its habit of growth appear to follow when it is deriving its nitrogen from ammonia and not from nitrates. In considering the fertility of the soil the ammonia-making and nitrifying organisms must be regarded as one group, which do the final preparation of the organic nitrogen residues for the food of the higher plants and upon the activity of which, particularly of the former, the rate of production of available plant food depends.

Summing up the above facts, it is seen that for the active production of nitrates from the organic compounds of nitrogen present in the soil—and this is necessary if the crop is to be kept supplied with the nitrogen required for its growth—the following conditions are requisite:—The presence of the ammonia-making and nitrifying organisms in sufficient quantities, a certain degree of temperature, sufficient moisture for the development of the bacteria, free aeration of the soil to supply the oxygen necessary, and a base to neutralise the acids as they are produced.

The scanty number of ammonia-making and nitrifying bacteria in any subsoil below the cultivated layer

helps to explain both its sterile nature when brought to the surface, and the difficulty and length of time required to develop a state of fertility, especially when dealing with a clay soil in which percolation and aeration have been deficient.

The effect of a low temperature in checking the formation of nitrates is well seen in the way the growing corn turns yellow through nitrogen starvation whenever a cold and drying north-east wind chills the ground in spring: the bright green colour returns as soon as warmer and moister soil conditions restore the activity of the bacteria in the surface layer. King found in the top foot of soil when oats were turning yellow only 0.26 parts of nitric nitrogen per million of dry soil, whereas in soil where the oats were green on the same date there was 2.55 parts of nitric nitrogen per million, itself a small amount. The greater warmth of a light soil also causes it to form nitrates quickly in the spring and so assists in producing an early growth.

But in obtaining early crops, even when the land is rich, a dressing of ready-formed nitrate is often of the greatest assistance, for the development of very early crops may easily outstrip the rate at which the nitrates they require can be formed in the still unwarmed soil. Nitrates are much more freely formed in the summer than in the winter, and as they are not retained by the soil, they may easily be washed away when the crop has been removed, unless weeds or a catch crop sown to that end are present to take up the nitrates and store them as organic compounds of nitrogen for the future enrichment of the land.

The need for aeration in connection with the nitrifying process has already been alluded to when discussing drainage: all processes of working and cultivating the soil assist nitrification, both by the thorough aeration

they effect, and by the mere mechanical distribution of the bacteria into new quarters, where there are fresh food supplies. In some experiments of Dehérain's he found that the drainage water from pots of cultivated soil, which had been sent from a distance, and thus much knocked about in travelling and filling into the pot, contained as much as 466 to 664 parts of nitrogen as nitric acid per million. The drainage water from the Rothamsted wheat plots contains only from 10 to 20 parts per million; even the cement tanks at Grignon, 2 metres cube, into which the soil had been filled, gave drainage water containing only 39 parts of nitric nitrogen per million. In another experiment a quantity of soil was thrown upon a floor, and worked about daily for six weeks; on analysis it contained 0.051 per cent. of nitric nitrogen, as against .002 per cent. of nitric nitrogen in the same soil left *in situ*. The diagram (Fig. 15), due to King, shows the dependence of nitrate production on temperature and the cultivation of the soil. The lower curve shows the amount of nitrate in parts per million in dry soil in the top foot of land, which was not being cultivated because it carried clover and oats. The upper curve shows the same results obtained on well-tilled land carrying maize and potatoes. On the cultivated land the proportion of nitrates rises rapidly until the end of June, when the crop begins to draw freely upon them, and reduces them to a minimum throughout August and September.

One of the best examples of the manner in which the thorough working and aeration of a warm soil promotes nitrification is seen in the management of the turnip crop as usually grown in this country. Though shallow-rooted, and taking away large quantities of nitrogen per acre, it is usually grown with but little nitrogenous manure; phosphates with a little




FIG. 15.—Nitrates per million parts Dry Soil, 1 foot deep, Cultivated and Uncultivated.

dung or with a comparatively small nitrogenous dressing, being sufficient. The rest of the nitrogen is derived from the rapid production of nitrates, due to the very thorough working of the soil in the warm season of the year that is characteristic of the cultivation of the turnip crop. The production of nitrates by cultivation for the benefit of a succeeding crop in bare fallowing, or of an adjoining crop as in the Lois-Weedon system of alternate husbandry, has been already alluded to. At Rothamsted, nearly 60 lbs. per acre of nitric nitrogen were found in October in the top 27 inches of soil that had been fallowed, as against about half that amount in land which had been under crop. The unmanured alternate wheat and fallow plots showed in September 1878 to a depth of 18 inches 33.7 lbs. of nitric nitrogen per acre after fallow, and only 2.6 lbs. after wheat. In land occupied by cereal crops the drainage waters show that there is practically no nitrate left in the soil by May, or, at the latest, June; they reappear again towards the end of July or in August, and after harvest, if rain falls, and especially if the land be ploughed, nitrification becomes very active. It depends upon the rainfall of the autumn and winter whether these nitrates, formed after harvest, are retained for the succeeding crop or are washed out of the soil. To sum up, increased nitrification, together with the conservation of soil moisture and the warming of the surface soil, are among the chief benefits derived from all forms of surface cultivation.

Attempts have been made to estimate the fertility of soil by determining the rate at which it will induce nitrification in suitable media, this being taken as a measure of the number of nitrifying organisms present. But, as has been seen, the activity of the ammonia-making organisms is the limiting factor in

the production of nitrates; in consequence it is their numbers that should be determined. A better indication is obtained by determining the rate of formation of nitrate within a mass of the soil; the difficulty attending the operation is, however, that of securing standard conditions of moisture and mechanical condition of the soil.

Denitrification.

The term denitrification is most properly applied to the reduction of nitrates to nitrites, ammonia, or particularly to gaseous nitrogen, which is brought about by bacterial action under certain conditions. Of late, however, the term has been more loosely used to denote any bacterial change which results in the formation of gaseous nitrogen, whether derived from nitrates, ammonia, or organic compounds of nitrogen.

Angus Smith was the first to observe the evolution of gas from a decomposing organic solution containing nitrates, which were destroyed in the process. Other observers, particularly Dehérain and Maquenne (1882), with regard to soils, confirmed these results and showed that they were due to bacterial action. In a paper published in 1882, Warington described an experiment in which sodium nitrate was applied to a soil saturated with water; after standing for a week, the nitrate was washed out of the soil, part of it had disappeared, and part had become nitrite. The total of both nitric and nitrous nitrogen only amounted to 20.9 per cent. of that which had been originally applied. That the nitrate had been reduced to gaseous nitrogen was seen by the development of transverse cracks filled with gas in the soil, and it was concluded that some of the nitrogen applied in manures and unaccounted for in crop and

soil may well be due to the reduction of nitrates to gas, by the combustion of organic matter with the oxygen of the nitrate, especially in ill-drained soils in wet weather. Gayon and Dupetit, in 1886, isolated two organisms from sewage which would reduce nitrates to gas in the presence of organic matter, the action being chiefly carried on when oxygen was absent; it came to a standstill when plenty of air was supplied, so that the organism had no need to attack the nitrate to obtain oxygen. Both in their experiments and in others, the presence of an abundant supply of soluble organic matter was one of the necessary conditions for the destruction of the nitrates. The denitrifying bacteria are widely distributed. Warington found, out of thirty-seven species of bacteria examined, only fifteen failed to reduce nitrate, twenty-two reduced it to nitrite, and one of them liberated gas. P. F. Frankland, again, found that fifteen out of thirty organisms derived from dust or water would reduce nitrate to nitrite. In fact, a large number of bacteria, when deprived of oxygen and in contact with abundant organic matter, will obtain the oxygen, which they normally require for the breaking up of the organic matter, at the expense of the nitrate.

Many experiments, in which farmyard and other organic manures have been employed in conjunction with nitrate of soda and similar active compounds of nitrogen, have shown a smaller crop for the manures used together than when either was employed singly. These results were particularly apparent when large quantities of material like fresh horse-dung or chopped straw were used in pot experiments. With well-rotted dung, the effect of organic material in depressing the yield which should be given by the nitrate was not so great.

The nature of the results obtained may be seen from the following table, which gives the percentage recovered in the crop of the nitrogen supplied in the manure, when used alone, or in conjunction with fresh horse-dung:—

PERCENTAGE OF NITROGEN RECOVERED (WAGNER).

	Per cent. recovered when used alone.	When used with Horse-dung.
Nitrate of Soda	77	52
Sulphate of Ammonia	69	50
Urine	69	40
Grass	43	20

Numbers of similar experiments in pots have been recorded. In some cases the use of fresh dung has even resulted in a smaller crop than was obtained without any manure at all; but it should be noted that very large amounts of the organic manures were used, equivalent to 100 tons or more per acre. Similar results have, however, been recorded in field trials, as in some experiments of Krüger and Schneidewind's, where fresh cow-dung was applied at the rate of 23 tons per acre, horse-dung, 21 tons per acre, and wheat straw at 10 tons per acre, on 10th July. These three plots were in part cross-dressed with urine or with nitrate of soda, each supplying 43 lbs. of nitrogen per acre. Two successive crops of mustard were immediately grown, and the amount of nitrogen removed by the crop was ascertained. Compared with the wholly unmanured plot, the cow-dung alone slightly depressed the crop by about 1½ lbs. per acre less nitrogen being recovered; the horse-dung produced a depression of nearly double this amount; the wheat straw produced the greatest depression, its crop containing about 18 lbs. per acre

less nitrogen than that given by the unmanured plot. Where straw was used with nitrate of soda the two gave a crop containing 23 lbs. less nitrogen per acre than the nitrate alone; where urine was used alone, the produce contained 25 lbs. more nitrogen per acre than when it was used in conjunction with cow-dung and straw.

In fine, all the results pointed to the same conclusion—that large amounts of fresh organic manure not only do not themselves help the crops, but diminish the effect of other rapidly acting nitrogenous manures like nitrate of soda, sulphate of ammonia, or urine.

The action cannot, in the two latter cases at least, be put down to denitrification proper, unless it is supposed that nitrification and subsequent denitrification can proceed practically simultaneously in the same soil. It must either be attributed to the fact that nitrification is very much checked by the presence of large amounts of organic matter; or to the conversion of readily available nitrogen into a comparatively insoluble albuminoid form in the actual material of the enormous numbers of bacteria that are developed by the free food supply; or, lastly, to those fermentation changes of organic nitrogen compounds which result in the liberation of free nitrogen. Several of these changes may take place together; the essential point is, that nitrification does not go forward in the presence of much organic matter, which instead favours all the bacterial processes resulting in the development of free nitrogen.

The conditions indeed which prevailed in these experiments are scarcely comparable with the ordinary practices of agriculture. Enormous quantities of fresh organic manure were employed immediately before the

crop was sown, the temperature of the pots, or of the ground in the field experiment quoted, was very high, so that it is easy to see that an abnormal condition, both as regards nitrification and the supply of oxygen and water, must have been developed.

There are not lacking both long-continued experiments and ordinary farming experience to show that nitrates and other artificial manures can be used in conjunction with dung with the best effects.

For example, the mangold crop at Rothamsted shows the following average results for the recovery of nitrogen from various nitrogenous manures used first with mineral manures alone and then with annual dressings of 14 tons per acre of farmyard manure, a quantity that never would be employed so frequently in practice :—

Nitrogenous Dressing.	YIELD. Tons per acre.	NITROGEN.		
		In Manure.	Recovered in Crop.	Percentage recovered per 100 in Cross- dressing.
PLOTS MANURED WITH PHOSPHATES AND ALKALINE SALTS.				
Nitrate of Soda . . .	17.95	86	67.2	78.1
Ammonium Salts . . .	15.12	86	49.3	57.3
Rape Cake	20.95	98	69.4	70.9
Ammonium Salts and Rape Cake	24.91	184	103.0	56.0
PLOTS MANURED WITH DUNG.				
Nothing	17.44	200	63.3	31.6*
Nitrate of Soda . . .	24.74	286	115.8	61.0
Ammonium Salts . . .	21.73	286	105.6	49.2
Rape Cake	23.96	298	111.1	48.8
Ammonium Salts and Rape Cake	24.05	384	129.8	36.2

* Percentage of Nitrogen in dung recovered.

It will be seen that all the nitrogenous cross-dressings produce an increase of crop when added to the farm-yard manure. When the cross-dressings are used on plots receiving only non-nitrogenous manures, the nitrogen recovered varies between 56 and 78 per cent. of that supplied in the manure; when they are used in conjunction with dung, the recovery of nitrogen in the increased yield above that produced by dung alone varies between 36 and 61 per cent. That the recovery is smaller in the latter cases is due to the fact that with such excessive amounts the yield ceases to be proportional to the supply of nitrogen, being limited by other factors.

Denitrification is only likely to cause rapid loss of nitrogen when large quantities of nitrate are applied to undrained or sour land, or when they are used with excessive amounts of fresh dung, which has not been rotted and so deprived of much of its soluble organic matter. Of course, a steady loss of nitrogen due to such causes as have been enumerated above must also be expected wherever large quantities of organic nitrogenous manures are accumulating in the land. If, for example, we compare 2 and 3 of the Broadbalk wheat plots at Rothamsted, the latter of which is unmanured and the former receives dung containing 200 lbs. of nitrogen per acre every year, we find that at the end of the fifty years, 1844-93, the dunged plot contained in the top 18 inches about 2680 lbs. more nitrogen than the unmanured plot, or a mean annual accumulation of 50 lbs. The extra crop grown on the dunged plot would remove a further 31 lbs., thus leaving 119 lbs. per annum to be accounted for, either as nitrogen washed away in the drainage water or lost as gaseous nitrogen by denitrification processes. After a wet winter the wheat crop, especially upon heavy land, often shows patches of lighter colour and poorer growth. These are

generally attributed to the washing out of the autumn-formed nitrates, but it is more probable that the shortage of nitrogen is due to denitrification consequent upon water-logging. Indeed denitrification and the evolution of gaseous nitrogen, rather than leaching is probably the main source of the loss of nitrogen to soils.

The Protozoa of the Soil.

A number of isolated experiments are on record, in which it was found that ordinary soil, which had been subjected to some form of treatment resulting in a disturbance of the organisms living in the soil, became, for a time at any rate, more fertile. For example, in connection with the fumigation of the soil of vineyards with carbon bisulphide in order to get rid of phythoxera, an increased crop-producing power had been noticed to follow in the soil itself. Again, attempts to sterilise soil by heat gave similar results.

The question remained vague and without explanation, until the publication, in 1909, of a systematic investigation by E. J. Russell and H. B. Hutchinson. Russell established the prime facts that soil which had been heated for an hour or so to the temperature of boiling water, gave, in the next crop, something like double the produce that a control of unheated soil did. The effect persisted, though to a smaller degree and with a steady decline, in the succeeding two or three crops. Similar results, though the initial increase was not so marked, were obtained when the soil was only heated to temperatures between 55° and 70° C. In other experiments the moderately dry soil might be mixed with 0.5-1 per cent. of some volatile antiseptic like toluene, carbon disulphide, or chloroform, left closed up with the antiseptic for some thirty hours, and then freely exposed to the air until the antiseptic had entirely

evaporated. The moisture in the soil was then adjusted, whereupon the soil showed the same increase in its crop-producing power. The effects were most pronounced with initially rich soils, and the plants grown in the treated soil showed every evidence, in their vigour of growth and the colour of the leaves, of an increased supply of nitrogen. Analysis showed an increased content in nitrogen, and, to a much smaller extent, of phosphoric acid and potash, but the whole effects were similar to those produced by a more liberal nitrogenous manuring.

On examination of the soils, it was found that the treatment, either by heat or antiseptics, had not effected the sterilisation of the soil. Some groups of bacteria were destroyed, *e.g.*, the nitrification organisms; but the decay organisms and those producing ammonia were still present. Moreover, and this is the significant fact, a count of the number of bacteria present in the soil showed invariably that, though the first effect of the treatment was to depress the numbers present, they very rapidly increased, until they reached numbers vastly greater than were ever found in the untreated soil. The following table illustrates the point:—

BACTERIA IN MILLIONS PER GRAM OF DRY SOIL.

	At Start.	After 16 Days.	After 80 Days.	After 74 Days.	After 300 Days.
Soil 1—					
Untreated . . .	27	10	10	45	...
Treated with carbon disulphide . . .	2	17	53	121	...
Soil 2—					
Untreated . . .	13	9	4	9	12
Treated to 65° C. .	13	21	37	45	60
Soil 3—					
Untreated . . .	11	16	9	13	6
Treated with toluene .	2	43	41	43	18

In an untreated soil the numbers of bacteria present, though showing variations with temperature, moisture, aeration, and similar factors, never undergo any permanent and pronounced change. Exceptionally favourable conditions may cause a temporary rise, which is often followed by a considerable decrease.

Clearly, then, the effect of the treatment had been to increase markedly the capacity of the soil for bacterial activity, and the increased fertility was due to the larger numbers of the bacteria present, which break down the nitrogenous reserves into ammonia and other forms assimilable by the crop.

Various hypotheses may be advanced to account for the increase in bacterial numbers; the treatment may have so altered the organic reserves that they become more readily available as bacterial food, a stimulus may have been given to the bacteria themselves, so that they became more effective, certain injurious or competing races may have been selectively removed, or again, toxins inhibiting the development of the bacteria may have been destroyed. As regards the first hypothesis, the experiments did show that in soil treated to 100° C. some of the organic matter had been altered, and bodies like ammonia had been set free. Germination and the growth of seedlings in such soil is often depressed for a time, the plant recovers later and the expected outburst of growth follows; but there is an initial period of depression due to these active products of decomposition.

But none of the hypotheses indicated are consistent with all the facts, which only become explicable on the assumption that the treatment has brought about the removal of some factor inhibiting the free development of the bacteria in untreated soils. In normal soils untreated, there is something present which keeps the

numbers of bacteria in check, why otherwise do they not run up indefinitely when the soil is placed under favourable conditions as to temperature and moisture, since the food supply is adequate? The heating and other treatment gets rid of this inhibiting factor, as it does of the majority of the bacteria; but those which remain, being free from the check previously imposed upon their development, multiply with great rapidity to an extent that they never previously could attain.

The experiments indicated that the factor in question must be a vital one, and Russell and Hutchinson concluded that it resided in a group of organisms whose existence in the soil, though known, had hitherto been regarded as without significance. These are certain organisms, large as compared with bacteria, definitely belonging to the animal kingdom, and called, from their simplicity of structure and primitiveness of type, the Protozoa. The protozoa, of which three main groups are found in soil—amœbæ, ciliates, and flagellates, are single-celled organisms, varying in size from 5 to 50 μ , which exist in the water films surrounding the soil particles and can only be active when there is sufficient moisture in the soil. They are mobile, moving, in the case of amœba by pushing out arms and flowing into them, in the other cases by their cilia or flagellum, and they obtain their nutriment by consuming bacteria. Though they are found numerously in all decaying organic materials and in putrefactive liquids, they cannot feed upon organic matter alone, but only upon the bacteria present in the material. The experiments show that there is an active population of protozoa in moist soil, increasing with its moisture and richness in organic matter. It is difficult to estimate numbers, but it is something in the order of 50,000 to 100,000 per gram of ordinary soil. They are killed off by relatively

low temperatures, and by the various antiseptics mentioned above, so that they are entirely absent from soils heated to 100° , and present only in relatively small numbers of a few species only in the less drastically treated soils. Their addition to culture media containing bacteria only has been found to limit the multiplication of the bacteria and the production of ammonia.

Much further work is yet required to clear up the whole story, but the main outlines are clear enough. Ordinary soil, in addition to its flora of bacteria preparing ammonia and nitrates from the organic reserves as food for the crop, contains also a fauna of protozoa which prey upon the bacteria and limit their multiplication. Whenever the soil is exposed to conditions favourable to the development of the bacteria, the same conditions also favour the development of the protozoa, which continue to limit the multiplication of the bacteria and therefore the preparation of available plant food, *i.e.*, the fertility of the soil. The partial sterilisation processes—heat, treatment with antiseptics, etc., cause a selective killing-off of the protozoa, and therefore remove the limitation to the succeeding development of the bacteria. In consequence, they develop to numbers unattainable in the presence of the protozoa, cause a corresponding increase in the production of ammonia, etc., and therefore in the fertility of the soil.

The extraordinary enhancement of the fertility of the soil, an enrichment that requires no additions to the stock of plant food, since it is brought about by the more rapid and complete utilisation of what is there, that can be produced in laboratory experiments by the process of partial sterilisation cannot but give rise to visions of a vastly greater productiveness to be attained from the land under cultivation. But many

practical limitations still remain to be overcome. The task of heating the layer of cultivated soil to the temperature of a little below the boiling point of water is a very great one, the heat from the combustion of three tons of coal being required to raise the temperature of an acre of soil, to the depth of a foot, by 70°. This is only the lowest possible estimate, when the whole of the heat reaches the soil and none is wasted. To realise the temperature in practice, some two or three times as much coal would be consumed and considerable labour would also be spent. The heating process has, however, been applied, with considerable practical success, to the treatment of soil from greenhouses when only small quantities of soil are involved, where heating mechanisms are at hand, and where the value of the produce is so large in relation to the soil employed that it can repay a heavy expenditure. Greenhouse soils, because of the great enrichment they are given, the high and regulated water supply and the high temperatures, very rapidly become "sick" through the extensive development of protozoa within them. It was customary to renew them at considerable expense, though the material to be replaced was still loaded with plant food. The heating processes to which they are now subjected not only renew and enhance their fertility, but at the same time get rid of nematodes and many other organisms which were injurious to the plants growing in them, so that, from the commercial point of view, the process is doubly remunerative. For the treatment of soils on a field scale, search is being made for an antiseptic that will be effective, and yet cheap enough for application on a large scale. Toluene, carbon bisulphide, etc., are too volatile to be of use in the open; what is needed is something that is volatile enough to be effective against the protozoa, and yet capable of retention for a sufficient

time to attain its full action within the soil. Both the required antiseptic and the method of applying it are now matters under systematic investigation.

The existence of "sick" soils is not confined to glass houses, and one such case, that of sewage sick soil, has been investigated and shown to be due to the presence of an excess of protozoa. In the purification of sewage by its application to cultivated land on which crops are grown, it is found that the productive power of the land, which is at first enormously enhanced by the abundant supply of water and soluble nitrogenous compounds in the sewage, after a time begins to fall off. If the land is anything heavier than almost pure sand, the physical condition suffers greatly, the surface becomes covered with a gelatinous skin of algæ and other organisms, percolation is impeded by this skin and by the deflocculation of the clay by the alkaline sewage water, in consequence the effluent is very imperfectly purified by oxidation. To some extent the condition of the soil may be ameliorated by resting the land, especially if lime is applied to flocculate the clay, and if the skin is destroyed by roughly ploughing and leaving the surface to dry out; but still the soil remains comparatively ineffective as a purifier of the sewage. Russell and Golding have shown that this condition of sickness is caused by the accumulation of active protozoa in the sewage-laden soil, in which the conditions are naturally favourable for their development. At first the soil bacteria multiply rapidly and purify the sewage by breaking down the nitrogenous materials; the numbers of the protozoa, however, grow up to the new bacterial content and then limit them, so that this powerful purifying action with the production of plant food becomes similarly limited. Treatment with toluene

and similar antiseptics is effective in restoring the soil to its earlier capacity for dealing with the sewage.

Though the experiments have as yet been tried on but a small working scale, there will undoubtedly be a valuable application in this direction of the antiseptic that is being sought for to get rid of the protozoa in ordinary cultivated soils, for by its means it will be possible to deal with sewage on much smaller areas of land than are now required for that purpose.

Iron Bacteria.

Another series of bacteria playing an interesting part in certain soils, consists of those which secrete hydrated ferric oxide or bog-iron ore in undrained soils, where the soil water contains ferrous bicarbonate in solution. Winogradsky investigated four of these organisms, to whose vital processes he considered the presence of soluble ferrous salts was essential. Molisch, however, regards the secretion of ferric hydrate as, in a sense, an accidental accompaniment of their growth, such as the separation of large quantities of silica, so characteristic of the straw of cereals, is unessential to their development. It has already been noted that these iron earths do not form in soils containing calcium carbonate, which seems to prevent the formation of any soluble ferrous compounds.

Fungi of Importance in the Soil.

Allusion has already been made to the fact that a large number of fungi inhabit the soil—*Penicillium*, *Typhula*, *Trichoderma*, *Spicaria*, etc., *Cladosporium*, *Cladobotrya*, and various wild yeasts, *Monilia*, etc.—all of which aid in breaking down the organic matter. Many of these fungi possess the power of attacking ammonium salts applied as manure, withdrawing the ammonia and

setting free the acid. To this action is due the acidity produced by the long-continued use of ammonium salts as manure, as seen on the experimental plots at Rothamsted and Woburn. At Woburn the soil is light and sandy, containing but little lime, and the application of ammonium salts containing 50 lbs. ammonia per acre every season for twenty-four years, has rendered the land practically incapable of carrying the crops. A moderate dressing of lime, however, restores the fertility. The following crops were obtained in 1900 on the barley plots:—

	Ammonium Salts only.	Minerals + Ammonium Salts.
With no Lime	5.6	12.3
With 2 tons Lime, applied Nov. 1897	28.9	33.7

The soil had become acid to litmus paper where the lime had not been used: it is interesting to note that though barley would not grow, oats flourished freely on this sour soil. There are, however, two special organisms which merit further consideration—the fungus which clothes the finer rootlets of many classes of plants, forming mycorrhiza, and the slime fungus, or *Plasmodiophora* which causes the disease known as “finger-and-toe” or “club” in turnips and other cruciferous plants.

The term “mycorrhiza” is applied to the symbiotic combination of the filaments of certain fungi, whose complete development is as yet unknown, with the finest rootlets of certain plants. Sometimes the fungus forms a sort of cap on the exterior of the short rootlets, which are generally without root-hairs; in other cases it penetrates the cortical tissue of the root itself, which may also be furnished with root-hairs. Accord-

ing to the researches of Frank, the fungus of the mycorhiza lives in symbiosis with the higher plant, attacking the humus and also the mineral resources of the soil, and passing on the food thus obtained to the host plant. In some few cases the host plant possesses no green assimilating leaves, and is wholly dependent upon mycorhiza to obtain its necessary carbon from the humus. Such a case is seen in the *Neottia Nidus-avis*, or Birds' Nest Orchis, to be found chiefly amongst beech underwood in this country.

More generally, the host plant is capable of nutrition in the ordinary way when growing in media in which nutrient salts are abundant, but becomes mycotrophic in soils and situations unfavourable to the production of directly absorbable food—as, for example, in heaths and moors, where the soil is almost wholly humus, or beneath the shade of trees, where nitrates are rarely found and where illumination is insufficient for much assimilation. Later researches, particularly those of Stahl, have shown that the symbiosis of mycorhiza, instead of being a phenomenon restricted to a few species, is widely diffused among many classes of plants, and is indeed causally connected with other facts of wide general importance in plant nutrition. It has already been indicated that the cultivated plants give off considerable quantities of water by transpiration; the form and arrangement of their leaves are adapted to expose a large evaporating surface, the root is well developed and provided with root-hairs to keep up the supply of water to the plant. There are, however, a number of plants in which transpiration is much less active, and the leaf area is restricted or otherwise arranged to diminish the loss of water, so that the proportion previously stated as existing between the dry matter produced and the water passing through the plants

is greatly diminished. A diminished supply of water to the root would, however, necessitate a loss of nutrient to the plant, as both nitrates and other mineral salts enter the plant with the transpiration water. Stahl has shown that, in general, these plants with a small transpiration activity are furnished with mycorrhiza, by means of which they obtain food of all kinds from the soil; whereas, on the contrary, the plants, like the cereals, the cruciferous and leguminous plants, Solanaceæ, etc., which give off water freely are never associated with mycorrhiza. Many of the conifers and heaths which grow on dry soils show this correlation of a low evaporation and restricted leaf development with a root-system furnished with mycorrhiza.

Another interesting generalisation has also been brought into line with the above facts by the observations of Stahl that the mycotrophic plants with a feeble transpiration do not store starch in their leaves, but contain instead considerable quantities of soluble carbohydrates, chiefly glucose. In normal plants, though sugar is the first tangible result of assimilation, it is rapidly removed from the sphere of action by being converted into starch, such withdrawal of the product of the reaction being necessary if a rapid rate of assimilation is to be maintained. Should, however, sugar accumulate in the cells, the concentration of the cell sap is increased, so that it parts with its water by transpiration less readily. Though many exceptions can be observed, there seems to be a very general association of the development of mycorrhiza with a diminished transpiration and the absence of starch from the leaf, especially among plants like the orchids, lilies, iris, etc., which often grow in dry or shady situations, such plants being further distinguishable by a shiny, glossy leaf surface. Stahl has again

shown that the average proportion of ash to dry matter in the leaf is lower for mycotrophic than for normal plants; the former grow, as a rule, in situations containing but little mineral salts, particularly in humic soils, where, in addition, the plant is put into competition for whatever nutriment may be present with the mycelia of fungi, which everywhere traverse humus in its natural state. By direct experiment, it has been shown that normal plants grown in humus develop better when the humus is previously sterilised by long exposure to chloroform vapour than when it is in its fresh condition, full of living mycelia competing successfully for the nutriment. The absence in the leaf of calcium oxalate and of nitrates is particularly characteristic of mycotrophic plants.

Stahl concludes that symbiosis between the roots of plants and the mycelia of fungi is a very general phenomenon, especially characteristic of plants growing in soils subject to drought, or poor in mineral salts, or rich in humus. These mycotrophic plants are generally of slow growth, possess a feeble transpiration, and limited root development; their leaves rarely contain starch; they are also characterised by containing a comparatively small proportion of mineral salts, among which calcium oxalate and nitrate are notably absent.

To the mycorhiza associated with plants of the genus *Erica* the power of fixing atmospheric nitrogen has been attributed, but the question still requires further investigation.

The existence of mycotrophy has certain interesting applications in practice; there are many plants which can only be cultivated with difficulty in gardens; for example, some of the orchids, ericas, lilies, and others, generally plants which must be grown in leaf-mould, peat, or other material rich in humus. Yet humus

alone is not always sufficient for the purpose, the peat or leaf-mould has often to be obtained from a particular place; other materials, though equally rich in humus and possessing similar mechanical properties, prove quite unsuitable. It is easy to surmise that this effect, confined in the main to mycotrophic plants and humic soils, may easily be due to the absence of the proper fungus from the soils found to be unsuitable.

It has also been shown that the difficulty usually experienced in raising seedlings of exotic orchids, which die off in great number just after they have germinated, may, to a large extent, be obviated by mixing with the medium in which the seeds are sown a little of the material in which the parent plants are growing. The young seedling is found to develop mycorrhiza at a very early stage, and only then will grow properly.

"Finger-and-Toe."

On many soils, particularly those of a sandy nature, the turnip crop is often almost wholly destroyed by the disease known as "finger-and-toe," "club," or "anbury." Cabbages and other cruciferous crops are equally attacked; so much so, that in gardens which have become infected it is practically impossible to raise crops of this nature. The disease is caused by an organism, *Plasmodiophora brassicæ*, belonging to the slime fungi and forming spores which may remain dormant in the soil for some time, certainly for two or three years. It has long been known that the best remedy against finger-and-toe consists in the application of lime; and as far back as 1859, Voelcker showed that soils on which this disease is prevalent are deficient in lime; and in many cases in potash also. Later researches have only served to emphasise the fact that the disease is associated with

soils of an acid reaction, in which calcium carbonate is wanting, or present in very small proportions. The fungus, as is generally the case with fungi, refuses to grow in a neutral or slightly alkaline medium, and the only way to get rid of the infection in the land is to restore its neutrality by repeated dressings of lime. At the same time, the land should be rested as long as possible from cruciferous crops; uneaten fragments of diseased turnips, etc., should not be allowed to go into the dung, or if they do, the dung should be used on the grass land. Manures, again, which remove calcium carbonate from the soil, like sulphate of ammonia or acid manures like superphosphate, should not be employed; neutral or basic phosphates, with sulphate of potash on sandy soils, should be employed instead.

The following figures show the amount of lime dissolved by hydrochloric acid from soils affected with "finger-and-toe," as compared with spots in the same field where the disease was not in evidence:—

	LIME PER CHT.				
	Voelcker.	Voelcker.	Hall.	Sandy Soil.	Clay Soil.
Soils affected by disease.	.14	.084	.13	.31	.39
Soils free from disease . .	.89	.52	.43

It must be remembered that in these cases the total lime soluble in acids is given, not merely the lime present in carbonate.

Whenever a turnip crop is seen to be infected with "finger-and-toe" the land should be well dressed with 3 or 4 tons per acre of quicklime immediately the crop has been removed; as long an interval as possible should be given before again taking a cruciferous crop,

substituting, for example, mangolds for turnips in the next rotation; every effort should be made to destroy cruciferous weeds like charlock; turnip-fed dung should not be applied, and another dressing of finely divided quicklime should be put on for the crop preceding the sowing of the new turnip crop.

CHAPTER VIII

THE POWER OF THE SOIL TO ABSORB SALTS

Retention of Manures by the Soil—The Absorption of Ammonia and its Salts ; of Potash ; of Phosphoric Acid—Chemical and Physical Agencies at Work—The Non-Retention of Nitrates—The Composition of Drainage Waters—Loss of Nitrates by the Land—Time of Application of Manures.

MANY of the substances employed as manures are soluble in water, hence it becomes important to ascertain what is likely to be their fate in the soil, when their application is followed by sufficient rain to cause percolation into the subsoil. Of substances containing nitrogen, nitrate of soda, the salts of ammonia, urea, and kindred bodies are freely soluble in water; superphosphate alone of the compounds of phosphoric acid commonly used as manure is soluble; but sulphate, chloride, and carbonate of potash are easily soluble.

Not long after the principles underlying the nutrition of plants had been established, Thompson and Way showed that ordinary soil possesses the power of withdrawing most of the above substances from solution, and so saving them from washing away into the subsoil or the drains. Some of the salts, like sulphate of ammonia, are decomposed, the base alone being re-

tained and the acid draining through. Way found that liquid manure from a dung-heap, which contains both organic and ammoniacal compounds of nitrogen, potash, and a little phosphoric acid, when filtered through a short column of soil, parted with almost the whole of its organic matter and much of its salts to the soil; compounds of calcium were, however, more abundant in the filtered liquid than before. Way's observations were extended by Voelcker, who compared the absorbing powers of different types of soils, and so obtained an idea of the method by which the absorption of each substance was effected; and later researches have only served to confirm the results then obtained. It was found that all the organic compounds of nitrogen, ammonia—either free or in combination,—phosphoric acid, and potash were almost wholly removed from solution by ordinary soil, though some soils were more effective than others; whereas nitrates, sulphates, chlorides, and, among bases, sodium and calcium, were only slightly, if at all, retained. These results are confirmed by the analysis of the water which flows from land drains under normal conditions; this will generally be found to contain nitrates (sometimes in fair quantity), sulphates and chlorides of calcium and sodium, and considerable amounts of calcium bicarbonate, but rarely more than a trace of ammonia, phosphoric acid, or potash. The absorptive action of the soil is partly a chemical process, due to interactions with the zeolitic double silicates and the calcium carbonate of the soil; and partly physical, dependent upon the extent and nature of the surface offered by the soil particles (for the surface of a solid possesses the power of concentrating molecules of any dissolved substance in the layer of solution with which it is immediately in contact). Adsorption, as this process is called, is a

characteristic property of colloids, and as we have already seen (p. 39), the clay and humus of soil behave as typical colloids. It has long been known that soils and even pure sand will remove sodium chloride from solution if the filtering column be sufficiently long; but the sand soon becomes saturated with salt and the water will begin to come through more and more salty. The soil materials have little adsorptive power for the sodium or the chlorine ions.

The absorption of the organic compounds of nitrogen by the soil is purely one of adsorption, comparable to the action of charcoal in absorbing ammonia or the strongly smelling products of putrefaction, etc. The deodorising powers of earth for fæcal and decomposing matter are very familiar; this means that fixation in a more or less insoluble and non-volatile state of various organic nitrogen and sulphur compounds is effected, and other inodorous nitrogen compounds are retained in the same way. The absorption is most marked with soils rich in humus or in clay—the colloid soil materials. The absorptive power of soil for organic compounds of nitrogen is well seen in a sewage farm, the object of which is to so far purify sewage by percolation through a few feet of soil, as to fit it to be turned into a river without danger to health. For example, on the Manchester Sewage Works, in 1900, percolation through 5 feet of soil reduced the organic nitrogen in the liquid from 0.26 to 0.056 parts per million, and the free ammonia from 1.89 to 0.92. It is necessary, also, on a sewage farm to work with soils possessing but a small absorbing power; only sandy and gravelly soils will permit of rapid enough percolation, both to deal with large volumes of sewage and afterwards to aerate themselves and accomplish the destruction by bacterial action of the absorbed material. Stiffer soils would

be far more effectual absorbents of the sewage material, but are unsuitable because they do not admit of percolation.

Absorption of Ammonium Salts.

The absorption of free ammonia follows the lines indicated above for the absorption of the organic compounds of nitrogen; but the retention of salts of ammonia may be interpreted either as a colloid adsorption process or as a purely chemical reaction in which the double silicates or zeolites and calcium humate take part. Way and Voelcker first found that when either the sulphate, chloride, or nitrate of ammonia in solution is allowed to remain in contact with soil, the base is absorbed, but the acid portion of the salt remains in solution in combination with lime. Voelcker also showed that when soil was shaken up with dilute solutions of ammonium salts, the withdrawal of ammonia from the solution was never complete, but varied both with the nature of the soil and the strength of the solution, a greater proportion being taken from weak than from strong solutions.

The readiest way of explaining this action is to suppose that a double decomposition takes place with the zeolitic silicates. Ammonium enters into the compound and turns out equivalent amounts of calcium, magnesium, potassium (sodium also on occasion), which enter into combination with the acid in the solution, for no acid is absorbed and the whole solution remains neutral.

The reaction is a reversible one, but the clay containing the zeolites is not capable of absorbing more than a certain small amount of ammonium from the strongest solutions of its salts. The following table shows the ammonia absorbed by 100 grams of very

pure clay when shaken with 300 c.c. of ammonium chloride solution of varying strengths.


Original Concentration of Solution.	Ammonia Withdrawn.	Ammonia Withdrawn.
	Grams.	Per cent.
N/10	0.126	24.7
N/12	0.115	28.1
N/15	0.104	30.5
N/20	0.090	35.3
N/30	0.068	40.3
N/50	0.049	48.0
N/100	0.031	60.0

Thus from the weaker solutions a smaller total but a larger proportion of the ammonia was removed by the clay, and the removal was never complete. The view of the process that is now more generally accepted is that the first step is the practically instantaneous adsorption by the soil of the ammonium ion of the salt, the acid ion being set free. This acid ion then proceeds to combine with an equivalent amount of calcium or other base in the zeolitic silicates, thus restoring the neutrality of the solution. This interpretation is in harmony with the proportion in which the ammonia is always shared between the soil and the solution, and the fact that its withdrawal from solution is never complete. Of course, in the field the amount of soil is so enormously in excess that the absorption of ammonium salts applied as manure is practically complete. Thus at Rothamsted the presence of ammonia in the drainage water is rarely detected, even when heavy rain immediately follows the application of the manures.

The adsorption of ammonium salts by humus follows much the same course as with clay. The ammonium

is adsorbed and the acid ion set free combines with the calcium which is present as a base in the calcium "humate."

With the calcium carbonate of soils a double decomposition of the type—



—takes place, not only with such substances as ammonium sulphate, but also with humic and zeolitic compounds of ammonium, and though the proportion converted into carbonate is small, it is constantly renewed as the ammonium carbonate is nitrified, so that eventually the whole of the ammonium salt applied to the land undergoes this change.

In consequence, the continued use of ammonium salts as a fertiliser results in the depletion of the stores of calcium carbonate in the soil, as may be seen from the following determinations of the rate of disappearance between 1865 and 1904, of calcium carbonate from some of the soils of the Rothamsted wheat field where the calcium carbonate is of artificial origin and is confined to the surface layer of the soil.

Plot.	Manuring.	Rate of Loss of Calcium Carbonate.
	Per acre per annum.	Lbs. per acre per annum.
3	Unmanured	800
5	Mineral Manures only	880
6	" " + 200 lbs. Ammonium Salts	1170
7	" " + 400 " "	1010
8	" " + 600 " "	1170
9	" " + 412 lbs. Sodium Nitrate .	565
10	400 lbs. Ammonium Salts only	1045
2	Farmyard Manure	590

Thus the use of ammonium salts increases the normal loss of calcium carbonate experienced by the soil (due to solution as bicarbonate), and the amount removed increases with the larger applications of ammonium salts. Taking the mean of these and other results obtained at Rothamsted, 200 lbs. of ammonium salts causes a removal of about 120 lbs. calcium carbonate, whereas the amount calculated from the equation given above would be about 160 lbs. That the loss from the plots receiving sodium nitrate and dung is less than from the unmanured plot, is due, in the former case, to the base left in the soil by the growth of plants which derive their nitrogen from sodium nitrate, and in the latter, to calcium carbonate formed by bacterial action from organic calcium salts in the dung.

The Absorption of Potash.

In all respects the absorption of potash follows the same laws as that of ammonia: *i.e.*, caustic potash is absorbed directly, but with sulphate, nitrate, and chloride of potash the adsorption of the base is accompanied by an attack of the acids set free upon the calcium or other bases in the double silicates of the soil, so that the solution is left neutral. In the ordinary way potash is retained and calcium sulphate, nitrate, or chloride, appear in the water draining through the soil. Voelcker found in laboratory experiments with small quantities of soil that potassium carbonate was more freely absorbed than sulphate, and that clays, marls, and pasture soils were more effective in retaining potash than light loams or sands, which latter had but little absorbing power.

The following table shows some of the results obtained when potash and soda salts were compared:—

Percentage retained.	Potash.	Soda.
Chalky Loam . . .	3.6	0.8
Clay	4.0	1.1
Sandy Loam . . .	2.6	0.6
Pasture	3.8	1.0
Loam	3.4	1.0
Ironstone Sand . .	1.1	0.6

Both the humus and the zeolitic double silicates take part in the retention of the potash salts, the reactions being exactly similar to those taking place with the ammonium salts. In some of Way's experiments with pure clays the application of potash salts was followed by the appearance of the corresponding sodium salts in the percolating water, though with most soils it is calcium that is turned out of combination. Potash salts applied to the soil also react to a certain extent with the calcium carbonate, giving rise to a little potassium carbonate, the bad effect of which upon the tilth of the soil will be considered later (p. 293). Dyer has examined the soils of the Rothamsted wheat plots which had then been continuously manured in the same way for fifty years, with the view of tracing the fate of the mineral manures applied. The following table shows a comparison of the amounts of potash soluble in strong hydrochloric acid, in lbs. per acre, found in the top 9 inches of soil from four of the plots; one (No. 11) received nitrogen and phosphates, but no potash, every year, the others were variously manured, but all received 200 lbs. per acre of sulphate of potash. Estimates are also given of the total amount of potash applied as manure and removed in the crops over the whole period, so that in the last two columns a comparison can be made between the actual surplus of potash in the manured over the unmanured soils, and the surplus calculated from the

differences between the potash added in the manure and removed in the crops:—

Plot and Manuring, per Acre.	POTASH—LBS. PER ACRE.			SURPLUS OVER PLOT 11.	
	In top 9 inches of Soil.	Added in Manure.	Removed in Crop.	Calculated.	Found.
11, receiving no Potash .	5107	15	1190
7 receiving 200 lbs. Sul- phate of Potash .	6793	5037	2550	3662	1686
5, receiving 200 lbs. Sul- phate of Potash .	7233	5203	1136	5242	2126
13, receiving 200 lbs. Sul- phate of Potash .	7078	5287	2410	4052	1971

On the whole, about one-half of the estimated surplus of potash received by the manured plots still remains in the top 9 inches of soil.

Dyer further estimated the proportions of potash in the same soils which was soluble in a 1 per cent. solution of citric acid, and found that both the surface and the subsoil down to a depth of 27 inches contained more of this readily soluble potash where it had been applied as manure, than did the companion plot receiving no potash, as will be seen from the following table:—

Plot.	LBS. PER ACRE OF POTASH, SOLUBLE IN 1 PER CENT. CITRIC ACID.			SURPLUS OVER PLOT 11:	
	First 9 inches.	Second 9 inches.	Third 9 inches.	Calculated.	Found.
11	83	75	101
7	602	374	179	3662	896
5	799	598	257	5242	1395
13	487	363	235	4052	826

These determinations show that soluble potash salts applied to the land are retained chiefly by the surface soil, as much as one-half of the estimated additions of

potash during fifty years' manuring being found there. Some of the potash, however, sinks further and is retained in the subsoil; in the top 27 inches a large proportion—nearly one-quarter of the whole—remains in such a loose state of combination that it is soluble in 1 per cent. citric acid, and so may be regarded as available for the plant.

Absorption of Phosphoric Acid.

The retention of soluble phosphoric acid by the soil is easily intelligible on chemical grounds, for there are present several substances capable of forming insoluble compounds with phosphoric acid—*e.g.*, calcium carbonate, hydrated ferric oxide, and the hydrated silicates of alumina which make up so much of clay. Soil has, however, an adsorptive power for phosphoric acid, and, as Russell has shown, the action of very dilute acids upon soil can best be explained by assuming a preliminary solution of the phosphoric acid followed by an adsorption, the extent of which is conditioned by the nature and strength of the dilute acid with which the soil is in contact.

The following table shows the percentages of the total phosphoric acid supplied, which were removed from solution by various soils after remaining in contact for the specified times, the ratio between soil and phosphoric acid being about 1000 to 1.

PERCENTAGE OF PHOSPHORIC ACID ABSORBED (VOELCKER).

	After 1 day.	After 8 days.	After 26 days.
Red Loam . . .	60	78	95
Chalky Soil . . .	89	99	100
Stiff Clay . . .	51	62	86
Stiff Subsoil . . .	48	69	74
Light Sandy Soil . .	53	59	73

In an ordinary soil containing a sufficiency of calcium carbonate, the application of soluble phosphoric acid like superphosphate will chiefly result in the precipitation of di-calcium or "reverted" phosphate, wherever the solution meets with a particle of calcium carbonate. This di-calcium phosphate is a compound easily soluble in weak organic acids or in water containing carbonic acid: hence the great value of applications of superphosphate on soils rich in lime, for thus a readily available phosphate is very quickly disseminated throughout the ground in a state of fine division. But on soils poor in calcium carbonate the precipitation will be chiefly effected by the hydrated iron and aluminium compounds, and the resulting phosphates are practically insoluble in water containing carbonic acid, and but little in saline solutions or in weak organic acids. Hence applications of superphosphate to such soils become much less available to the crop, and should be preceded by a thorough liming of the land. Even a subsequent liming on soils containing phosphates of iron or alumina will help to bring them into a more available form, because a double decomposition resulting in calcium phosphate and aluminium or ferric hydrate will proceed to an extent dependent on the mass of lime present in the medium.

Further evidence of the precipitation of phosphoric acid within the soil is afforded by Dyer's examination of the Rothamsted wheat soils at various depths, after fifty years' continuous manuring with and without superphosphate. By comparing the amount of phosphoric acid contained in the soil of the unmanured plot with that contained in the soils of the plots receiving superphosphate every year, and knowing also the amount removed by the successive crops in each case, it is possible to calculate the surplus that should

remain in the manured over the unmanured plots, on the assumption that the soil was uniform at starting. Calculating in this way, Dyer found that no less than 83 per cent. of the phosphoric acid which six of the plots should possess after fifty years' manuring was still present in the top 9 inches of soil, whereas the subsoils from 9 inches to 18 inches, and 18 inches to 27 inches, showed no accumulation of phosphate. Dyer further determined the phosphoric acid which was soluble in a 1 per cent. solution of citric acid and found that on the manured plots the top 9 inches of soil contained about 39 per cent. of the estimated surplus of phosphoric acid so combined as to be insoluble in this medium, whereas in the subsoils the "available" phosphoric acid was, if anything, less for the manured than for the unmanured plots. It has already been pointed out (p. 185) that if the extraction with citric acid be repeated, practically the whole of the phosphoric acid applied as manure and not removed by the crop can be recovered from the top 9 inches of the Rothamsted soils. It is clear, then, that soils well provided with calcium carbonate, as the Rothamsted soils, will precipitate very near the surface any soluble phosphoric acid applied, and retain it for a long time in a form easily redissolved and obtainable by the plant. It follows, therefore, that superphosphate, the most soluble of the phosphatic manures, can be applied to normal soils in the winter or early spring without any fear of the phosphoric acid being washed out.

The Composition of Drainage Waters.

Further evidence of the fate of the various substances applied as manures, their retention or otherwise by the soil, can be obtained by studying the composition of the water flowing from land drains.

The drainage from the continuously manured wheat plots at Rothamsted, each of which possesses a tile drain running down the centre at a depth of 2 feet to 2 feet 6 inches, has been collected from time to time and completely analysed by Voelcker and Frankland; in addition, systematic determinations of the nitrogen contents have been made for many years. In a general way, the chief constituent of the various drainage waters is lime, either as bicarbonate, sulphate, chloride, or nitrate; soda is the only other base present in any quantity, very small amounts of magnesia, potash, and ammonia pass into the drains. Of the acid radicles, chlorine and sulphuric acid predominate, according to the manuring, and the proportion of phosphoric acid is minute; but the amount of nitric acid varies according to the manure applied and the season at which the water is collected.

The table on p. 260 shows the complete analysis of the drainage water from twelve of the plots.

An examination of these figures shows that the amount of organic matter and ammonia reaching the drains is practically nil; the organic matter supplied as dung, and the ammonia, which is employed up to 400 lbs. of mixed ammonium chloride and sulphate per acre, are wholly retained by the soil. The effect, however, of adding either organic compounds of nitrogen or ammonium salts is to increase the proportion of nitrates in the drainage water. Lime is the chief constituent of the dissolved matter in the drainage waters, the proportion is lowest for the unmanured plot (3), it rises with the application of minerals (5), and rises again with each successive application of ammonium salts (6) and (7). The formation of calcium chloride and sulphate respectively, when the corresponding ammonium salts are applied to land containing calcium carbonate, has already been discussed: it is well seen in the increased richness in

COMPOSITION OF DRAINAGE WATERS FROM BROADBALK FIELD, ROTHAMSTED,
IN PARTS PER MILLION (VOELCKER).

Plot.	2	3 & 4	5	6	7	9	10	11	12	13	14
Manuring.	Dung.	0	MINERALS.				400 LBS. AMMONIUM SALTS.				
			0	+200 lbs. Ammonium Salts.	+400 lbs. Ammonium Salts.	+650 lbs. Nitrato of Soda.	0	+Superphosphate.			
								0	+ Sulphate of Soda.	+ Sulphate of Potash.	+ Magnesia
Organic Matter . . .	26.1	22.9	19.3	25.7	34.9	26.7	33.6	38.4	29.3	45.3	56.1
Nitrogen as Nitric Acid . .	16.1	3.90	5.10	8.50	14.0	18.4	13.9	15.3	15.1	17.4	19.2
Nitrogen as Ammonia . . .	0.16	0.12	0.13	0.20	0.07	0.24	0.08	0.17	0.30	0.16	0.09
Lime . . .	147.4	98.1	124.3	143.9	181.4	118.1	154.1	165.6	191.6	201.4	226.7
Magnesia . . .	4.9	5.1	6.4	7.9	8.3	5.9	7.4	7.3	6.6	9.3	11.6
Soda . . .	5.4	1.7	5.4	4.4	2.9	4.1	1.9	1.0	2.7	3.3	1.0
Potash . . .	13.7	6.0	11.7	10.7	10.9	56.1	7.1	6.6	24.6	6.1	5.6
Oxide of Iron . . .	2.6	5.7	4.4	2.7	8.1	5.1	4.0	3.4	3.6	3.7	3.7
Chlorine . . .	20.7	10.7	11.1	20.7	26.1	12.0	32.0	31.6	30.9	30.6	39.4
Sulphuric Acid . . .	106.1	24.7	66.3	73.3	90.1	41.0	44.4	54.3	96.7	86.9	99.7
Phosphoric Acid	0.63	0.91	1.54	0.91	...	1.44	1.66	1.26	1.09	1.01
Carbonic Acid . . .	43.3	48.1	44.4	59.0	58.0	73.0	45.4	44.9	64.6	51.1	56.9
Silica . . .	35.7	10.9	15.4	24.7	17.0	10.6	10.9	11.3	17.9	28.3	14.0
Total Solids . . .	476.1	246.4	326.0	407.6	492.4	433.9	406.9	425.9	530.9	544.3	598.6

lime, sulphuric acid, and chlorine of the drainage water from 6 and 7, which receive 200 and 400 lbs. respectively of ammonium salts, as compared with 5, which receives the same minerals without any nitrogen compounds. Plot 11 receives superphosphate in addition to the ammonium salts which 10 receives: the effect of the gypsum contained in the superphosphate is seen in the increased lime and sulphuric acid content of the drainage water of 11. The increase is not so great, however, as that caused by the addition of sulphates of potash and magnesia to the superphosphate and ammonium salts (plots 13 and 14) whereas sulphate of soda causes little loss of lime (12). The use of nitrate of soda on plot 9 causes no increase in the proportion of lime in the drainage water, but a large quantity is removed, chiefly as sulphate, from plot 2, receiving dung every year. The quantity of lime removed annually in this way will be very great: assuming a mean annual drainage equal to 10 inches of water, the unmanured plot will lose about 220 lbs. per acre per annum of lime: equivalent to about 400 lbs. of carbonate of lime, whereas the analysis of the soil shows (p. 252) an annual loss of about 800 lbs. per acre. The discrepancy between these two figures is due to the fact that the results are calculated from but a small number of analyses of the drainage water, the amount of which is also very uncertain. When 400 lbs. of ammonium salts are used as manure, either alone or with minerals, the increased loss of lime calculated on the same basis amounts to 126 lbs. or 225 lbs. of carbonate of lime per acre per annum, as against about 240 lbs. found from the analysis of the soil.

The amount of magnesia lost is small, 5 to 20 lbs. per acre per annum, nor is the amount reaching the drainage water much increased by its application as manure to plots 5, 6, 7, 9, and 14.

The amount of potash lost is still smaller, from 3 to 12 lbs. per acre per annum, but it is distinctly dependent on the amount supplied as manure, being at a maximum with the dunged plot (2) and the plot receiving minerals only (5), and greater from all the other plots receiving potash than from those without it, *i.e.*, 3, 10, 11, 12, 14. The use of sulphate or nitrate of soda increases the amount of potash in the drainage water, not so, however, the use of sulphate of magnesia. Practically all the soda, chlorine, and nearly all the sulphuric acid, that are applied in the manure pass through into the drainage water.

A comparison of the drainage waters in winter and spring shows that they are more concentrated in the winter, because the manures (excepting the nitrate of soda) have then been recently applied: the chlorides wash out first, then the sulphates, and as the season advances not only is the total amount of lime present much diminished, but it comes away chiefly as carbonate. With the growth of the crop in spring the nitrates disappear from the drainage waters.

The amount of nitrates found in the drainage water varies not only with the time of year, but also according to the interaction of temperature, growth of crop, cultivation, and percolation. Nitrates are only rapidly produced when the temperature of the soil has risen: if the percolation is not excessive the crop may remove the nitrates as fast as they are formed, but a heavy rainfall in the spring before the nitrates have been much drawn upon by the crop, or one just after the land has been broken up in the autumn and is still warm, will result in a considerable washing out of nitrates. At the same time a certain amount of moisture in the soil is necessary for the formation of nitrates, and the crop itself may so

dry the soil as to reduce nitrification considerably. The following table shows the estimated loss of nitrates from the same wheat plots at Rothamsted as have previously been dealt with, during two years, each of which has been divided into two periods: firstly, from the date at which the nitrogenous manures were sown up to harvest; and secondly, from harvest round again to the sowing of manures in spring.

NITRIC NITROGEN IN DRAINAGE WATER.—LBS. PER ACRE.

Plot.	Manuring, per Acre.	1879-80.		1880-81.	
		Spring Sowing to Harvest.	Harvest to Spring Sowing.	Spring Sowing to Harvest.	Harvest to Spring Sowing.
3	Unmanured	1.7	10.8	0.6	17.1
5	Minerals only	1.6	13.3	0.7	17.7
6	Minerals + 200 lbs. Ammonium Salts	10.1	12.6	2.2	19.8
7	" + 400 "	18.3	12.6	4.3	21.4
9	" + 550 " Nitrate of Soda	45.0	15.6	15.0	41.0
10	400 lbs. Ammonium Salts alone .	42.9	14.3	7.4	35.2
11	Do. do. + Superphosphate	28.3	17.7	3.4	29.6
12	Do. do. + Sulph. Soda .	21.2	17.5	3.3	27.2
13	Do. do. + Sulph. Potash .	19.0	16.4	3.7	25.3
14	Do. do. + Sulph. Mag. .	26.0	16.8	4.2	25.9
15	Minerals + 400 lbs. Ammonium Salts in Autumn	9.6	59.9	3.4	74.9
	Estimated Drainage— <i>inches</i> .	11.1	4.7	1.8	18.8

The diagram (Fig. 16) shows the same results in a graphic form.

The seasons were rather exceptional, the summer rainfall and drainage in 1879 and the winter rainfall in the following year being both above the average. It will be seen that except on the autumn manured plot 15, the loss was greatest from plot 9 receiving 550 lbs. of nitrate of soda, and this excess of loss was chiefly in




FIG. 16.—Losses of Nitrogen in Drainage from Rothamsted Wheat Plots.

Black = Losses in Summers 1879, 1880.
 Shaded = Losses in following Winters.

the summer drainage water of 1879; the figures are, however, exaggerated by the fact that half the nitrate plot received no mineral manures, and therefore grew but a scanty crop. The losses during the winter months are more nearly the same for all plots, and represent to a large degree the nitrification of the organic residues in the soil. The losses from the plots receiving minerals and varying amounts of ammonium salts (5, 6, and 7) increase with each application of nitrogen: the losses from the plots receiving ammonia and various mineral manures diminish as the mineral manure becomes a more complete plant food, because the greater growth of crop thus secured more completely removes the nitrates as they are formed, besides hindering nitrification by drying the surface soil.

The effect on nitrification of crop and surface cultivation is well seen in the following table of results

Cropping.	Drainage.	Nitrogen as Nitric Acid.
	Inches.	Lbs. per acre in Drainage Water.
Fallow, no cultivation	11.2	186.70
Rye Grass	7.8	2.28
Oats	7.3	7.37
Maize	6.9	21.60
Wheat, followed by Vetches . .	6.6	12.90
Wheat	7.5	28.70
Fallow, hoed	11.5	196.56
Fallow, no cultivation	11.2	158.00
Fallow, hoed and rolled	11.2	183.20
Vine	7.5	36.20
Sugar Beet	7.2	0.27

obtained by Dehérain, who collected the drainage from cement tanks 2 m. cube and systematically filled with soil taken from corresponding depths in the field. The soils had been several years in the tanks, so that they had settled down into practically normal conditions,

though the effect of the aeration and disturbance of the soil in filling the tanks is still visible in a rather high rate of nitrification. Each tank carried the crop indicated in the first column.

The rainfall of the year in question, March 1896 to March 1897, amounted to 28.8 inches, most of which fell in the autumn. The most noteworthy results are the effect of the various crops in diminishing the loss of nitrates, which is not wholly to be attributed to the quantity taken up by the crop, because the sum of the nitrogen removed in the crop and that carried off in the drainage water is never equal to the nitrogen removed from the uncropped plots by the drainage water alone. During the comparatively dry spring months the crops leave so little moisture in the soil that nitrification is checked, and the total production of nitrates is less where there is a crop than on the moister uncropped plots.

When the wheat was followed by a crop of vetches the loss of nitrates during the comparatively wet autumn was considerably reduced. Lastly, the hoeing of the fallow plots resulted in a considerably increased production of nitrates.

Time of Application of Manures.

The facts set out above as to the retention of most of the soluble constituents of manures by the soil, while the nitrates are liable to wash out, have an important bearing on the season at which artificial manures should be sown. In the first place it is evident that there is no danger of losing phosphates, or even of their washing deep into the soil, when employed in their most soluble form as superphosphate. It is the general custom to sow superphosphate with the drill for roots at the same time as the seed: the large

quantity of manure near the seedling in its early critical stages is probably valuable, and as the roots of swedes and turnips do not extend very deeply, the phosphoric acid may be placed in the most likely place to reach them.

But for more deeply rooting crops, hops and fruit or even mangolds, it seems probable that superphosphate is often applied rather too late in the season, and that if used as a winter instead of a spring dressing it would have a better chance of getting well diffused through the soil. Basic slag and other insoluble phosphates should be used in the winter or even the autumn: there is no risk of loss, and as much rain as possible is wanted to get them distributed in the soil. As regards potash salts, Dyer's experiments go to show that they descend further in the soil, and are a little more subject to washing than the soluble phosphates: for this reason, where sulphate of potash is employed, as for potatoes, it will best be sown with the seed. Where kainit is used, it is best employed as a winter or autumn dressing; there will be little loss of potash, for this will get fixed chiefly in the surface soil. But the chlorides, which are present in kainit and are sometimes not wholly beneficial in their action upon the crop, will be removed and washed out into the drains or the subsoil water by the winter rains: the magnesia salts also will be precipitated within the soil, and to a large extent removed from possible action upon the crop. Turning to the nitrogen compounds, it is necessary to keep in mind that all of them will become transformed into nitrates which are liable to be washed out. All insoluble organic manures should be put on before or during the winter: the decay processes will begin, resulting in the formation of amino-acids, ammonia, etc., which will become fixed in the soil, but

the low winter temperatures will not permit of much nitrification. Liquid manure and similar materials containing such readily nitrifiable substances as urea and ammonium carbonate, should be reserved until early spring, so that the crop may be growing whenever nitrification begins. Ammonium salts are very rapidly nitrified, so that they should only be used in spring. At Rothamsted nitrates begin to appear in the drainage water immediately after the application of the ammonium salts to the wheat plots in March if rain falls, and one of the plots which has its ammonium salts applied in autumn shows not only a considerable falling-off in crop but also large quantities of nitrates in the winter drainage waters.

The following table shows the amounts of nitrates removed in the drainage water from the two plots which receive 400 lbs. per acre of ammonium salts with mineral

1879-1881.—LBS. OF NITRIC NITROGEN PER ACRE.

Plot.	1879-80.		1880-81.		Crop.	
	Spring Sowing to Harvest.	Harvest to Spring Sowing.	Spring Sowing to Harvest.	Harvest to Spring Sowing.	Grain.	Straw.
					Bushels.	Cwt.
7	18.31	12.63	4.29	21.38	31½	31
15	9.62	59.92	...	74.94	28½	26½
Drainage	11.1"	4.7"	1.8"	18.8"

manures, only differing in the fact that on plot 7 the ammonium salts are sown in March, and on plot 15 in October; also the average crops of grain and straw for the twenty-three years, 1875-97.

That sulphate of ammonia will to some extent

persist in the soil and become available for a succeeding crop, after even a whole year has elapsed, is to be seen from the results of the Woburn experiments upon wheat. Some of the plots at Woburn receive mineral manures every year, but ammonium salts or nitrate of soda only every alternate year: in both cases the crop falls very much in the years of no nitrogen, but the decrease is by no means so marked with ammonium salts as with nitrate of soda, which latter seems to leave no residue whatever.

The soil at Woburn is an open sandy loam; but in the years for which the results are quoted the rainfall was low—

Plot.	1899.	Bushels.	1900.	Bushels.
8B	Minerals only . . .	20.3	Minerals + Ammonium	
8A	Minerals + Ammonium		Salts	27.3
	Salts	33.1	Minerals only . . .	16.2
9B	Minerals only . . .	9.8	Minerals + Nitrate of	
9A	Minerals + Nitrate of		Soda	27.7
	Soda	4.1	Minerals only . . .	6.8
4	Minerals only, every			
	year	6.9	Minerals only . . .	5.9

The difference between the results set out in the table on p. 268 and those obtained upon the corresponding plot at Rothamsted, where the dressing of ammonium salts every other year seems to leave no residue for the following year, may perhaps be set down to the different texture of the two soils. The ammonium salts are converted which are washed down into the subsoil; at Woburn they can rise again by capillarity, as the soil, though sandy, is still fine in texture; at Rothamsted the soil is too close-grained to admit of any considerable movement of the subsoil water back to the surface.

The experiments recorded above and the results of the examination of drainage waters go to show that nitrate of soda should only be employed when there is a crop in possession of the ground and ready to seize upon the salt as soon as it becomes diffused through the soil. Only on dry soils can it be safely applied as early as the sowing of the seed; in wet climates sulphate of ammonia will often be preferable if the soil is warm enough to induce reasonably quick nitrification, and when large quantities of nitrate are wanted they should be put on by successive applications of not more than 1 cwt. per acre at a time.

CHAPTER IX

CAUSES OF FERTILITY AND STERILITY OF SOILS

Meaning of Fertility and Condition—"Fairy Rings"—Causes of Sterility: Drought, Waterlogging, Presence of Injurious Salts—Alkali Soils and Irrigation Water—Effect of Fertilisers upon the Texture of the Soil—The Amelioration of Soils by Warping, Liming, Marling, Claying, Paring, and Burning—The Reclamation of Peat and Heath Land.

IN discussing the question of fertility, a difficulty at the outset crops up in the definition of the term "fertility": we are dealing with something intangible and dependent upon so many varying factors that it becomes a matter of judgment and experience rather than of scientific measurement. We have to distinguish between the fertility proper, "the inherent capabilities of the soil," to use the language of the old Agricultural Holdings Act, which is the property of the landlord, and for which the tenant pays rent; and the "condition" or "cumulative fertility," the more temporary value which is made or marred by the tenant. Though in the main it is easy to feel the distinction, it is often difficult, if not impossible, to draw a line of demarcation between them. Clearly the farmer in a new country on virgin soil is dependent wholly on the inherent fertility of the land, but with much of the land in this country it is hard to say how far its value is inherent, or due to long-continued cultivation. When a tenant by many

years of skilful management makes a good pasture, the improvement is rightly credited to him, as fertility which he has accumulated: the next tenant must regard the same pasture as part of the inherent capacity of the soil. Again, a farmer working on the old four course rotation, selling only corn and meat and purchasing neither feeding stuffs nor manures, is dependent on the fertility of the soil: another farmer, carrying on an agricultural business such as market gardening or hop-growing, and putting more into the land every year as manure than he takes out as crop, is only using the land as he would a building, as a tool in a manufacturing process.

Fertility proper is by no means a wholly chemical question, dependent upon the amount of plant food the soil contains; in many cases the physical conditions which regulate the supply of air and water to the plant, and as a corollary, the bacterial life, are far more potent in producing a fertile soil than the mere amount of nutrient material it contains. Especially is this the case in an old settled country like England, where manure is cheap and abundant; here a fertile soil is often one which is not rich in itself, but one that is responsive to, and makes the most of, the manure applied. Clay soils are not uncommon which show on analysis high proportions of nitrogen compounds and potash, and again no particular deficiency in phosphoric acid, but from their closeness of texture they offer such resistance to the movements of both air and water as to carry very poor crops. Some light soils again, such as those on the chalk, would be regarded on analysis as rich, but they are made so persistently dry by the natural drainage, that only in a wet season do they keep the crop sufficiently supplied with water for a large crop production. On nearly all poor soils it is impossible to

effect much improvement by the use of manures ; in fact, manuring will not turn bad into good land, the conditions limiting the amount of crop being other than the food supply. Of course, by the continued incorporation of humus into a light soil, its physical texture may be improved at the same time as its richness, until it becomes sufficiently retentive of water for the needs of an ordinary crop, just as a heavy soil may be lightened by similar additions of humus. It has already been mentioned that many subsoils, especially of the heavier loams and clays, are extremely infertile when brought to the surface, even though they may possess a fair proportion of phosphoric acid and potash and be artificially supplied with nitric nitrogen. Some of this effect is due to texture, part to the very scanty bacterial flora they possess ; but it is to be noted that in arid climates the subsoils, which are not more fine-grained than the surface soils, do not show the same infertility when brought to the surface.

The soils which show the greatest fertility are, as a rule, soils of transport, uniform and fine-grained in texture, but with particles of a coarser order than clay predominating, so that, while moving water easily by capillarity, they are freely traversed by air and percolating water. As a rule, they also contain an appreciable amount of organic matter at all depths ; in Britain they have been deposited from running water, and represent the silt from which both the coarsest sand and the finest clay particles have been sifted, together with a certain amount of vegetable débris. We have nothing comparable with the typical "black soils" of the North American prairies or the Russian steppes, which contain very large proportions of organic matter to considerable depths in the subsoil : as, for example, a soil from Winnipeg that contained 0.428, 0.327, 0.158,

and 0.107 per cent. of nitrogen in the top 4 feet of soil successively. Many of these deep rich soils appear to be wind-borne: in all cases they are of very uniform texture, and represent the accumulated residues of ages of previous vegetation in a form that is capable of decay and nitrification so as to become available for subsequent crops. In a peat bog there is equally an accumulation of organic matter and nitrogen, but the mass is infertile because of the acid character of the humus (which causes the absence of the valuable bacteria, such as those fixing nitrogen and nitrifying ammonia) the deficiency of mineral plant foods, and the bad mechanical condition which affects the supply of air and water. In the main, then, a fertile soil is one rich in the debris of previous vegetation, one which has been sorted out by running water, wind, the agency of worms, etc., as to possess a very uniform texture, adapted to satisfy the needs of the plant for air and water. Mechanical texture is of fundamental importance: in this country many soils owe their value to this property alone; for example, the Thanet Sand formation in East Kent (a very fine-grained sand or silt), though it contains but little plant food, yet carries some of the best fruit and hop plantations in the kingdom, and farms on it command a high rent. Even more famous examples are the silt soils of Boston and Wisbech on the seaward side of the Fens, or the famous red soils of Dunbar. Both are light and easy working and show no great richness from the chemical point of view except as a result of continuous and heavy manuring. But they are happily tempered and of the right texture for the free movement of water in the soil, with the result that they respond to good cultivation and carry some of the best crops in the country.

Condition.

The question of condition has equally its chemical and its mechanical side; it is well known that on any but the lightest soils continued cultivation makes the texture better and renders it easier to obtain a seed bed. On clay soils the effects of bad management are very persistent; any ploughing, rolling, or trampling when the soil is wet will so temper the clay that the effect is palpable until the land has been fallowed again or even laid down to grass. Once protected from the action of frost, stiff soil which has been worked when at all wet never seems able to recover its texture, as may be seen by examining the clods that are to be found on digging up an old post, the result of the trampling when the post was originally put in. The dependence of "condition" upon the maintenance of a good texture is to be seen in the custom of regarding wheat as an exhausting crop, whereas few of our farm crops withdraw less plant food from the soil. The popular opinion really represents the fact that the wheat crop occupies the land for nearly a year, during which period it receives little or no cultivation, and so falls into a poor state of tilth.

From the chemical side "condition" means the accumulation within the soil of compounds that will by normal decay yield sufficient available plant food for the requirements of an ordinary crop, *e.g.*, of organic compounds of nitrogen which readily nitrify, of phosphoric acid and potash compounds which readily become "available" for the plant. A soil in good condition must also contain an abundant flora of the ammonia-making and nitrifying bacteria; indeed high condition is almost measurable by the content of the

soil in these bacteria and the rate at which it will produce nitrates.

The condition of land cannot be restored all at once by manuring; the residues of manures left in the soil after the first season are slow-acting, *i.e.*, only a small proportion of them becomes available year by year, so that there must be a considerable accumulation of such residues before the proportion becoming available during the period of growth is sufficient for the crop. *Per contra*, the condition can be only too easily destroyed by cropping without manure; the unexhausted residue left after each year is successively less and less active, the crop falls off rapidly, till at last a sort of stationary condition is reached, and the somewhat inert materials, still left in large quantity, liberate year by year a fairly constant proportion of active plant food. The plots at Rothamsted which have been cropped without manure for more than fifty years show but little less average production during the last twenty years than in the twenty immediately preceding. For example, the unmanured wheat plot shows the following crop in bushels of dressed grain:—

First 28 years, 1852-74.	Second 28 years, 1876-07.	1898.	1899.	1900.
14½	11½	12½	12	12½

Condition may best be regarded as a state of equilibrium when the land will continue to give a good return in crop for the manure applied; as a rule, the crop recovered by no means contains the whole of the material applied as manure, a certain portion being retained in a comparatively inactive form. With the land in condition the remaining nutrient material required for a good crop is supplied by the dormant

residues in the soil which have become active: at the same time, these reserves are protected from depletion by renewal from the inactive portions of the current manuring. On the other hand, if the land is in poor condition the crop gets little or no assistance from the soil, but is grown from the active part only of the manure: the rest of it accumulates and begins to build up condition, which, however, does not tell on the yield for some time. As a practical consequence, it is noticed that only land in good condition gives a paying return year after year for the application of manure: yet if the experiment be made of omitting the manure on a portion of the land for one year, there is little corresponding reduction of yield, as though the manure went to keep up the "condition," and the crop was grown out of that rather than from the manure applied.

From the point of view of analysis the estimation of the "condition" of a given piece of land is a difficult matter on which light is only just beginning to be thrown by the determination of "available" plant food, such as the nitrates and the phosphoric acid and potash soluble in dilute acid solvents. By considering such factors as these and the amount of humus soluble in alkali, the ratio of the soil carbon to the nitrogen, and the proportion of calcium carbonate, the agricultural chemist may form an idea as to the immediate state of the land. Doubtless, the prevalence and distribution of such necessary bacteria as those making ammonia are also important factors in determining the fertility, but on this point we are without exact information. It will be seen that "condition" is one of the most valuable of the properties of the soil to the cultivator; as it may be destroyed or created by the tenant during his occupation of the land, it should

be as far as possible a tenant's asset, to be bought by him on entry and valued to him on leaving. The difficulty which even an experienced man finds in putting a value on so intangible an item makes it almost impossible to assess the condition of a farm, but it is desirable in every way that the outgoing tenant should be encouraged to maintain the condition of his farm by giving him due compensation for the unexhausted value both of manures and foods used in the latter years of his tenancy.

"Fairy Rings."

The significance of "condition" and its dependence upon a supply of recently decayed organic matter is well seen in the development of "fairy rings" in pastures. "Fairy rings" are circles of dark-green grass, common enough in poor pastures, which are found to extend their size every year, leaving the grass within the ring of a lighter colour and of generally poorer aspect than that outside. On examining the soil immediately outside a ring, it is found to be full of the mycelium of one or two common species of fungi, but the mycelium rarely occurs in the soil beneath the ring itself, and never in that within the ring. The ring appears to be dependent on the growth of the fungus, which starts at one point and draws upon the humus reserves contained in the soil. Having consumed whatever humus is available, the mycelium must proceed into the annular area of soil immediately round the first patch, thus from year to year it spreads outward. After the death of the fungus, there is left behind in the soil it has just occupied a quantity of organic matter, which readily decays and becomes available for plant nutrition; thus a ring of luxuriant vegetation immediately

follows the death of the fungus. In other words, the humus of the soil, slow to decay and nitrify in the usual way, is changed into material undergoing rapid change by its preliminary conversion into the tissue of the fungus. At the same time, as the supply of rapidly acting plant food has been solely derived from the soil, the ultimate result is the impoverishment of the soil within the ring by the development of the fungi and the subsequent luxuriant growth of grass.

The following figures relate to the composition of the soil (mean of five examples) within, on, and outside "fairy rings" :—

	Carbon per cent.	Nitrogen per cent.	Nitrates per million.
Outside the ring . . .	3.30	0.281	2.44
On the ring . . .	2.99	0.266	11.46
Inside the ring . . .	2.78	0.247	1.03

It will be seen that the unchanged soil outside contains the most carbon and nitrogen; the ring itself contains an intermediate amount, and the least is contained within the ring after the luxuriant vegetation has passed away. The soil on the ring is in high condition, because the organic residues it contains are recently formed and will change rapidly; after they have been cropped out, the land is less able to support a crop, even though there is still much plant food left in the soil. The last column in the table (the analysis of a single example only) shows the difference in available nitrogen; and though in a pasture there are never many nitrates to be detected, so rapidly are they seized upon by the crop, still the organic nitrogen compounds in the soil must be in a more nitrifiable condition on

the ring to yield the results there shown. Doubtless an investigation of the nature and distribution of the bacteria and micro-fungi in and about a "fairy ring" would throw further light on the varying fertility of such closely neighbouring areas of soil, but no data are at present available.

Sterility of Soils.

Few soils occurring in this country can be described as absolutely barren, yet from time to time land is met with which yields such poor crops that it may fairly be designated as sterile. The causes of sterility are various; amongst them may be enumerated both the want and the excess of water due to texture and situation, deficient aeration, the absence of calcium carbonate, and the toxic action of certain salts, such as the sulphates of soda and of magnesia, and common salt itself. An acid reaction of the soil, which is highly prejudicial to vegetation, is generally brought about by one or other of the causes enumerated above.

The sterility brought about by a deficiency of water is only seen in this country when the soil is so entirely composed of coarse sand that it possesses no retentive power for the rainfall; even then the absolutely bare condition does not persist long, and may be attributed as much to the lack of nutriment as to the want of water. Little by little vegetation is found to creep over recent deposits of coarse sea-sand and shingle, until a turf is established. As a rule, such deposits have permanent water at a comparatively short distance below and by this the vegetation is maintained; but where a coarse, open-textured sand occupies the uplands, as on the Bagshot and Lower Greensand formations of the south of England, or the Bunter beds of the Midlands, the soil is kept so poor that it has largely remained

common heath land, never having been worth the expense of enclosing. Allusion has already been made, under the head of drainage, to the evils which ensue in a waterlogged soil: from time to time clays are met with of so close a texture that the vegetation suffers in an analogous manner through deficient aeration. On certain areas of the Oxford Clay and London Clay, and the Boulder clays derived therefrom, pastures degenerate after a few years into a mass of creeping rooted plants like bent grass, and the land must be broken up afresh in order to aerate it before any crop can be grown.

Sterility due to chemical causes is perhaps most generally caused in this country by the absence of calcium carbonate from the soil. When this happens on light sandy land it will become evident by the tendency of black mild humus to accumulate, by the paucity of leguminous plants in the herbage, and by the prevalence of fungoid diseases like "finger-and-toe." On strong lands, and when accompanied by water-logging, black acid peat accumulates: the soil shows an acid reaction, oxide of iron forms below the surface, and the soil water contains soluble iron salts, as is seen by the iridescent scum which spreads over any water standing in the ditches.

Another source of sterility is the presence of un-oxidised iron salts in the soil: many clay subsoils are coloured dark blue or green by double ferrous silicates like glauconite, or by finely disseminated iron pyrites. Until these materials become oxidised to ferric hydrate, the soil remains sterile: particularly is this the case with iron pyrites, which in the form of marcasite easily oxidises to yield both ferrous sulphate and sulphuric acid. Voelcker has recorded three instances of soil sterile through these causes: one was land reclaimed from the bed of the Haarlem Lake, which contained 0.71

per cent. of iron pyrites and 0.74 per cent. of ferrous sulphate, as well as some insoluble basic sulphate of iron. Another example of land reclaimed from the sea contained 0.78 per cent. of pyrites and 1.39 per cent. of ferrous sulphate. Under anaerobic conditions such as are set up in a completely waterlogged soil, the sulphates present are reduced to sulphides, and, by further reactions with the compounds of iron present, black ferrous sulphide is produced. Cultivation with a free use of lime and chalk is the best means of ameliorating such soils, which always show an acid reaction.

Kearney and Cameron in America have shown that salts of magnesia possess, even in solutions of great dilution, a toxic action upon plant roots, which is much diminished if calcium salts be present at the same time. Loew at the same time has indicated that a comparative excess of magnesium over calcium in certain soils results in sterility. With this may be correlated the fact that the soils resting upon the serpentine, which is a compound containing magnesia, are notoriously poor, also that certain very impoverished clays on the Wealden formation contain a high proportion of magnesia.

Sterility caused by salt is sometimes to be seen in this country in the marshes near the sea: more often a "salting," even where the sea has regular access, is clothed with vegetation which is able to endure very considerable proportions of salt. Most farm crops will grow in soil containing 0.25 per cent. of salt, and in the reclaiming of the old sea lake of Aboukir in Egypt, it was found that grasses would grow freely when there was still as much as 1 per cent. of salt in the soil, and a scrubby winter crop of barley was grown on soil containing more than $1\frac{1}{2}$ per cent. "With 2 per cent. of salt in the soil, a

fair crop of dineba (grass), 2 feet high, can be grown ; with 1 per cent. it attains its full height of 4 feet, and sells as a standing crop at from 20s. to 25s. per acre. For 'berseem,' or clover, the percentage of salt should not exceed $\frac{1}{2}$, and about the same for 'sabaini (quick-growing or seventy-day) rice.'" Much, however, depends upon the relations between water supply and evaporation, as to the amount of salt in a soil which would be tolerable to vegetation. From time to time cases occur in this country of crops being destroyed, and land rendered sterile by the incursion of sea water ; the effect is not always apparent at first, though sea water contains as much as 2.7 per cent. of sodium chloride and 0.5 per cent. of other soluble salts, but the permanent pasture becomes seriously injured, and for two or three years even the arable land yields very indifferent crops. Dymond has attributed this after-effect to the injurious action of the sea water on the texture of the soil, due to the attack of the sodium chloride upon the double silicates of the soil, lime in particular being displaced by soda. The result is the deflocculation of the clay, which will not settle down for many weeks when suspended in water. The sodium chloride of the sea water would also interact with any calcium carbonate in the soil, giving rise to sodium carbonate, the deflocculating effect of which upon the clay has already been noticed. Biological effects may also be surmised : it is always seen that the earth worms are killed in the land which has been flooded with sea water, and in view of the known unfavourable effect of chlorides on nitrification, it is possible that the rate of production of nitrates in the inundated soil is seriously lessened.

Alkali Soils.

In arid climates the rainfall is often insufficient to produce percolation through the soil and subsoil into the underground water system; in consequence, the salts produced by the weathering of the rocks tend to accumulate in the subsoil, and may be brought to the surface by capillary rise so as to cause almost entire sterility. Such bad lands are known in America as "alkali soils," but they are well known in India and in Egypt, and indeed are common to all countries possessing a small rainfall and great evaporation. In its most aggravated form alkali land, particularly at the end of the dry season, shows an actual white efflorescence of salts at the surface; all vegetation is destroyed, except one or two plants which seem tolerant of large quantities of saline matter, such as "greasewood," *Sarcobatus* sp., or the Australian "saltbushes," *Atriplex semibaccatum*, etc. In some cases the alkali is chiefly located at a slight depth in the soil, and only effloresces on spots a little below the general level, where the subsoil water comes to the surface. A heavy rainfall may be followed by a rise of alkali, because a connection is then established between the saline subsoil water and the evaporating surface, whereupon a continuous capillary use of salts takes place, followed by their crystallisation at the surface. *Per contra*, the establishment of a soil mulch, and shading the ground with a crop, so that evaporation only takes place through the leaves, will aid in keeping the alkali down. The composition of the salts varies; as a rule, sodium chloride predominates, with some sulphates of sodium, magnesium, and calcium, in which case the material is known as "white alkali." Under other conditions the material is really alkaline, containing carbonate and bicarbonate of soda; the

saline solution then dissolves some of the humus present in the soil, and also causes the resolution of the clay material into its finest particles, so that the soil forms an intensely hard black pan when dry, which is known as "black alkali." The carbonates are far more injurious to vegetation than the neutral salts; few plants can bear as much as 0.1 per cent. of sodium carbonate, but are tolerant of 0.5 to 1 per cent. of the other salts.

Though the alkali salts are sometimes chiefly sulphates, more commonly sodium chloride is the main constituent, together with the products of its action in mass upon calcium carbonate and sulphate. The diagram (Fig. 17), due to Hilgard, shows the distribution with depth of alkali salts in this type of soil at Tulare, California; the greatest accumulation of salts takes place at a depth of 30 inches, the point to which the annual rainfall penetrates. One of the most difficult features presented by the cultivation of land in arid regions where alkali occurs in the soil, comes from the tendency of the sterile spots to spread and the alkali to be brought to the surface as soon as irrigation water is employed, for without irrigation agriculture is hardly possible. Many districts, which at first carried good crops and were even laid down in fruit or vines, have been ruined through the rise of alkali to the surface brought about by irrigation; in fact, in all these arid regions it becomes exceedingly dangerous to raise the water table in the land anywhere near the surface, because capillarity then causes a rise of the salt-charged water, and evaporation concentrates it on the top. Just as some of the worst alkali land occurs where rain falling upon the surrounding mountains finds its way by seepage through the subsoil rich in salts and then rises to the surface in the dry basin areas below, so the introduction of irrigation




FIG. 17.—Nature and Distribution of Alkali Salts (Hilgard).

canals pouring large volumes of water upon the land may equally establish the capillary connection between the subsoil salts and the surface. The following extract from Bulletin No. 14, U.S. Dept. of Agric., Div. of Soils, dealing with alkali soils in the Yellowstone Valley, shows the evil effects of incautious irrigation:—

“Irrigation has been practised for twelve or fifteen years. The water for the main ditch supplying the valley is taken out of the river nearly 40 miles above the town of Billings. When the country was first settled, and indeed above the ditch at the present time, the depth to standing water in the wells was from 20 to 50 feet, and there were no signs of alkali on the surface of the ground. Under the common practice of irrigation, however, an excessive amount of water has been applied to the land, and seepage waters have accumulated to such a degree that water is now secured in wells at a depth of from 3 to 10 feet in the irrigated district, while many once fertile tracts on the lower levels are already flooded, and alkali has accumulated on them to such an extent that they are mere bogs and swamps and alkali flats, and the once fertile lands are thrown out as ruined and abandoned tracts.”

Nor is it necessary that the subsoil be charged with salts for irrigation to produce alkali land; the mere continual evaporation of ordinary river or spring water may cause such an accumulation of saline matter at the surface as is harmful to vegetation. This is well seen in Egypt, where perennial irrigation is practised with the Nile water, and the following quotation from Willcock's *Egyptian Irrigation* will explain the action that takes place:—

“The introduction of perennial irrigation into any tract in Egypt means a total change in crops, irrigation, and indeed everything which affects the soil. Owing to

the absence of rain, the land is not washed as it is in other tropical countries, unless it is put under basin irrigation.

"An acre of land may receive as many as twenty waterings of about 9 cm. in depth each, *i.e.*, a depth of water of 1.80 metre per annum, which is allowed to stand over the soil, sink about half a metre into the soil, and then be evaporated. Since the Nile water, especially in summer, has salts in excess, these salts accumulate at the surface, and if not eaten down by suitable crops, soon appear as a white efflorescence. While the spring level is low, capillary attraction cannot bring up to the surface the spring water, which generally contains a fair proportion of salts, but where the spring level is high the salt-carrying water comes to the surface, is there evaporated, and tends to further destroy the soil. In old times the greater part of the cultivation land was under basin irrigation, and was thoroughly washed for some fifty days per annum; while the rest, consisting of the light sandy soils near the Nile banks, was protected by insignificant dykes, which dykes were burst every very high flood, and thus allowed to be swept over by the Nile and washed once every seven or eight years. All this is at an end now in the tracts under perennial cultivation, and other remedies have to be found."

The only remedy for the evils attending irrigation is the introduction of drainage channels at a lower level than the canals bearing the irrigation water; in this way the percolation through the soil, which in humid climates naturally removes the salts not taken up by the crops, is effected artificially; there is some apparent loss of water, but this is absolutely necessary to maintain the land free from injurious salts. As an example, the following passage may be quoted

from one of Major Hanbury Brown's reports on Egyptian Irrigation:—

"It has been ascertained that the blessing of improved water supply which has resulted from the barrage having been made to do its duty, has been attended in some localities with the evils due to infiltration and want of drains. The remedy, as pointed out in last year's Report, is to remove the want of drains by digging them, and to provide the means of washing out the salt brought to the surface, by infiltration in the shape of a liberal supply of water, by which the salt would be carried away in solution along the drains, or be forced down below the surface of the soil to a depth at which it would be harmless. The liberal water supply is not to be obtained except by the construction of a storage reservoir at Aswan or elsewhere."

It was the neglect of drainage, when irrigation canals were introduced, that led to so widespread a deterioration of land in Egypt. To quote from Lord Milner's *England in Egypt*:—

"But perhaps the worst feature of all was the neglect of drainage, which was steadily ruining large tracts of country. Even where drains existed, they were frequently used also as irrigation channels, than which it is impossible to conceive a worse sin against a sound principle of agriculture. In some cases these channels would be flowing brimful for purposes of irrigation, just when they should have been empty to receive the drainage water. Elsewhere the salt-impregnated drainage water was actually pumped back upon the land.

"It was the want of drainage which completed the ruin of the Birriya, that broad belt of land which occupies the northern and lowest portion of the Delta, adjoining the great lakes. There are upwards of

1,000,000 acres of this region, now swamp, or salt marsh, or otherwise uncultivable, which in ancient times were the garden of Egypt."

It has been the business of the English irrigation officers since the occupation to restore and improve the drainage system, and to begin the reclamation of the salted areas by cutting drainage canals and passing enough of the abundant winter flood water through the soil to wash out the salts into these drains.

Hilgard in California has also indicated that it is impossible to wash the salts from the soil, even by leaving the water to stand upon the surface for some time, unless provision is made to remove the salted water by underdrainage. In the case of black alkali, however, the soil has become too impervious to allow water to percolate at all; the first remedial measure is to incorporate considerable quantities of gypsum with the soil; this will interact with the sodium carbonate, producing sodium sulphate and calcium carbonate, at the same time precipitating the humus in a flocculent form. If now underdrainage be brought into practice the soluble salts can be washed through, and a very fertile soil results, owing to the presence of the finely divided humus and calcium carbonate. Where underdrainage is hardly practicable because of the expense, irrigation water should be used in as limited amounts as possible, and every care should be taken to keep the surface tilled and under crop, so as to minimise evaporation from the bare ground. In humid countries like our own, damage due to the accumulation of salts are rare; the author has, however, seen one case where the vegetation of a lawn was destroyed during a hot dry spell of weather by continuously applying water in quantities which never washed down into the subsoil,

but evaporated every day. An efflorescence practically identical with white alkali is sometimes seen on greenhouse borders, which are constantly watered, but never in sufficient quantities to cause percolation; and gardeners again are familiar with the check of growth which sometimes occurs in the case of plants long in one pot and constantly watered with hard water. The remedy is to water from time to time so heavily as to cause abundant percolation and thus wash all the salts out.

Closely related to some of the phenomena presented by alkali soils are certain secondary effects upon the texture of the soil which are produced by the action of some of the salts used as artificial manures. A good friable texture in a heavy soil depends upon the clay particles being generally flocculated and gathered together into little aggregates, which give the soil a coarser grain until they are resolved into their ultimate particles by incautious working when the clay is in a wet state. It has already been shown that acids and most soluble salts, particularly those of calcium, possess a strong flocculating power, whereas the soluble alkalis—the carbonates and hydrates of sodium, potassium, and ammonium—are active deflocculators, causing the clay particles to separate into their most fine-grained condition.

It has long been recognised that large or frequent dressings of nitrate of soda had an injurious action upon the tilth of the soil, causing it to remain very wet, and then to dry into hard, unkind clods. Since nitrate of soda is very hygroscopic, the wetness induced in the land was attributed to the absorption of moisture from the atmosphere by the nitrate of soda, but when it is considered what a very small proportion the water absorbed by as much as 5 cwt. of nitrate of soda would bear to the hundred tons which is the approximate

weight of an acre of soil an inch thick, it is obvious that the difference in water content so induced would not be sensible.

Clay soils, in fact, which have been treated with nitrate of soda, do not show any excess of water; but they are very much deflocculated, as may be ascertained by comparing the appearance after standing of a jar of distilled water rendered turbid by shaking up in it a gram of the soil, and a second jar in which the water has been shaken with a gram of the same soil in its normal condition. But nitrate of soda itself possesses flocculating powers even when concentrated, hence the observed deflocculation cannot be due to the direct action of the fertiliser upon the clay. However, it has been found that when plants feed upon a nutrient solution containing nitrate of soda, an excess of the nitric acid is withdrawn by the plant, and part of the soda is left in the medium combined with the carbon dioxide secreted by the plant. The existence of this soluble alkali after the growth of the plant can be verified by experiments with water cultures, it can also be extracted from the soil of the Rothamsted plots which have for many years been manured with nitrate of soda. Small as the amount may seem to be, it is quite sufficient to account for the deflocculation of the clay and the defective tilth observed on heavy land after nitrate of soda has been used.

The bad repute of nitrate of soda as exhausting or scourging the land, is less due to any sensible diminution in the stock of plant food in the soil that follows its use, than to the deflocculation it sometimes induces, and the consequent deterioration of the texture of the soil. As a remedy lime is not effective, since it is an alkali itself; instead, the nitrate of soda should be used in conjunction with acid flocculating manures like super-

phosphate, or a mixture of nitrate of soda and sulphate of ammonia should be used as a nitrogenous manure, because the two manures will act upon the soil in opposite ways, the nitrate of soda as an alkali and the sulphate of ammonia as an acid. Dressings of soot are also effective; not only does it assist the soil mechanically, but also the small percentage of sulphate of ammonia it contains possesses some power of flocculating the clay.

Other fertilisers which give rise to an alkaline reaction in the soil are sulphate of potash, common salt, and other soluble salts of sodium and potassium, which, as has already been noticed (p. 254), interact with calcium carbonate in the soil, and give rise to a little soluble alkaline carbonate. The injurious effects of sulphate of potash upon the tilth of the heavy soil at Rothamsted is very evident on the mangold field, where the plots receiving this fertiliser every year become excessively sticky and clinging in wet weather, and dry with a hard caked surface. It has often been noticed that applications of potash salts and common salt have depressed instead of increasing the yield; this may probably be set down to the deterioration of tilth that ensues when the soil is heavy and also contains calcium carbonate. Some fertilisers, on the contrary, aid in the flocculation of clay soils, the most effective being superphosphate, which is acid and contains gypsum, an effective flocculating agent. The ammonium salts, which give rise to free acids, in consequence of the withdrawal of ammonia by the moulds, etc., living in the soil, act as very potent flocculators, and at Rothamsted, for example, give rise to an open and friable soil, as compared with the neighbouring plots receiving nitrate of soda. Lime, which is the chief flocculating agent employed in practice, is only effective

when it has become dissolved as bi-carbonate in the soil water.

Amendments of the Soil.

Many soils, without being absolutely sterile, carry very poor crops until their physical character has been altered by the admixture of some considerable quantity of one or other of the constituents of a normal soil that may happen to be originally wanting. These amendements of the soil by the mixture of other soils date from the time that enclosures first began to be made; they were perhaps at their height during the early years of the nineteenth century, after the middle of which they rapidly diminished as it began to be less and less remunerative to "make" land, until at the present time the fall in the prices of produce and the rise in the cost of labour have put an end to all such operations. Among other causes of this neglect may perhaps be set down the increased use of artificial manures; men began to take too exclusively a chemical view of the functions of the soil, and shirked expenditure which did not seem to add directly any food for the plant. However, it is probable that with modern facilities for moving earth on a large scale by steam power, the improvement of much poor land might even now be profitably undertaken.

The operations which may be grouped under the head of "amendments of the soil," comprise—drainage, which has been dealt with elsewhere; the marling and claying of light sands; the reclamation of peat bogs; the improvement of clay soils by liming and chalking, or by paring and burning; and lastly, the creation of new alluvial soils by warping.

Warping.

The operation of "warping," or "colmetage," is only possible in the vicinity of tidal estuaries, where lands exist below the level of high water, and is in this country practically confined to the estuaries of the Humber and Ouse. Warping is carried out by the construction of a wide drain protected by sluices from the tidal river to the low land, which is first divided by embankments into compartments of various sizes up to 150 acres. When the embankments have become consolidated, the flood tide, heavily charged with suspended matter which is really fine earth brought down by the river, is admitted into the compartment, where it deposits most of its silt and is allowed to run off when the level of the water in the river has fallen during the ebb. The operation is repeated until a layer of silt has formed 1 to 3 feet thick over the land, which is then dried and brought under crop. As the chief deposit is always near the mouth of the drain, where the velocity of the silt-bearing current is first checked, the position of the inlet must be shifted about to secure a uniform deposit all over the land and to distribute the valuable fine silt which settles furthest from the inlet. In some cases the sluice gates are automatic, and water is admitted and drawn off at every tide, but in others only every other tide is admitted, thus giving time for the deposit of the finer particles, and greatly improving the character of the resulting land. As a rule, only the spring tides are utilised, because the suspended matter is then at its maximum, and the process is confined to the summer months, to avoid danger from flooding when there is much land water about. In exceptional cases land

may be warped 2 or 3 feet deep in one year—from January to June—in other cases, where the water is less charged with sediment, or the land is at a higher level, an efficient warping, which should not be less than 18 inches deep, requires three or four years. When finished, the land is allowed to dry and consolidate, drainage grips are then thrown out, and a light crop of oats, in which are sown clover and ryegrass, is taken; after the seeds have been down two years the land is generally ready to carry wheat. Warp soils are, as a rule, fertile, and noted for growing seed corn of high quality; they are to all intents and purposes artificial alluvial soils, composed entirely of the finer sands and silts without much clay material, and are comparatively rich in organic débris and other plant food, except perhaps potash. The fertilising of the Egyptian land by the red Nile flood water, the formation and improvement of river meadows by winter flooding, are both analogous to the process of "warping."

Marling and Claying.

Many light and blowing sands, almost too pure to permit of any vegetation, have in their immediate neighbourhood a bed of marl or clay which can be easily incorporated, practically creating a soil where there was none before. Among the New Red Sandstones of Cheshire and the Midland Counties beds of true marl occur and were at one time enormously worked, so that every farm and almost every field shows its old marl pit; the sandy Lower Greensand soils in the Woburn district have been extensively marled from the adjoining Oxford clay, and many of the Norfolk soils have been made out of blowing sands, by bringing up the clay which immediately underlies them. The

earlier volumes of the *Journal of the Royal Agricultural Society* contain numerous accounts, showing how much land was brought into cultivation by these means in the first half of the nineteenth century.

“ He that marls sand may buy the land,
He that marls moss shall suffer no loss,
But he that marls clay flings all away.”

The usual practice in Norfolk was to open pits down to the marl or clay, dig and spread it at the rate of 50 to 150 loads to the acre on a clover ley or turnip fallow. In some cases trenches were opened all along the field, and the clay thrown out on either side. By the action of the weather, drying and wetting, followed by frost, the clay comes into a condition to be harrowed down, after which it can be ploughed into the ground.

The effect of marling or claying is more evident after a year or two than at once, because the fine particles become each year more thoroughly incorporated with the soil. The effects are to be seen in increased crops, the production of better leys and pastures, greater resistance to drought, and particularly an increased stiffness in the straw where manures are used to grow the crop.

Marl containing carbonate of lime is always far more valuable than clay; pure clay is so little friable, and so sterile itself, that it effects an improvement only slowly; marl not only ameliorates the texture but adds at once a supply of carbonate of lime, potash compounds, and in some cases phosphoric acid also. Clay and marl both have a tendency to sink, and eventually require renewing, but if well done will last for thirty to fifty years, because the accumulation of humus and fibrous root-remains, due to the increased crops, itself binds the soil together.

At the present day the need of marling or claying

on a small scale is often seen in old gardens, particularly in old town gardens which are situated upon gravel soils, initially very short of the finer soil particles. The constant breaking of the surface by cultivation, and the use of large quantities of stable manure, which decays and leaves the soil open, result in a continual washing down of the finest particles, until the remaining soil loses all power of cohesion and of resisting drought, falling into a dusty powder immediately on drying. A coating of clay in the early autumn, or, better still, of good marl, is the only method of giving consistency to such a soil and soon remedies its worst defects, such as susceptibility to drought and rapid fluctuations of temperature, and tendency to produce soft vegetation, very liable to disease.

Reclamation of Peat and Heath Land.

One of the earliest methods of bringing peat land in the Fens and similar districts into cultivation was, to dry the land by means of open drains and break up the surface with the breast plough; the clods were then gathered together, and burnt when dry, afterwards the ashes were spread and a crop of rape taken. The fire was never allowed to burn too fiercely, the object being to obtain charred residues rather than white ashes. The effect of burning the peat was to provide a certain amount of ash rich in saline matters and particularly in alkaline carbonates, thus correcting the two great faults of the remaining peat, its deficiency in mineral matters, and its sour reaction. At the same time the weeds and other coarse vegetation occupying the surface were destroyed, and a clean seed-bed prepared for the crop. However, the process of burning is a very wasteful one, involving the loss of the combined nitrogen contained in the accumulated organic matter,

and after a few repetitions the land was found to be seriously depleted of its reserves of humus. Burning became replaced in the Fens by a marling process, especially where the peat was of a sandy nature; trenches were opened to the bed of marl or clay always found beneath the peat, and the clay thrown out and spread at the rate of 100 loads or so per acre, the burning process being reserved for the first reclamation, when a mass of surface vegetation had to be got rid of. In other districts, where marl is less available, peat has to be brought into cultivation by draining the land with open cuts, allowing some considerable time to elapse during which the peat dries, shrinks, and consolidates, and then correcting the acidity with lime.

It is in Germany and Holland that the reclamation of peaty areas has been most systematically pursued. The process must begin with a thorough drainage of the area, either by cutting off the sources of the incoming water or by deepening the outlet, so as to lower the permanent water level to some distance below the surface of the land. According to the conditions, the area may require a system of drainage cuts and open ditches to get away the water, which the peat parts with slowly because of its colloid nature. The consolidated peat may be removed if there is a market at hand for peat fuel, but the loose, less rotted material near the surface is thrown back to form the soil. Where the land is to be used for arable cultivation it is very desirable to spread a layer of whatever soil is available below the peat, even if it is pure sand. The rough vegetation on the surface is carefully burnt off and the fundamental manuring upon which the cropping depends is then applied. This consists of from 2 to 4 tons per acre of ground chalk or marl, about 5 cwt. of basic slag, and 6 to 8 cwt. of

kainit or other potash salts, all of which are well worked into the surface soil with cultivators and harrows of the disc type before cropping begins. The chalking will have to be repeated in a few years, and the basic slag and potash salts need to be regularly applied, though not in the initial quantities. On a newly reclaimed bog the horses require special shoes or boots with broad flat soles, and the wheeled implements are fitted with wide flat bands in order to enable them to traverse the spongy surface without sinking in. Good crops can be grown cheaply after the initial reclamation, for the land contains an immense reserve of nitrogen. Rye and oats among cereals, potatoes, mangolds, cabbage and kale form the best crops; the quality, and especially the stiffness of the straw of the cereals, are very dependent upon the incorporation of some mineral soil in the cultivated layer.

Permanent pastures may be formed by burning over the surface, incorporating the chalk and manures with the burnt ashes by a series of shallow cultivations and sowing the seed mixture, in which alsike clover, trefoil, timothy, and cock's-foot and rye grass should predominate, in the spring without any cover crop. In Germany reclamations of the low moors, the wet peaty alluvial deposits near the river mouths are regarded as the most profitable undertakings of this nature, the financial results being in the main dependent upon the cost of the initial drainage. The treatment of the great area of heaths which cover the coarse sandy glacial deposits of Northern Europe follows much the same lines, and can undoubtedly be applied with success to considerable areas in Great Britain, as, for example, to the "brek" land of Norfolk and Suffolk, the Dorset and Cornish heaths, etc. In all these

areas farms are to be found reclaimed at some time or other from the heath, which alongside is still waste. The farms are often poor because the soil has only been made by a long process of cultivation and cropping, without attention to the fundamental amelioration of the soil by a supply of lime, phosphoric acid, and potash. Success in reclamation is entirely dependent upon the courage with which this initial expenditure necessary to "make" the land is faced. At pre-war costs, some £5 or £6 an acre had to be expended, and it is difficult to say at the present time whether the demand for land will repay the increased costs now to be incurred.

The work of reclamation must begin in many cases with drainage; shrubs and trees have to be removed; banks roughly levelled and hollow places filled in; then the heather, if present, is burnt over and a steam cultivator or deep tractor should be set to work. It is sometimes necessary to break up an iron pan existing a few inches below the surface. The ameliorating materials are then sown, 2 to 4 tons of chalk, 6 to 8 cwt. of basic slag, and 5 to 6 cwt. of potash salts per acre; subsequent shallow cultivations work in the manures and remove the moss, bracken roots, and other rough vegetable débris. For arable land the best preparation is to sow a crop of blue lupins, to be turned in and supply a stock of nitrogen and humus for succeeding crops. Vetches also may be used and folded off with sheep. For the subsequent cropping rye and oats are the best cereals; potatoes, carrots, and peas give good crops, and the land may be sown down to lucerne successfully. Continuous manuring is indispensable, nitrate of soda is better than sulphate of ammonia, and potash salts cannot be omitted. Early sowing is also a very necessary feature in the manage-

ment. A very successful experiment of this type has been made on some 200 acres of the "brek" land at Methwold in Norfolk, land which was covered with bracken and had never previously been cultivated. In the second year after breaking up the land was yielding $27\frac{1}{2}$ bushels per acre of wheat and 28 of oats, and within the first five years of the trial the initial expenses of reclamation, amounting to between £5 and £6 per acre, had been repaid by the profits on the crops.

The financial results have been published, but as both the cost of the work and the value of the crops are abnormal owing to the war years, it is sufficient here to draw the conclusion that land worth only 2s. 6d. to 5s. an acre for sporting purposes has been given a letting value of 15s. an acre by an initial expenditure of about £6 an acre. The soil was one of the coarsest of sands and the rainfall in the district among the lightest in England.

Paring and Burning.

When the poorer clay soils were first taken into cultivation, a beginning was generally made by "paring" the surface with the breast plough, and "burning" the clods as soon as they were sufficiently dry. The clods were made up into heaps a yard or so in diameter, with the brushings of the hedges and all the rough surface vegetation, together with as much clay as was judged prudent. Each heap was then allowed to burn slowly and char the clay, without permitting the heat to rise sufficiently to vitrify the clay or dissipate such valuable material as the alkalis of the ash. The resulting ashes effected a great improvement in the soil: the clay was partially dehydrated, or at least coagulated, thus providing a certain amount of coarse material to ameliorate

the texture; in the charred clay also, some of the potash was rendered more available, while the plant residues provided mineral salts and alkalis to promote nitrification. The drawback to the process is the inevitable loss of nitrogen to the soil; but any one who has noticed how freely crops grow on the patches of arable land where couch heaps have been burnt the season before will see that, for the time being, the fertility of the soil is increased by the process. Other advantages of burning lie in the destruction of weeds and insect life of all kinds, and although it has been almost wholly discontinued at the present day, the older writers on agriculture are unanimous as to its beneficial effects in bringing poor clay land into cultivation. The destruction of the protozoa and the subsequent burst of activity on the part of the organisms producing plant food, to which reference has already been made (p. 232), is also doubtless a factor in the result.

A variation on the old process of "clod burning" consists in "border burning," in which clay is dug from one corner of the field and burnt by means of the couch and other weeds cleaned off the land, the hedge trimmings, etc.; the burnt clay is then spread over the surface to improve the texture of the soil. Without doubt the latter process might still be profitably adopted where heavy clay land is under the plough; if every year some clay were added to the fires made from the weeds and hedge trimmings, valuable material for lightening the soil would be obtained without wasting too much soil nitrogen.

Of course the incorporation of any large-grained material will improve the texture of clay soils; in some cases sand has been dug and spread with advantage; road scrapings, town refuse, and even coal ashes help

to lighten the soil, though in the case of gardens coal ashes should be avoided.

Liming and Chalking.

Of all the methods of improving the soil, other than actual manuring or cultivation, none is more important than the incorporation of lime or chalk. It has already been indicated that many soils exist, chiefly clays and sands, containing less than 1 per cent. of carbonate of lime; on all such land liming produces very pronounced effects, both on the physical texture of the soil and on the character of the resulting vegetation.

It is on the clays and other strong soils that lime produces the greatest alteration in texture; its effect in coagulating and causing the finer particles to form into aggregates, which remain loosely cemented by the carbonate of lime, has already been discussed. The soil becomes much less retentive of water, percolation is increased so that the limed land is drier and warmer, admits of cultivation at an earlier date in the spring, and is far more friable when dry. In fact, the liming gives a coarser texture to the clay soil, and all the effects pertaining to the coarser texture, such as diminished capacity for retaining water and consequent greater warmth, less shrinkage and tendency to cake on drying, are all manifest after the application of lime. It does not, however, follow that the crop will mature more readily though the season is made earlier through liming; in many cases in dry seasons crops upon clay ripen prematurely, because the drying up and shrinkage of the impervious clay cut the roots off from all access of moisture. The liming, by opening up the soil to the motion of water by surface tension, keeps the plant growing for a longer period; at the same time, the increased amount of plant

food rendered available also tends to prolong the duration of growth. On very light soils the addition of lime acts to a certain extent as a binding material, and increases the cohesion and water-retaining power of the soil, but it is not so effective in this respect as humus. Besides its physical effect upon the texture of stiff soils, lime has a very powerful chemical effect, liberating freely the reserves of plant food of all kinds in the soil and rendering them available to the plant; so that on soils naturally deficient in carbonate of lime, manures of all kinds can only find their proper value if lime be also used from time to time. On soils that have been under intensive cultivation for a long time immense reserves of plant food have been accumulated, which only require the addition of lime to bring them into action. As an example may be quoted the result of applying lime to an old hop garden at Farnham, Surrey, where the soil consisted of an alluvial loam, very deficient in carbonate of lime, and heavily dressed with organic manures for many years previously. The plots chosen for comparison received a complete artificial manure with or without 1 ton of lime per acre; the figures for the crops in the following table have been reduced to percentages to eliminate the great fluctuations due to season.

Year.	ARTIFICIAL MANURE.	
	With Lime.	Without Lime.
1895	100	70
1896	100	84
1897	100	80
1900	100	81
1901	100	90

Of course, as lime itself supplies no food to the

plant, but only sets in action the dormant residues already present in the soil, the forcing of crops by the aid of lime alone soon results in the exhaustion of the land. Hence the old saw:—

“Lime, and lime without manure,
Will make both land and farmer poor.”

The exact effect of lime in promoting fertility depends upon the plant food in question. We have already seen that all the decay processes which result in the oxidation of the humus are promoted by the presence of a base to combine with the organic acids produced by the decay, and, in particular, that the presence of an easily attacked base is necessary for nitrification. As a nett result, the oxidation of the humus and the formation of nitrates is much increased by a dressing of lime, which, indeed, is the first indispensable step towards rendering available the rich organic residues accumulated in a sour soil. As regards the mineral constituents, lime has a very marked power of bringing potash into a soluble state; the double hydrated silicates of potash and alumina, etc., which result from the partial breaking down of felspars and are the sources of the potash of our soils, are decomposed, lime being substituted for the potash going into solution. It is a case of mass action, where the addition of one soluble constituent to the soil will increase the amount that goes into solution of all the other constituents which are capable of being replaced by the base added; the extent of the action is therefore dependent upon the amount of lime used. The fact that more potash has been rendered available in limed soils is clearly seen in the character of the vegetation, *e.g.*, in an increased proportion of clovers in the herbage of pasture or hay land. The

action of lime as a liberator of potash is illustrated by the effect of a dressing of chalk applied in 1881 to part of the permanent grass plots at Rothamsted; by 1884 differences began to be manifest, the chalk caused a change in the herbage of those plots which had been receiving potash each year for twenty-five years previously, increasing the production as a whole, and particularly increasing the proportion of leguminous plants in the herbage. On the plots, however, which had been receiving no potash, and therefore contained no recently accumulated reserves of this material, the chalk had practically no effect, either in the weight or character of the crop.

To some extent lime seems able to act as a liberator of phosphoric acid in the soil. As pointed out by Thénard, lime is able to act upon the very insoluble phosphates of aluminium or iron which are present in many soils, and, by converting them into phosphate of lime, renders the phosphoric acid more available for the plant.

Besides its specific actions in thus rendering more soluble the soil constituents which nourish the plant, lime exerts a very beneficial action by maintaining the neutral reaction of the soil; it neutralises the acids produced by the decay and nitrification (see p. 197) of the organic matter in the soil. Again, as has been shown already, it is necessary as a base to satisfy the requirements of artificial manures like sulphate of ammonia, superphosphate, and kainit (see p. 252), or to prevent the soil being invaded by such organisms as the destructive fungus causing "finger-and-toe" (see p. 244). It must, however, be clearly realised that lime is wanted as a base, not as a compound of calcium, necessary though calcium itself may be to the economy of the plant; and that only carbonate of lime (chalk,

limestone, etc.) or quicklime and slaked lime, which promptly become carbonate of lime when incorporated with the soil, are capable of acting as the required base. Other calcium compounds, as superphosphate of lime or sulphate of lime (gypsum), or phosphate of lime in bones, etc., are either acid or neutral, and do not supply the base required to effect the beneficial actions set out above; they cannot replace lime or chalk—in fact, they do not contain any “lime” in the farmer’s sense. Unfortunately, it has been too often supposed that the use of artificial manures, such as superphosphate of lime, removed the necessity of a periodical liming of the soil, and some of the neglect into which this all-important operation has fallen may be set down to the unfortunate confusion hanging round the word lime. However, as will have been gathered from a consideration of the effects of sulphate of ammonia in depleting the Woburn soil of carbonate of lime, the use of artificial manures generally demands an increased rather than a lessened attention to the periodical liming of the land.

The method of liming which was formerly in vogue consisted in applying very large quantities of quicklime at comparatively long intervals, 100 to 150 bushels per acre (=2 to 4 tons) every eight or ten years, or an initial dressing of 100 bushels, with a further dressing of 50 bushels per acre every third year. The reason for this interval lies in the fact that the best effects of lime are to be seen after the lapse of a year or two; the material becomes carbonate, which, being insoluble, is incorporated with the soil and passes into solution as bicarbonate but slowly. The immediate effect of lime may even be a diminution of the crop, if it be used on very rich land, or in actual contact with fresh dung; under these conditions there appears to be some loss of ammonia by volatilisation. Of course the

effect of lime is not very persistent, and the dressing must be repeated ; as the farmers say, the "lime sinks in the land," *i.e.*, carbonate of lime is removed from the surface soil by solution as bicarbonate.

In carrying out the operation of "liming," the aim should be to ensure as fine a division as possible, so as to incorporate the material intimately with the soil. In some cases the lime is thrown out in heaps on the stubbles in autumn, and slaked by pouring on water, the hot slaked powder into which the quicklime falls being immediately spread over the land. This method only answers with "fat" limes, which slake and fall readily to a dry powder ; a better method is to lay up the quicklime in heaps and cover the heaps with soil, in which case the lime slakes gradually to a fine powder that can be spread before the plough. It is not wise to spread the quicklime over the land, as much of it, after slaking and becoming carbonated, remains in lumps which cannot be reduced to a powder.

The expense of liming in this fashion is considerable, and as the action is not immediate, owing to the difficulty of getting the material mixed with the soil, it is desirable to replace it, if possible, by a cheaper process. This has been attained by the use of ground lime, which is at the present time prepared by most lime works for the use of builders ; 5 cwt. of ground lime per acre, distributed by a manure barrow or by one of the artificial manure distributors now manufactured, will be found more effective for one or two seasons than ten or twelve times as much applied in the old-fashioned method. Of course such a small dressing of ground lime requires renewing more frequently ; but, as the expense is comparatively trifling, both for labour and material, as compared with the older process, it may be hoped that on many soils this

all-important operation will assume its old prominence in the routine of farming.

Considerable differences are to be seen in the character of lime made from the various calcium carbonate rocks burnt for lime in the British Islands; in the main a distinction may be drawn between the white "fat" limes made from the White Chalk, the Mountain Limestone and other comparatively pure deposits of calcium carbonate, and the "thin" grey or stone limes made from less pure and more argillaceous limestones. The "fat" limes are the purer, slake readily and swell considerably in the act, forming afterwards a bulky white powder; the "poor" or "thin" limes slake with comparative difficulty and do not increase much in bulk. The "thin" limes partake somewhat of the nature of a cement, setting after mixture with water, and are more esteemed by builders than the "fat" limes, which harden with extreme slowness and are chiefly employed for plastering and kindred work. Naturally the "fat" limes are preferable from an agricultural point of view, both from their purity and the finer condition into which they fall; unfortunately few of the lime works grind the white lime in the ordinary course of trade, as they do the builders' lime.

The lime made by burning the Magnesian Limestone which occurs in Durham, Yorkshire, Derbyshire, and Notts, is disliked by farmers and regarded as injurious rather than beneficial to the land. It contains 50 to 80 per cent. of lime and 4 to 40 per cent. of magnesia, which latter constituent may be the cause of the ill effects.

The following analyses show the mean composition of several samples of "fat" and "poor" lime, being "white" and "grey" lime respectively, made from the Upper and Lower Chalk of the North Downs:—

	White Lime.	Grey Lime.
Caustic Lime	90.20	74.00
Carbonate of Lime	2.40	2.66
Magnesia	0.35	0.38
Oxide of Iron	0.52	1.00
Alumina	1.70	7.60
Silica as Soluble Silicates	2.60	8.60
Insoluble Residue25	.94
Water, Alkalis, etc.	1.98	4.82
	100.00	100.00

In place of lime, chalk may often be used with advantage when it is readily accessible; for example, on one side of the Chalk formation the Gault and the upper beds of the Lower Greensand, and on the other side the London Clay and the Bagshot Sands, are generally in need of lime, and are never very remote from the outcrop of the chalk. The superficial clays and sands lying on the Chalk itself are often deficient in lime, and may be readily chalked by sinking shallow pits. It must be remembered that much larger quantities of chalk than of lime are needed to produce a given effect; not only is the chalk equivalent chemically to about half its weight of lime, but in practice it can never be reduced to so fine a state of division as lime obtains by careful slaking. In chalking, it is desirable to obtain the soft upper white chalk from a pit, so that it is saturated with quarry water; if then spread over the land in autumn it gets frozen while still full of water, and becomes reduced to a comparatively fine powder which can be ploughed in if on arable soil or spread with a harrow on the pastures. Very large quantities of chalk are used, up to 100 loads to the acre; naturally the effect of such treatment is more permanent than the usual liming.

The custom of "chalking" was very extensively practised during the seventeenth and eighteenth centuries in Hertfordshire on the high plateau land on which the Rothamsted estate is situated. There the "clay with flints" and the "boulder clay," though not, as a rule, more than 10 to 12 feet thick, and resting on the chalk rock from which they have largely been derived, have been completely decalcified by the solvent action of the rain water, and no longer contain more than a trace of carbonate of lime. It was customary to sink bell pits through the clay until the chalk was reached; this was then dug out, hauled to the surface in baskets, and dragged out on to the fields in sledges. Sixty to a hundred or even a hundred and fifty loads per acre were spread, and from time to time the process was repeated. The amount of chalk thus spread upon the surface was considerable; the surface soil of the arable fields on the Rothamsted estate now contains from 3 to 5 per cent. of carbonate of lime, which is equivalent to 30 to 50 tons per acre; and since none has been spread for the last seventy years at least, and solution in the rain water has constantly been going on, there must have been nearer 100 tons per acre at the beginning of the nineteenth century.

The result has been practically the creation of a soil fit for arable farming, for some of the Rothamsted fields which had never undergone the operation have had to be laid down to grass, so difficult did their cultivation prove in wet seasons.

A similar process, with like results, has been applied to the "red clay with flints" which occurs on the top of the chalk plateau in Kent, Surrey, Hants, and Dorset, as well as in the Chilterns and Herts. In several cases where advice has been sought as to the reasons for the infertility or bad working quality of a particular field, it

has been found that the particular field had escaped the chalking process, and that the land could be brought into order by a good chalking or liming. On the lighter soils ground chalk or limestone is more suitable than lime. With the carbonate, though larger quantities have to be applied to produce the same effect and the action is slower, there is not the same risk of giving an excess, as is the case with caustic lime. An excess of caustic lime begins by causing a partial sterilisation of the soil and a disturbance of the micro fauna and flora, which results in a depression of the first crop, followed by a comparatively rapid decay of the plant reserves and increased yields later, though accompanied by waste of these reserves. The action of the carbonate of lime in ground chalk or limestone, even in large excess, does not cause either the preliminary depression or the too rapid decay and waste of the organic matter of the soil.

A large proportion of the soils of Great Britain are in need of lime, by the lack of which their fertility is impaired, cultivation is rendered both more difficult and uncertain, and disease is more prevalent among the crops. On many of the sands and clays that cover much of England, as, for example, on the New Red Sandstone, the Lias, Oxford and London Clays, and the Tertiary Sands, the output of the soil might be enhanced and its value increased by from 10 to 20 per cent. by the proper use of lime.

A comparatively simple chemical determination, which can be obtained from the laboratory of any agricultural college, will provide the necessary information as to whether the soil needs lime. There are also several trustworthy natural indicators. The presence among the weeds of the arable land of any quantity of spurrey (*Spergula arvensis* and *Spergularia rubra*) on

sandy soils, of sheep's sorrel (*Rumex acetosella*) and of corn marigold (*Chrysanthemum segetum*) or of foxgloves in the hedgerows, provides a sure indication of acidity in the soil, that needs lime for its correction.

CHAPTER X

SOIL TYPES

Classification of Soils according to their Physical or Chemical Nature—Geological Origin the Basis of Classification—Vegetation characteristic of Various Soil Types: Physical Structure, Chemical Composition, Natural Flora and Weeds characteristic of Sands, Loams, Calcareous Soils, Clays, Peat, Marsh, and Salt Soils—Soil Surveys, their Execution and Application.

PERHAPS the question of the greatest practical importance in connection with the scientific study of soils is their classification into certain types defined by their physical or chemical properties, and the allocation of these types to their appropriate areas, so as to obtain a soil map of any given district. Despite disturbing factors, to which allusion will be made later, certain types of soil persist over wide stretches of country, and are characterised not only by a general resemblance in chemical or physical constitution, but by a corresponding similarity in the natural flora they bear, and their appropriateness to certain crops. The constancy of the soil types is the result of a common origin from the same kind of rock, and the difficulty lies less in recognising the types than in drawing boundary lines, so imperceptibly does one class shade off into another. The only classification that can be at all general, is one based upon the physical structure

and texture of the soil, viz., into sands, loams, and clays, with subdivisions dependent on the presence or absence of calcium carbonate, and upon the situation, as causing the accumulation or otherwise of humus.

In attempting to review the vegetation appropriate to different types of soil it will be found that two distinct factors must be taken into account—the relations of the soil to water, and its chemical constitution—which factors often interact in a complex fashion, different causes producing the same effect. A plant, for example, may be found upon sand because of its dryness, or, because of the absence of calcium carbonate usually associated with sand; another plant, having adapted its structure to use very small quantities of water, may equally well be found on a dry sand, or on a clay which holds so much water as to be injurious to the ordinary plant.

Plants have adapted themselves to conditions of dryness in very diverse ways; in some cases, as in gorse or broom, the leaf surface is much restricted; in others, the thickness of the cuticle has been increased, or the surface of the leaf is thickly clad with hairs; in other cases the leaves possess special tissues for storing water. Such plants are known as “xerophytes,” and are found on soils which appear to differ very much from one another, for a soil may contain plenty of water and yet be physiologically dry, because of the presence of some other constituent hindering the absorption of water by the plant.

The areas on which xerophytic plants are found include not only the true desert areas, where great heat and intense illumination occur during the larger part of the year, but also the pervious sandy soils retaining very little moisture—sand dunes, shingle flats, and the like. Again, the plants of alkali soils and of

salt marshes invaded by the sea, develop a xerophytic structure, because they would be injured if they absorbed large amounts of saline soil water. Peaty areas also act in the same way, for it is found that the humic acids in such soils withhold the water from the plant very obstinately. Exposed elevated regions with a low temperature, by reducing the power of the roots to absorb moisture, render it necessary that the plant should lose little by transpiration; hence we see certain conifers flourish both on dry sandy soils and wet elevated moors.

As regards the chemical side of the question, the most important soil constituent affecting vegetation is calcium carbonate; a large number of plants seem absolutely intolerant of lime in the soil, while others are rarely seen off limestone and chalk areas. Even among the humus-loving plants a different flora is found on the acid peaty areas from that prevalent on the mild humus areas where the soil water contains calcium bicarbonate in solution.

But, however characteristic the general aspect of the vegetation may be upon the different types of soil, it is rare to find cases of plants entirely intolerant of a different kind of soil from that which they habitually frequent; many plants show a preference for one soil or other without being exclusively confined to it. For example, the common primrose is undoubtedly a clay lover, yet it will be found widely distributed over all the English soils; the beech and the yew are typical trees of the chalk, good oak and hornbeam of the clay; Spanish chestnut, and many conifers like the Scotch fir, are sand lovers; yet each of these trees will be found commonly enough on other kinds of soils. It will rarely be found that plants will absolutely refuse to grow or even to flourish on soils of which they are naturally

season but can be proceeded with very readily, they are especially suited to market gardening, wherever situated sufficiently near to a large town to enable large quantities of manure to be obtained cheaply. Where the water table is close to the surface, sandy soils can become very fertile, roots range freely in them, and applications of manure have their full effect. Like all light soils, they are apt to become very weedy. Of the crops suitable to soils of this type, spring wheat is often better than the autumn-sown variety; the quality of wheat is, however, generally inferior on sandy soils; barley is better than oats, and maize is worthy of attention as a fodder crop. Swedes, cabbages, and the cruciferous crops generally, are subject to "finger-and-toe," in consequence of the poverty of the soil in lime and soluble mineral constituents.

With certain exceptions, leguminous plants do not grow well on sandy soils, and require considerable supplies of lime and mineral manures; there are, however, some leguminous plants which are characteristically *calcifuges*—i.e., intolerant of lime in the soil—lupins, serradella, and gorse belong to this class. Allusion has already been made to the reclamation of sandy land in Prussia by means of lupins, and probably more use might be made of the crop in this country on similar soils. Experiments made with gorse on the coarse sandy soil of the Royal Agricultural Society's farm at Woburn, indicate that it may become a profitable fodder crop on such soils.

Potatoes are perhaps the best crop on the sandy soils, but require considerable expenditure of manure, including large dressings of potash, to do well. Carrots are another crop particularly appropriate to sandy soils, as they need a deep, fine tilth.

The manuring of sandy soils must be based upon a

liberal use of lime, frequently renewed because of the ease with which water percolates and removes the calcium carbonate. Marling and chalking, wherever such materials are available, are better for the land than the use of quicklime, which is apt to induce too rapid an oxidation of the organic matter. Nitrogen is best supplied in its organic forms, as in well-rotted dung, the guanos, fish or meat manure, rape cake, etc.; nitrate of soda is apt to induce too rapid a growth, and also to be washed away. Sulphate of ammonia is unsuitable, owing to the lack of lime in the soil. Of phosphatic manures, superphosphate is unsuitable owing to its acid nature. Owing to the small quantities of water retained by the soil, basic slag is better suited for the permanent enrichment in phosphates of a sandy soil than for the feeding of a particular crop, though it answers well on sands where the water table is near the surface; on the whole, neutral easily available phosphates like phosphatic guano and steamed bone flour give the best results on these soils. Potash manures are much needed, and either kainit or sulphate of potash may be used. Gypsum is often used with good effect on such soils in the Wealden area, acting as a liberator of what little potash may be in the soil.

The natural flora of the sandy soils is of a double character—in part *xerophytic*, and associated with the prevailing dryness of the soils; in part *calcifuge*, and dependent on the absence of calcium carbonate. Plants with mycorrhiza are abundant, owing, as already explained, to the comparative poverty of these soils in both water and soluble salts.

The characteristic sand trees are the Spanish chestnut, birch, holly, and many conifers; of these the Spanish chestnut and some of the firs, like

Pinus pinaster, are particularly intolerant of calcium carbonate.

Many of the Ericaceæ, such as common heather and the heaths, cultivated species like the rhododendrons and azaleas of our gardens, are similarly intolerant of lime and associated with sandy soils; at higher levels various species of *Vaccinium* and kindred plants are common. Gorse (*Ulex europæus* and *U. nanus*), broom (*Cytisus scoparius*), *Genista anglica*, *Ornithopus*, and several vetches like *Vicia cracca*, are characteristic leguminous plants of sandy soils. The foxglove (*Digitalis purpurea*), sorrel (*Rumex acetosella*), and in undrained situations the sundews (*Drosera* sp.) are intolerant of lime and are common plants on sandy soils, as also are the common bracken (*Pteris aquilina*), and wavy hair grass (*Aira flexuosa*).

Characteristic weeds of sandy soils are, spurrey (*Spergula arvensis*) and sandwort-spurrey (*Spergularia rubra*), corn marigold (*Chrysanthemum segetum*) and knawel (*Scleranthus annuus* and *perennis*); *Papaver dubium* and *Centaurea cyanus* are also common on such soils. The bulbous buttercup (*Ranunculus bulbosus*) is very frequent on dry pastures, whether sandy or chalky, as is the small bindweed (*Convolvulus arvensis*) of similar soils under cultivation; the silverweed (*Potentilla anserina*), though generally indicative of winter flooding, is to be found on all kinds of poor, light land.

The Loams.

The sandy soils pass by imperceptible stages into the loams—free-working soils containing enough sand to be friable and to admit of percolation, yet retaining sufficient water near the surface to withstand short spells of dry weather. If the sandy fractions of the loam are mainly fine grained, the soil is apt to

run and become very sticky in wet weather, afterwards drying to hard clods; an admixture of coarser sand results in a better texture. The loams are typical soils of arable cultivation and are suitable to all crops; their manurial requirements vary with the origin of each soil, and are largely conditioned by its poverty or richness in calcium carbonate. While no special flora can be associated with the loams, there are several weeds generally taken as indicative of good fertile soils of this class; such are chickweed (*Stellaria media*), groundsel (*Senecio vulgaris*), fat hen (*Chenopodium album*), stinking mayweed (*Anthemis Cotula*), and the Sow thistle (*Sonchus oleraceus*). Other weeds of cultivated land, which only occur when the soil is capable of carrying fair crops, are goose grass (*Galium aparine*), the speedwells (*Veronica agrestis*, etc.), pimpernel (*Anagallis arvensis*), henbit (*Lamium amplexicaule*), wild poppy (*Papaver rhæas*), and the small spurges like *Euphorbia Peplus*. The alluvial soils which border the rivers and pass into considerable marshes at their mouths, must, by their texture, be classed among the loams, and present no specific features, except where they are waterlogged and marshy, or near the sea where the subsoil water becomes so rich in salt as to alter the character of the vegetation. The marshy patches accumulate, as a rule, what has already been described as "mild humus," owing to the presence of bicarbonate of lime in the soil water; it is generally accompanied by deposits of pulverulent ferric hydrate. The presence of rushes, of sedges like the carnation grass, or orchids, like *O. maculata* and *O. latifolia*, are characteristic of these spots requiring drainage. Lousewort (*Pedicularis palustris*) is said only to occur in marshes where the water contains lime.

The salt marshes possess a characteristic vegetation of what are termed halophytes, plants capable of resisting a considerable quantity of salt in the medium in which they grow. Among cultivated plants, mangolds, asparagus, and crucifers like cabbage are most tolerant of salt, and the two former are true halophytes.

Many halophytes live by acting as xerophytes, and taking very little water up; they are also able to store away in their tissues quantities of saline matter which would be toxic to the majority of plants. The ash of *Armeria maritima* shows 12 to 15 per cent. of chlorine in the ash; in *Aster tripolium* the proportion rises to over 40 per cent. in the ash of the leaves, and to 50 per cent. in that of the stem; yet although the plants habitually contain these large amounts of salt, they will grow perfectly well in ordinary soil where they can get but little.

The Australian salt-bush (*Atriplex semibaccatum*), which has already been mentioned as tolerant of a large amount of alkali in the soil, also removes much soluble matter—the dry plant containing as much as 20 per cent. of ash, so that the salt content of the soil may be materially reduced by cropping with this plant. The halophytes seen in the salt marshes of this country consist of various species of *Atriplex*, *Beta* (the source of the cultivated beets and mangolds), and other Chenopodiaceæ, *Statice armeria*, *Aster tripolium*, *Frankenia*, and a number of cruciferous plants like *Crambe*, and *Cakile*, with umbellifers like *Crithmum*. Some plants show a great dislike to salt, even in small proportion, e.g., the Rosaceæ, Orchidaceæ, and the Ericaceæ.

Calcareous Soils.

It is difficult to draw an exact line of demarcation between the loams and calcareous soils, so variable is the proportion of carbonate of lime, owing to its continual removal by the percolation of water containing carbonic acid. Even on the chalk and limestone, where the thickness of the soil layer is to be measured in inches, the surface soil may have its calcium carbonate almost wholly removed, and, again, where the deeper soils of calcareous origin accumulate in the valleys, there is nothing to distinguish them from ordinary loams. However, the general aspect of the calcareous soils containing from 5 to 60 per cent. of calcium carbonate is characteristic, and the natural flora always indicates the presence of much lime. The texture of the calcareous soils may vary within any limits, according to the formation from which they have originated. On the one hand, extremely fine-textured heavy marls exist; for example, the soils derived from the strata at the base of the Chalk and upper beds of the Gault in the south and east of England; on the contrary, fairly coarse sand may form a considerable proportion of the soil, rendering it light in texture, as is the case with many of the soils resting on the chalk of the North Downs. In all cases these calcareous soils are typically sticky when wet, and easily cake on the surface when dried. Such soils, again, lose their organic matter very rapidly by decay; in farming them it is desirable to use every means to increase the proportion of humus by adding farmyard manure, by folding roots on the land, or by ploughing in green crops. Slowly acting nitrogenous manures, like rape dust or shoddy, are valuable; again, there is always enough calcium carbonate present naturally to render to sulphate of

ammonia its full value as a source of nitrogen. The lighter calcareous soils require a free use of nitrogenous manures to get good crops. Calcareous soils are generally well provided with phosphoric acid, owing to the organic origin of the calcium carbonate; the rule is, however, by no means universal, the upper Chalk, for example, yields soils with less than 0.1 per cent. of this constituent. Superphosphate is undoubtedly the best source of phosphoric acid for such soils, basic slag is almost without action. The proportion of potash present in these soils is generally reflected in their texture; if light and near the unaltered rock, they are, as a rule, very deficient in this constituent, and require its addition for the growth of any of the root crops. Salt is generally beneficial as an addition to manures on the calcareous soils.

The calcareous soils are generally warm, dry, and healthy for stock; when deep and sheltered they are extremely fertile; the thinner soils are rather subject to certain insect pests, like the turnip flea. The abundance of worms in chalky pasture is worthy of note. The lighter calcareous soils are notoriously weedy. In addition to the usual weeds of light land, Fumitory (*Fumaria officinalis*), *Geranium molle*, and kindred species, are almost confined to soils with a considerable proportion of calcium carbonate. Two crops are very characteristic of calcareous soils wherever the climate will admit of their growth, viz., sainfoin and lucerne, which flourish excellently, and provide abundant and valuable fodder even on the driest chalk soils.

The natural flora of these calcareous soils includes the beech, yew, and wild cherry, among trees; the juniper, box, mealy guelder rose (*Viburnum lantana*),

beam tree (*Pyrus aria*), dogwood (*Cornus sanguinea*), and *Clematis vitalba*, among shrubs.

The vegetation is characteristically rich in flowering plants: amongst the Leguminosæ, the horse-shoe vetch (*Hippocrepis comosa*), bird's-foot trefoil (*Lotus corniculatus*), kidney vetch (*Anthyllis Vulneraria*) are everywhere abundant; milkwort (*Polygala*), bladder campion (*Silene inflata*), *Spiræa filipendula*, burnet (*Poterium sanguisorba*), wild parsnip (*Pastinaca sativa*), sheep's scabious (*Scabiosa columbaria*), chicory (*Cichorium intybus*), and certain of the Gentianaceæ, as *G. amarella* and *Chlora perfoliata*, the viper's bugloss (*Echium vulgare*), and a number of labiates like *Origanum*, are characteristic of the pastures and waste places on chalk and limestone. Amongst grasses, *Avena pubescens*, *A. flavescens*, *Bromus erectus*, and *Brachypodium pinnatum* are common.

While it has been indicated that many plants are intolerant of lime, others show the effect of any excess in the soils by a stunted development of the plant, often accompanied by a reduced size of the leaf, and a sickly yellow or even white colour. This unhealthy condition of "chlorosis" is particularly noticeable on the stiff marls, which are but little aerated but contain much calcium carbonate; on the Continent it often affects vines, particularly when grafted on American stocks.

Clay Soils.

It has already been indicated that clay soils are those in which the finer fractions of sand, silt, and clay predominate; the presence of any considerable proportion of coarse sand causes the soil to become friable, and would class it with the loams. The texture of clay soils naturally varies very much; the heaviest clays occur in dry climates, where the percolation

has not been sufficiently great to wash away many of the finer particles; in the east and south-east of England the Oxford and the London Clay, with the Boulder clays derived therefrom, give rise to the most stubborn and intractable clays. On these soils the old practice of an occasional bare fallow is still carried out, and is almost necessary to maintain the soil in good cultivation. As a rule, the strong clay soils towards the close of the last century were laid down to permanent pasture; the cost and the difficulty of arable cultivation (for much wet weather in autumn or spring may render it impossible to put horses on the land for long periods), and the great fall in prices of both wheat and beans, the staple crops of such land, rendered it necessary to resort to a cheaper method of farming.

Most clays carry good permanent pasture, because the soil retains enough water to keep the grass growing through any but the longer periods of drought; in very dry years, however, clay suffers severely from the drought; the surface cracks and the subsoil dries through the cracks; the resistance also offered by the close texture of the soil to the capillary rise of soil water renders the winter rainfall less available to the crop than on soils of lighter texture. The benefits accruing from drainage, in making the soil dry more quickly after rain and resist drought better, have already been discussed. Certain clay soils may be found too close textured to carry good pasture; the soil sets so firmly that aeration becomes very defective, and the vegetation degenerates into surface rooting, stoloniferous grasses like *Agrostis alba*.

Owing to their fine division, their origin from the compound silicates of primitive rocks, and the reduced percolation which they permit, all clays are compara-

tively rich in soluble mineral salts. Many of them show crystals of selenite ($\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$) in the subsoil comparatively near to the surface; magnesium sulphate is often abundant, and strongly impregnates the water obtained from the wells or the occasional springs to be found in the clays. In the Weald of Kent the shallow wells in the clay yield water that is almost undrinkable, containing, as it does, from 150 to 450 parts of dissolved matters per 100,000, consisting chiefly of the sulphates (with some chlorides) of magnesium and calcium. The sulphates often originate from the oxidation of finely divided iron pyrites. The presence of ferrous salts and other unoxidised iron compounds has already been alluded to as a source of sterility in clay soils, particularly where the subsoil has been incautiously brought to the surface. In the cultivation of all land it is important to keep the surface soil on the top, and to attempt to deepen the staple with care; but this is particularly the case with clays, where the land may easily be injured for years by over-deep ploughing. No soils show more marked change than the clays do in passing from soil to subsoil, both in chemical composition and physical texture.

Many clay soils, especially when undrained, possess a great tendency to accumulate hydrated ferric oxide some few inches below the surface, at about the level to which the soil is ordinarily aerated. This deposit sometimes forms a continuous layer or "pan"; in drier climates it becomes a kind of "crowstone" gravel, made up of little nodules of hydrated oxide of iron, containing also manganese. This material frequently forms a serious obstacle to cultivation, and requires to be broken up with a crowbar or a subsoil plough before any deep-rooting crop can be properly grown. Its origin is perhaps not entirely explained as yet; the

respective shares of the iron bacteria of Winogradsky, or the purely chemical actions of solution and reduction by the organic matter and carbonic acid, followed by redeposit on evaporation, is a matter requiring further investigation. The formation of the material is only noticed in clays very poor in calcium carbonate and liable to waterlogging through insufficient percolation.

Owing to their coolness, their retention of moisture, and comparative impermeability to air, humus tends to accumulate in the clay soils; both arable and pasture soils show a higher proportion of organic matter and of humus than is found, as a rule, on the lighter lands; the effect of manures like farmyard manure is also more lasting. The use of more slowly acting nitrogenous manures is therefore not so desirable on the clay soils; on the other hand, sulphate of ammonia is often unsuitable because of the want of calcium carbonate, and nitrate of soda, which often gives the best returns, is apt to affect the texture injuriously.

The clays are very generally deficient in calcium carbonate, often to an extreme degree, much to the detriment of the texture of the soil. The use of lime is of the utmost value to all clay soils, improving the texture, making them drier and therefore warmer and earlier, and rendering available the supplies of nitrogen and potash with which they are often liberally endowed. The excess of magnesia and unoxidised iron compounds which also characterise many clays is corrected by the use of lime.

Many clay soils also show a considerable deficiency of phosphoric acid, and respond freely to dressings with manures containing this substance. Superphosphate may be used with advantage wherever there is

enough calcium carbonate in the soil, but basic slag is the typical phosphatic manure for the strong soils which retain sufficient water to render the phosphates active. While supplying phosphoric acid, it also contains free lime in a fine state of subdivision, and so liberates in a soluble state the reserves of nitrogen and potash in the soils. It should, however, not be forgotten that as the basic slag only supplies one element of plant food, the phosphoric acid, the soil may easily be exhausted by continual cropping and manuring with basic slag alone.

Potash is always present in large amounts in clay soils, 0.5 per cent. soluble in strong hydrochloric acid is often to be found, while the proportion which can be extracted after completely breaking up the soil with hydrofluoric acid may rise to 2 per cent. Clay soils are late, and their crops grow slowly and ripen tardily except in specially dry seasons, when the clay shrinks so much as to cut off all access of moisture from the subsoil, and prematurely ends the period of growth; on the other hand, the quality of crops grown on the clay is often high. The typical crops of strong land are wheat, beans, and mangolds; owing to the closeness of the texture of the soils, weeds are much less in evidence on the clays than elsewhere, though some few are exceedingly troublesome.

On the poorer pastures, the spiny form of rest harrow (*Ononis arvensis*), the wild teasel (*Dipsacus sylvestris*), *Ranunculus arvensis*, and *Genista tinctoria* are characteristic and often troublesome weeds; on cultivated land, the "black-bent" grass (*Alopecurus agrestis*) and field mint (*Mentha arvensis*) are difficult to deal with. Other plants characteristic of strong soils are the primrose (*Primula vulgaris*), and the wild carrot (*Daucus carota*).

Peaty Soils.

The accumulation of humus to form peaty soils has already been discussed, and is associated with water-logging, which cuts off the access of air and so sets up an anaerobic fermentation of the residues of the vegetation growing upon the surface. There is always a deposit of ferric hydrate accompanying the accumulation of peat, as explained before. As the reclamation of peaty soils has already been dealt with, it will be sufficient here to indicate that their great characteristic is a deficiency in soluble mineral constituents, notably salts of lime and potash. It has also been mentioned that, as a consequence of the acid nature of the medium, the bacteria of nitrification are absent or few in number. All attempts at the cultivation of peaty soils begin with drainage, and must then proceed on the basis of neutralising the organic acids with lime and providing a sufficiency of mineral food for the plant, thus also inducing nitrification to render available the large quantities of nitrogen which have accumulated. Of the common crop plants, oats and potatoes are perhaps the most tolerant of extreme amounts of acid humus. The normal vegetation of peaty soils is a mixture of xerophytic and calcifuge forms; the Conifers, the Ericaceæ, *Drosera*, *Rumex Acetosella*, *Pedicularis sylvatica*, Sphagnum moss, and many sedges and rushes, are characteristic of sour, peaty soils. Other characteristic plants are more properly Northern or Arctic species, and, occurring only in the uncultivated uplands, need not be considered here.

Soil Surveys.

To render the scientific study of soils properly available for the service of the agriculturalist, more is required than the examination of single samples of soil, representing, at the best, only the land dealt with by one person. Over any wide district, not only would such work become expensive and practically endless, liable also to many sources of error through local and accidental variations of the soil on the spot from which the sample was drawn, but each analysis would lose the greater part of its value if it could not be co-ordinated and brought into line with others drawn from soils of the same type. A general soil survey of a district, so as to be able to lay down a plan of the distribution of the various soil types, accompanied by a discussion of the broad characteristics of each, should be the basis upon which the interpretation of the analysis of the soil of any particular field is to be founded. Only by comparison with the type can the analysis of any particular soil be properly interpreted—*e.g.*, the fact that a soil from a given arable field contains 0.15 per cent. of phosphoric acid takes a very different aspect when it is known that the soils of the same type contain, as a rule, 0.18 to 0.20 per cent. of phosphoric acid, particularly if, also, the response of that kind of land to phosphatic manures is known by field trials, or from the accumulated experience of farmers. The first question which requires settlement is how far a soil survey is possible; to what extent can the boundaries of soil types be traced; are the various types sufficiently constant over a wide area to render this mapping feasible? In many cases there seems to be little but confusion, even in the soils on a single farm; field differs from field, and great variations

may be manifest even within the confines of a single field. But, in the main, each soil type has a well-defined area, within which it presents a reasonably constant composition and texture, and though the boundaries cannot be laid down with the precision of the outcrop of a stratum, the zone of transition from one type to the other may be indicated with approximate accuracy.

The basis upon which any soil survey must be constructed is the origin of the soils; each geological formation, for example, will give rise to a distinct type of soil if it has been formed *in situ*; should the weathered material have further undergone transport by water, two or more types may have been constructed by the sorting action of the water. It is also well known that a geological formation may change very considerably in lithological character in passing from the lower to the upper portions of the bed. For example, stiff as the London Clay is, the upper beds become increasingly sandy in character, so that it is not easy to draw a line of demarcation between the soil arising from these beds and those due to the Bagshot Sands above. The lower beds of the Gault Clay are also very pure, and give rise to a stiff clay deficient in calcium carbonate; the upper beds become marly, and form soils indistinguishable from those due to the contiguous Chalk Marl. Similarly, a geological formation may show a progressive change of character in passing into a different area, which change will be reflected in the soils derived from them. For example, the Great Oolite limestones of the Cotswolds shade off into sandstones in Northamptonshire, and the Hythe beds of calcareous sandstone in East Kent become pure coarse-grained sandstones in West Surrey. However, in the main, geological origin may be taken as the basis of a soil survey, to which must be added the

further subdivisions due to the causes enumerated above, or to the local movements of rain-wash or ill-defined drift, that may alter the character of the soil without being of any particular geological importance.

A soil map will consist of a "drift" map, with some further details showing the superficial formations occupying the surface of the ground, and notes regarding the local variations in the type of soil derived from each particular stratum. The aim of a soil survey is to carry further the work of the geological survey as regards the superficial formations; the only classification which can be adapted will be one based upon the physical texture of the soil, and indicated by such conventional terms as clays, clay loams, sandy loams, marls, etc. At the same time, the map must indicate the various origin of the different loams which may be found in the area under survey, and, by reference to the accompanying text, should give those details of physical structure and chemical constitution which characterise the soil, but which cannot be set out except by an over-elaborate classification.

The field portion of the work of a soil survey consists in the exploration of the subsoil by means of an auger, aided by any natural sections which may be displayed. The boundary between two soil types may generally thus be laid down by the aspect of the soil and subsoil; from time to time, however, samples must be retained for more detailed examination in the laboratory, whenever the look and touch of the material are not sufficient for a decision *in situ*. An immediate examination with the microscope, the behaviour of the soil with acid, or a rough sifting in a stream of water, will, as a rule, be sufficient to refer a given example of subsoil to one type or another. Complicated cases arise from time to time, especially in

the river valleys, where alluvium of varied epochs and rain-wash of not very different origin may be hopelessly intermingled. In many cases, however, where the outcrop of the originating formations is broad, and where the gradients of the country are slight, the soil may be extremely constant in composition over a wide area, so that the survey has only to notice such minor variations as the grading from a lighter to heavier type as one descends a slope, or the occasional influx of drift material by creeping from a neighbouring area. The further work of a field survey will be the selection of typical samples of soil and subsoil for detailed examination and analysis in the laboratory, the collection of such data as the distance to, and nature of ground water, and any particulars which may be available locally, as to special features in the working of each type of soil, or in the growth of its crops; the nature and character of such deposits as "brick earth" in each district can also be reported. The samples for detailed analysis should be taken where a general survey of the district indicates the soil as most likely to be typical of the formation and free from admixture with drift and other accidental intrusions. At the same time, since the soil in the main will by no means be so pure as the typical samples, a much larger number of samples should be taken and subjected to a less detailed examination, by way of ascertaining within what limits the normal variation of the soil is confined.

The number of type samples to be taken must be entirely decided by an examination of the circumstances; in continental areas, where deposition has been very uniform over wide districts, one or two samples may be sufficient to characterise an extensive soil type; in other cases the local variations may be so

much in evidence that the "typical soil" can only be constructed by putting together the results of many separate determinations.

But the practice of constructing a typical soil for analysis by mixing together equal fractions of many samples drawn in the area in question, is not to be recommended. Not only may an entirely foreign or accidentally impure sample be introduced without detection, but, further, the limits of variation normally to be expected in individual soils of the same type is just as important as the composition of the type itself. Again, the existence of unsuspected systematic variations is entirely obscured by any process of mixing samples. The character of the information which should accompany the soil maps must largely depend on the purpose of the survey, whether it is concerned with the agriculture of an old and settled country, or whether it partakes of the nature of an exploration, and aims at showing the capacities of the land for new crops and industries. In the United States, for example, the latter form of soil survey is exemplified; in many parts of the country agriculture is so recent that there is no accumulation of experience as to the crops most suited to each kind of land; hence the survey, by comparisons of the texture of the soil, the climatic conditions, and the depth to ground water, with the conditions prevailing in better known areas, can directly tell the settler with what crops he is most likely to succeed. The cultivation of special crops like tobacco and sugar beet, to take two examples of special interest at the present time in the United States, can be extended into new districts possessing suitable soils, with a minimum of the risk which must always attend the introduction of a novel form of culture. The suitability of other classes of land for irrigation, the

nature and extent of already existing alkali patches, and the most promising methods of reclamation, are also prominent features in the work of the United States soil survey. As the crops in a new country of this kind are in the main grown by the aid of the natural fertility of the soil alone, and fertilisers are little used, the chemical examination of the soil becomes of less importance than the mechanical.

In a settled country like our own, the character of the information to be derived from a soil survey is of a different order; the land has been under cultivation so long that a great mass of local information, based upon experience, exists as to the character even of individual fields.

Hints as to the cultivation, based upon the texture of the soil as determined by analysis, would be too general to be of any service; indeed, it is rather to be hoped that by collating many mechanical analyses with the information derived from men possessing long experience of the soil, further light can be shed upon the connection between physical structure and the finer points of tillage. The suitability of the different types of soil to new crops—as, for example, the extension of the area under fruit—can be ascertained, and many expensive mistakes due to planting on unsuitable land could be saved to the farmer. Suggestions can also be made as to the amelioration of the soil by drainage, or by the incorporation of materials like clay, chalk, or marl, occurring in the vicinity. Fifty years ago, no department of British agriculture was more carefully attended to than the improvement of the texture of the soil, and great tracts of what is now fertile land were practically created; lower values to-day have caused this important matter to be almost entirely neglected.

But the chief application of a soil survey in this country lies in the information that can be afforded as to the use of manures; enormous economies might be effected in the bills of almost every farmer using artificial manures, if the latter were properly adapted to his soils and crops. Farmers are often recommended to carry out manurial trials upon their own farms until they have ascertained the peculiarities and specific requirements of the soil, but advice of this kind treats altogether too lightly the somewhat delicate business of conducting field experiments. Putting aside the mechanical difficulties attending a trial of this kind, and the overpowering effect of minor inequalities of the ground and other accidental conditions which so often nullify the experimental treatment, it is rarely that the farmer will be found able to arrange a scheme of experiment likely to give information of permanent value. If one may judge from the published accounts of many field experiments carried out in this country by public bodies, which so often show a misapprehension of the points really at issue, there is every probability that the individual farmer will be as often misled as guided by the results of his own experiments. The design and conduct of field experiments must be left to the expert, who surveys the subject from a wider standpoint, who can compare various trials, and is in a position to continue them for a period of years, rejecting at any early stage a considerable proportion which are inevitably vitiated by some concealed local peculiarity. A body of experts conducting a soil survey and field experiments simultaneously in the same area and co-ordinating their results, can give advice of the most definite character as to the scheme of manuring to be adopted for each soil type. The fundamental factor requiring consideration in this matter, and brought out

in the soil survey, is the proportion of lime normal to each soil type; knowing this factor, and the retentivity of the soil for moisture under ordinary conditions of rainfall, one can decide upon the character of the manures for most loamy soils. Soils of more specific character, like the sands or clays, present more characteristic deficiencies of some of the manurial constituents, so that for many crops the use of manures like phosphates and potash is wholly determined by the soil and not the crop.

It is not too much to say that the information as to the manuring which is being accumulated at many experimental centres throughout the country can only be rendered properly available by the execution of a soil survey in the district under consideration. In many countries a soil survey has been made part of the national service for the agriculturist; the magnificent publications of the Division of Soils of the United States Department of Agriculture form a case in point. In Prussia, the maps and reports of the *Laboratorium für Bodenkunde* at Berlin may be consulted as models of the thoroughness and refinement to which work of this kind can be pushed; the Gembloux Station in Belgium is executing a systematic chemical survey of the Belgian soils. In France, the work rests with the local authorities of each Department, but in parts is being carried out, as witness the beautiful maps due to the single-handed work of M. Gaillon, Director of the Station Agronomique de l'Aisne at Laon. In Britain the great initial want is the publication of "drift" maps of the geological survey on the 6-inch scale; the 1-inch to the mile survey, which alone has been published, or even executed in most districts, is too small to admit of necessary detail. It is also very

often laid down on an early cadastral survey, which makes the identification of the modern boundaries a matter of difficulty. If the country were in possession of a series of "drift" maps on the scale of 6 inches to the mile, the work could be rapidly supplemented by soil surveys and analyses executed by the local agricultural colleges and research institutions, until every farmer could be put in possession of that exact knowledge of the soil which is fundamental to all farming operations.

APPEN

ANALYSES OF SOME

	1	2	3	4
	Red River Valley.	Dunbar.	Boston Warp.	Oving, Sussex.
MECHANICAL ANALYSIS.				
	Prairie.	Arable.	Arable.	Arable.
Fine Gravel, above 1 m.m.	0.99	0.0	0.9
Coarse Sand, 1-0.2 m.m.	1.6	23.66	0.11	1.30
Fine Sand, 0.2-0.04 m.m.	3.8	35.18	53.58	16.0
Silt, 0.04-0.01 m.m.	17.1	6.81	12.32	36.5
Fine Silt, 0.01-0.002 m.m.	28.3	11.80	10.32	13.3
Clay, below 0.002 m.m.	23.3	9.48	14.66	15.9
Moisture	1.08	2.06	3.3
Loss on Ignition	26.3	6.16	6.35	6.5
Calcium Carbonate	0.31	0.08	0.75
CHEMICAL ANALYSIS.				
Moisture	1.08	2.06	3.3
Loss on Ignition	26.3	6.16	6.35	6.58
Nitrogen	1.0	0.162	0.184	0.22
Potash	1.033	0.460	0.629	0.43
Potash, soluble in 1 per cent. Citric Acid	0.076	0.023	0.017	0.014
Phosphoric Acid	0.288	0.120	0.189	0.138
Phosphoric Acid, soluble in 1 per cent. Citric Acid	0.054	0.022	0.034	0.020
Lime, CaO	1.89	0.90	0.62	1.79
Magnesia, MgO	0.65	...	0.40
Carbonates as CaCO ₃	0.31	0.08	0.75
Oxide of Iron, Fe ₂ O ₃	5.50	3.60	3.05
Oxide of Manganese, Mn ₂ O ₄	0.13	0.11	0.06

Soil No. 1 represents one of the richest soils in the world, from the Red River Valley, Manitoba. It extends to a depth of 4 feet of black clay loam, alkaline in its reaction, and crumbling easily when dry. The most remarkable feature is the astonishing amount of nitrogen it contains, the organic matter constituting one quarter of the soil. Its potash content is also exceptionally high, and is correlated with the large percentage of clay and silt in the inorganic portion of the soil.

No. 2 is one of the famous red potato soils from Dunbar, of a rather lighter type than the soils that follow, but in high condition from continued high cultivation.

Nos. 3, 4, 5 and 6 are all alluvial soils of great repute and in a high state of fertility. It will be noticed that they have much in common. The fine sand and silt fractions predominate, and the clay does not exceed fifteen per cent. These are all good wheat and potato soils under the climate of the east and south of England; they are also among the finest fruit soils.

DIX I.

TYPICAL SOILS.

5	6	7	8	9	10
Teynham, Kent.	Yalding, Kent.	Orgarswick, Kent.	Whitstable, Kent.	Newington, Kent.	Blackheath, Surrey.
Arable.	Arable.	Pasture.	Arable.	Arable.	Waste.
0.7	3.2	0.1	0.4	0.5	1.2
2.1	13.1	0.0	0.8	16.9	65.9
39.1	40.0	35.5	6.5	57.3	23.7
26.1	16.5	17.7	15.8	8.2	2.4
8.6	9.0	10.5	16.3	3.9	2.0
11.7	9.1	19.1	40.5	6.0	0.9
3.5	2.1	2.4	6.5	1.7	0.4
5.3	4.0	14.2	9.0	3.7	2.6
0.14	0.1	0.10	0.35	0.18	Nil.
3.48	2.12	2.37	6.48	1.68	0.48
5.32	4.07	14.21	9.08	3.70	2.62
0.198	0.145	0.445	0.276	0.133	0.033
0.44	0.59	0.56	1.13	0.200	0.025
0.032	0.044	0.044	0.026	0.013	0.010
0.161	0.258	0.149	0.119	0.111	0.081
0.083	0.080	0.010	0.008	0.049	0.004
0.57	0.30	0.80	...	0.36	0.05
0.41	0.20	0.64	2.02	0.20	0.06
0.14	0.09	0.10	0.35	0.18	Nil.
2.53	3.98	3.62	6.16	1.51	2.24
0.09	0.03	0.08	0.15	...	Trace.

With them may be compared No. 9, a much lighter type, a barley rather than a wheat soil, but with a good reputation for fruit. It may be regarded as approaching the limit, as regards lightness, for a really fine soil.

No. 7 is a heavy pasture of great fertility; it will grow fine wheat crops, but the absence of coarse sand and the large proportion of silt and clay renders it liable to glaze and cake on the surface.

No. 8 is an excessively heavy London clay soil, with the highest proportion of clay of any British soil within the writer's experience. Very rarely do soils so heavy as this remain in arable cultivation.

No. 10 represents a soil at the other extreme, a barren heath clothed only with heather and bracken. Two-thirds of the soil consists of coarse sand, and the clay is entirely absent. Again, the soil is almost devoid of soluble material.



APPENDIX II

BIBLIOGRAPHY

THE following short list of references will take the student to some of the more important original sources of information on each of the subjects treated of in this book. They have been selected from among the great mass of papers that exist, not because they are necessarily the most important, but as suggestive in themselves, and likely to lead the student to make further acquaintance with the methods as well as with the results of research. Several of the papers also contain a series of references to other workers in the same field.

THE ORIGIN OF SOILS.

- RISLER, E.—*Géologie Agricole*, 4 vols., Paris, 1884-97.
MERRILL, G. P.—*Rocks, Rock Weathering, and Soils*, New York, 1897.

GENERAL.

- HILGARD.—*Soils*, New York, 1906.
HILGARD.—*Soils in the Humid and Arid Regions*, 1914.
RAMMAN.—*Bodenkunde*, Berlin, 1911.
LYON, FIPPIN, AND BUCHANAN.—*Soils*, New York, 1915.
RUSSELL.—*Soil Conditions and Plant Growth*, London, 1917.

ANALYSIS AND COMPOSITION OF SOILS.

- LAUNFER AND WAHNSCHAFTE.—*Mit. a. d. Laboratorium für Bodenkunde*, B. III., h. 2, Berlin.
PETERMANN.—*Recherches de Chimie le*, III., Brussels, 1898.
HILGARD, U.S. Dep. of Agric., Div. of Chem., Bull. 38, 1893.
HILGARD, U.S. Dep. of Agric., Div. of Soils, Bull. 4, 1896.
MITSCHERLICH, E. A.—*Bodenkunde für Land u. Forstwirte*, 1905.
LAWES AND GILBERT.—*Rothamsted Memoirs*, V., No. 19.
DYER.—*J. Chem. Soc.*, 1894, 65, 115.
DYER.—*Phil. Trans.*, 194, B. (1901), 235.
DYER.—U.S. Dep. of Agric., Bull. 106, 1902.
HALL AND RUSSELL.—"Soil Surveys and Soil Analyses," *J. Agric. Sci.*, 1911, 4, 182.

SOIL PHYSICS.

- WARINGTON.—*Physical Properties of Soils*, Oxford, 1900.
 KING.—*Physics of Agriculture*, Madison, Wis., 1901.
 HELLRIEGEL.—*B. s. d. nat. Grundlagen des Ackerbaues*,
 Braunschweig, 1883.
 MOSIER AND GUSTAFSON.—*Soil Physics*, Philadelphia, 1917.
 LAWES AND GILBERT.—*Rothamsted Memoirs*, Vol. III., No.
 11; Vol. V., No. 5.
 BRIGGS.—U.S. Bureau of Soils, Bull. 45, 1907.
 KEEN.—"Soil and Water Content," *J. Agric. Sci.*, 1920, 10, 44.
 LIVINGSTONE AND HAWKINS.—*Water Relation between Plant and
 Soil*, 1915.

THE SOIL SOLUTION.

- WHITNEY AND CAMERON.—Chemistry of the Soil as related to
 Crop Production, U.S. Bureau of Soils, Bull. 22, 1903.
 CAMERON.—*The Soil Solution*, Easton.
 HALL, BRENCHLEY, AND UNDERWOOD.—*Phil. Trans.*, B. 1913,
 204, 179.
 BOUYONCOS.—*Michigan Tech. Bull.*, 24, 31, 36, 37, 42 (1915-18).
 HALL AND MILLER.—"Retention of Bases by the Soil," *Proc.
 Roy. Soc.*, B. 1905, 77, 1.

SOIL ORGANISMS.

- WOLLNY.—*Zersetzung der Organischen Stoffe*, Heidelberg, 1897.
 OMELIANSKY.—*Compt. Rend.*, 121 (1895), 653; 125 (1897), 970.
 WINOGRADSKY.—*Compt. Rend.*, 121 (1895), 742.
 LAFAR.—*Technische Mycologie*, 2nd ed., Fischer, Jena, 1904.
 HUTCHINSON AND CLAYTON.—*J. Agric. Sci.*, 1919, 9, 143.

FIXATION OF NITROGEN.

- LAWES AND GILBERT.—*Phil. Trans.*, II., 431, 1861; B. I., 1889.
 LAWES AND GILBERT.—*J. R. Ag. Soc., E.*, 3rd s., II., 657, 1891.
 HELLRIEGEL AND WILFARTH.—*D. Land. Vers. Stat.*, 460, 1887.
 NOBBE AND HILTNER.—*D. Land. Vers. Stat.*, 1899.
 WINOGRADSKY.—*Compt. Rend.*, 118 (1894).
 MAZÉ.—*Ann. de l'Inst. Pasteur*, 11 (1897).
 JACOBITZ.—*Cent. für Bakt.*, II., 1901, 7, 783.
 BEIJERINCK.—*Cent. für Bakt.*, II., 1902, 9, 3.

NITRIFICATION.

- SCHLOESING AND MÜNTZ.—*Compt. Rend.*, 80 (1877), 1250.
 WARINGTON.—*J. C. S.*, 1878, 1879, 1884, 1891.

LAWES, GILBERT, AND WARINGTON.—*J. R. Ag. Soc., E.*, 2nd s., 19 (1883).

WINOGRADSKY.—*Compt. Rend.*, 113 (1893), 116.

DEHÉRAIN.—*Ann. Agron.*, 19, 409.

KING.—Wisconsin Ag. Exp. Station Annual Reports, 17 (1900), 18 (1901).

RUSSELL.—*J. Agric. Sci.*, 1914, 6, 18.

DENITRIFICATION.

GAYON AND DUPETIT.—*Compt. Rend.*, 95 (1882), 644.

WAGNER.—*D. Landw. Presse*, 1895, 123.

WARINGTON.—*J. R. Ag. Soc., E.*, 3rd s., 8.

STOKLASA.—*Cent. f. Bakt.*, 7 (1901), 260.

MYCORHIZA.

STAHL.—*Jahrb. f. wiss. Botanik.*, 34.

PROTOZOA.

RUSSELL AND HUTCHINSON.—*J. Agric. Sci.*, 1909, 3, 111; 1913, 5, 152.

ABSORPTION OF SALTS BY SOIL.

WAY.—*J. R. Ag. Soc., E.*, 1st s., 11, 323; 13, 123.

VOELCKER.—*J. R. Ag. Soc., E.*, 1st s., 21 (1860), 93; 25 (1864) 333.

VOELCKER.—*J. R. Ag. Soc., E.*, 2nd s., 10 (1874), 132.

LAWES, GILBERT, AND WARINGTON.—*J. R. Ag. Soc., E.*, 2nd s., XVII. (1881), 241; XVIII. (1882), 1.

BEMELLEN.—"Absorption von wasser durch Thon," *Zeit. anorg. Ch.*, 1904, 12, 314.

RUSSELL.—British Association Second Report on "Colloid Chemistry," 1919.

ALKALI SOILS.

HILGARD.—U.S. Dep. of Agric. Year-Book, 1895, 103.

HILGARD.—Univ. of California Ag. Exp. Sta., Bull. 128 (1900).

WILLCOCKS.—*Egyptian Irrigation*, 2nd ed.

SOIL SURVEYS, ETC.

SCHIMPER, A. F. W.—*Pflanzen Geographie*, Jena, 1898.

U.S. Dep. of Agric., Div. of Soils, "Field Operations," 1901.

WHITNEY.—"Tobacco Soils," U.S. Dep. of Agric., Bull. 11, 1898.

VEITCH.—"Maryland Soils," Maryland Ag. Exp. Sta., Bull. 70, 1901.

HALL AND RUSSELL.—"Agriculture and Soils of Kent, Surrey, and Sussex," *Board of Agric. and Fisheries*, 1911.



INDEX

- ABSORPTION of salts by soil, 247
 Acid soils, 32, 50, 171, 197, 240, 281
 Aerobic bacteria, 195
 Alinit, 198
 Alkali soils, 284
 Alluvial soils, 323
 Alluvium, 12
 Altitude, effect on temperature, 153
 Always, soil-water required for crops, 96, 112
 Ammonia, absorption by soil, 250; formation from urea, 196; in soil, 221; salts, removal of lime by, 252, 259
 Anaerobic bacteria, 199
 Analysis, available constituents, 177; chemical, 159; interpretation of, 171, 183; mechanical, 35, 55; of soil by plant, 176
 Anbury in turnips, 240, 244
 Angus Smith on denitrification, 226
 Anti-cyclones, reversal of temperature in, 153
 Antiseptics, effect of on soil, 233
 Apatite, 24
 Arid soils, characteristics of, 31, 51
 Assimilation and transpiration, 101
 Atwater on fixation of nitrogen, 204
 Augite, 21
 Autumn cultivation, gain of water by, 106
 Available plant food in the soil, 177, 181
 Azotobacter chroococcum, 213
 BACTERIA in soil, 4, 192, 233; denitrifying, 226; nitrifying, 218; iron, 239; nitrogen fixing, 199
 Bailey-Denton on effect of drainage on temperature, 151
 Bare fallows, 96, 125, 130, 225, 328
 Basalt, weathering of, 22
 Beaumont, E. de, on antiquity of soil, 33
 Beijerinck on Azotobacter, 213
 Benetzungs-warme, 98
 Berthelot on fixation of nitrogen, 204, 212; and André on nitrogen in humus, 52
 Black soils, 32, 52, 273
 Bog iron ore, 26
 Boulder clays, 16
 Boussingault on source of nitrogen in plants, 200, 202
 Brick earth, 13, 15
 Brown on energy absorbed in assimilation, 101
 Brownian motion, 43
 CALCAREOUS soils, 325
 Calcifuges, 320, 332
 Calcium carbonate, 23, 46, 170; aids decay of organic matter, 198; determination of, 164; in soils subject to "finger-and-toe," 245; removal by manures, 252
 Capacity of soil for water, 73, 87
 Capillarity, 77; supply of water to crop by, 111, 118
 Carbohydrate and nitrogen fixation, 214
 Carbon, determination of, 163
 Carbon to nitrogen in soils, ratio of, 51
 Carbonic acid in soil gases, 13; excreted by roots, 179; and water, action on rock minerals, 13
 Catch crops, 122
 Chalk, 46; "pipes" in, due to weathering, 24; soils, 325
 Chalking, 304

- Chemical analysis of soil, 159
 China clay, 20, 39
 Chlorosis, 327
 Citric acid as solvent in soil analysis, 181
 Clay, colloid, 39; flocculation of, 42; impermeability to water, 38, 76; nature of, 44, 57; origin of, 20; shrinkage on drying, 38, 328; soils, 65, 327
 Clayey, 296
 Cleopatra's Needle, weathering of, 11
 Climate and situation, 158
 Clostridium Pastorianum, 212
 Club root in turnips, 240, 244
 Cohesion due to surface tension, 91
 Colloids, 39, 50, 249
 Colmetage, 295
 Colour of soils, 28; and temperature, 144
 Condensation of water by soil, 98
 Condition of land, 271
 Conventions necessary in chemical analysis of soil, 161
 Crops, plant food removed by, 172
 Crops, water required by, 101, 121
 Crowstone, 25, 329
 Cultivation, effect of, on water content of soil, 106, 114, 118

 DARWIN on action of earthworms, 14
 Daubrée on size of sand grains not rounded by running water, 18; weathering of felspar, 20
 Deflocculation, 45, 283, 292
 Defoe, definition of manure, 174
 Dehérain on available phosphoric acid in soils, 180; nitrates in drainage waters, 265; nitrification, 223
 Dehérain and Maquenne on denitrification, 226
 Denitrification, 226
 Density of soils, 69
 Drainage, 103; required with irrigation, 288; warms the land, 149; waters, composition of, 258
 Drains, flow of, 84
 Drain-gauges, 85, 111; flow greater than rainfall, 91
 Drift, glacial, 16; maps, 341; soils, 8

 Drought of 1870 at Rothamsted, 121
 Drought, susceptibility of different soils to, 113
 Dry farming, 129
 Drying effect of crops, 121, 130
 Dunbar, potato soils of, 1
 Dung, effects on water in soil, 131; and denitrification, 228
 Dyer on determination of available phosphoric acid and potash, 181; potash and phosphoric acid retained by Rothamsted soils, 254

 EARLY and late soils, 154
 Ebelmar on weathering of basalt, 21
 Egypt, irrigation in, 287
 Eremacausis, 195
 Evaporation, cooling effect of, 147; losses of water by, 109
 Exhausting effect, of nitrate of soda, 292; of wheat, 275

 FAIRY rings, 278
 Fallows, bare, 96, 125, 130, 225, 328
 Felspar, 19
 Fen land, potatoes from the black soils of, 2; reclamation of, 298
 Fertility, 271
 Film of water surrounding soil particles, 78
 "Finger-and-toe," 240, 244, 281
 Fixation of nitrogen, 199
 Flint, 18
 Flocculation of clay, 42, 45, 283
 Flow of water through soils, 75
 Frank on mycorrhiza, 241
 Frosts in valleys, 152; killing effect of, 141
 Fruit trees in grass land, 123
 Fuller's earth, 41
 Fungi in the soil, 192, 239, 278

 GAYON and Dupetit on denitrification, 227
 Germination, temperatures of, 142
 Glacial drift, 16
 Glauconite, 27
 Granite, weathering of, 19
 Gravel, 15
 Green manuring, 210
 Greenhouse soils, 237
 Greenstone, weathering of, 22

- Grey wethers, 18
Gypsum, 25
- HALOPHYTES**, 324
Hanemann on weathering of basalt, 22
Heat received by the soil, 135, 143; required for evaporation, 147
Heaths, reclamation of, 298
Heating soils, effect of, 233
Heavy soils, 65
Heinrich on hygroscopic moisture, 95
Hellriegel on fixation of nitrogen, 201, 205; on optimum proportion of water for growth, 75; on water transpired by crops, 100
Hilgard on alkali soils, 285; on distillation of water from subsoil, 98; on mechanical analysis of soils, 56; on method for determination of water capacity, 73
Hilgard and Jaffa on nitrogen in humus, 51
Hiltner, cultivation of nodule organisms, 208
Hoeing, 115
Hornblende, 21
Humic acid, 49
Humus, 28, 47, 131, 187, 194, 198, 243, 298
Humus, soluble, 49, 187
Hygroscopic moisture, 93
Hutchinson, lime in soil, 164, 171; protozoa, 232
- IGNITION**, loss on, 163
Inoculation of soil, 208
Interpretation of soil analysis, 59, 171, 188
Irrigation, 285
Iron bacteria, 239
Iron pan in soils, 25, 319, 329
Iron pyrites, 27; causing sterility, 381
- KAOLINITE**, 19, 38, 40
King on area of surface of soil particles, 72; on bare fallows, 126; on effect of cultivation on water content of soil, 109, 114, 119; on effect of slope on temperature of soil, 151; on flow of water through sand, 76; on nitrates in soil, 222; on percolation, 82; on transpiration water, 100; on water in soils too dry for growth, 95
Kossowitsch on fixation of nitrogen, 212
Krüger and Schneidewind, 212, 228
- LANGLEY** on solar radiation, 143
Late soils, 154
Laterite, 31
Laurent on fixation of nitrogen, 206
Lawes and Gilbert on fixation of nitrogen, 201; on ratio of carbon to nitrogen in soils, 51; on transpiration water, 100 (*see also* Rothamsted)
Leguminous plants, fixation of nitrogen by, 205; green manuring with, 210
Liebig, mineral theory, 200
Light soils, 65, 70
Lime, effect on temperature of soil, 146; composition of, 313; flocculation of clay by, 45; for "finger-and-toe," 244; in drainage waters, 259; removal from soil by use of ammonium salts, 252, 259; amount required by soil, 171
Liming, 45, 245, 304
Limonite, 25
Loams, 35, 322
Loess deposits, 10, 31
Lois-Weedon husbandry, 127, 225
Lucerne requiring inoculation, 209
Lysimeter, 85
- MAGNESIA** in drainage waters, 261; in soils, 167, 282, 329
Manures, absorption of, by soil, 247; effect on texture of soil, 292; original significance of, 174; recovery of, in crop, 185, 230; time of application of, 266
Marcasite, 27
Marling, 296
Marls, 35, 297
Mechanical analysis of soil, 35, 55
Mica, 21
Mineral theory, Liebig's, 200

- Minerals, composition of rock-forming, 17
Mitscherlich on benetzungs-warme, 98
Molecular forces, 77
Molisch on iron bacteria, 239
Moor-baud pan, 25
Moore, cultivation of nodule organisms, 208
Mould, 196
Mulches, 108, 115, 284
Müller on nitrification, 218
Mycorrhiza, 240, 321
- NATROLITE, 27
Nile water, 287
Nitragin, 208
Nitrates, determination of, 168; formation of, 116, 218; in drainage waters, 262; in soil, effect of cultivation on, 223; produced by bare fallow, 125, 225
Nitrification, 218
Nitrogen, determination of, 164; fixation of, 199; proportion recovered in crop, 228, 230
Nobbe on nitragin, 207
Nodules on leguminous plants, 205
- OEMLER on specific heat of soil, 147
Olivine, 23
Optimum proportion of water in soils, for growth, 75, 89; temperatures for growth, 140
Orchids, germination of, 244
Osborne on mechanical analysis of soils, 56
Osmosis, entry of plant food by, 178
- PACKING of soil particles, 66
Pan, iron, in soils, 25, 319, 329
Paring and burfing, 302
Parkes on temperatures of drained and undrained land, 149
Peat, origin of, 48, 197, 199; reclamation of, 298; soils, 332
Percolation, 81, 128; through gauges at Rothamsted, 85
Phosphoric acid, determination of, 166, 184; retention by soil, 256
Pipe clays, 39
Pipes in chalk rock, 24
Plasmodiophora brassicæ, 240, 244
Plasticity of clay, 38
Ploughing, damage done by deep, 30, 329
Pore space, 68
Potash, determination of, 166, 170; origin in soils, 20, 29; retention by soil, 253
Potatoes grown on different soils, value of, 1
Protein in wheat, 158
Protozoa in soil, 194, 232, 303
Pseudomonas radiculicola, 205, 207
- QUALITY of produce from early and late soils, 157
Quarry water, 11
Quartz, 17
Quincke on range of molecular forces, 77
- Radiation, 143
Rainfall and crops, 102
Rainfall and drainage, 85, 128
Recovery of manures in crop, 185, 230
Red lands of Dunbar, value of potatoes from, 1, 62
Richthoven on loess deposits, 10
Rock-forming minerals, 17
Rolling, effect of, 118
Roots, solvent action of, 179; weathering action of, 14
Rothamsted, available constituents in soil of, 173; bare fallows at, 126; composition of drainage waters at, 259; composition of soil, 41, 63; drain-gauges at, 85; drought of 1870 at, 121; investigations on fixation of nitrogen at, 201, 216; lime in soil of, 252; losses of nitrogen in manure at, 230; method of sampling soils at, 53; nitrates in soil at, 215; phosphoric acid in soil of, 184, 258; potash in soil of, 254; weights of soil at, 71
Russell, protozoa in soil, 232
Rutile, 37
- SACHS on solvent action of roots, 179; on temperature and trans-

- spiration, 141; on water in soil, when plants wilt, 94
 Salfeld on soil inoculation, 211
 Salt, causing sterility, 282; marshes, vegetation of, 324
 Salts, soluble in soils, 167
 Sampling of soils, 53
 Sand, origin of, 17, 37; velocity of current required to carry, 37
 Sandy soils, 34, 296, 318
 Saturation of soils by water, 73
 Saussure on theory of nutrition, 199
 Schloesing on colloid clay, 39; on mechanical analysis of soils, 56
 Schloesing and Muntz on nitrification, 218
 Schloesing's *filis* on fixation of nitrogen, 206
 Schneidewind on denitrification, 228; on fixation of nitrogen, 212
 Schultz on green manuring, 210
 Sea, effect on climate, 156
 Sedentary soils, 7
 Selenite, 25, 329
 Senft on decomposition of felspar, 20.
 Serpentine, 23
 Sewage farms, crops on, 103; purification of, by soil, 228, 249
 Shingle, growth of vegetation on, 10
 Shrinkage of clay on drying, 38, 328
 Sibirtzeff, 31
 Silica, 17
 Silt, 58
 Soil, alkali, 284, 316; analyses of typical, Appendix I.; description of, 7, 30; drift, 8; gases, 13; inoculation, 208; mulch, 115; of transport, 8; relation to subsoil, 7, 28, 221; sedentary, 7; solution, 179; surveys, 333; temperatures, 136; typical, 60, 169, 337; worn-out, 29, 298
 Soot, effect on temperature of soil, 145; effect on texture of soil, 293
 Specific heat of soils, 146, 319
 Spring on impermeability of clay, 77
 Spring cultivation, gain of water by, 108; frosts, 152
 Stahl on mycorrhiza, 241
 Steppe soils, 31
 Sterility of soils, 280
 Stoklasa on alinit, 198
 Stones, reputed growth on arable land, 12; retention of moisture by, 117; warming effect of, 149
 Subsoil, description of, 7, 28, 221; as regulator of water supply, 110; packing, 120
 Surface of soil particles, area of, 71, 98; rise of salts to the, 284
 Surface tension, 77; cohesion due to, 91; variations in, 90; water lifted by, 111, 118
 Surveys, soil, 333
 Symbiosis, 193, 241
 TALC, 23
 Tchernozem, 32
 Temperature, effect of colour on, 144; effect of exposure on, 148, 151; required for growth, 138, 140; weathering due to alternations of, 9
 Texture of soil, 36, 66, 275, 291
 Thanet sand, soils on, 274
 Tillage and soil water, 103
 Tilth, 108, 291
 Transpiration water, 101
 Tundra soils, 33
 Typical soils, chemical analysis of, 169; mechanical analysis of, 61
 UREA, conversion into ammonia, 196
 VALLEY frosts, 152
 Velocity of currents carrying sand grains, 37
 Ville on fixation of nitrogen, 204
 Vineyards, stones on surface of, 149
 Virgin soils, nitrogen in, 216
 Voelcker on absorption of manures by soil, 248; on analysis of drainage waters, 259; on fixation of nitrogen, 204; on "finger-and-toe" in turnips, 244
 WAGNER on denitrification, 228
 Warrington on determinations of nitrates in soils, 168; on denitrification, 227; on nitrification, 218; on wetness of land in February, 98

- Warp soils, 295 ; growth of potatoes on, 2
 Water capacity of soil, 73
 Water table, 84
 Way on absorption of salts by soil, 247
 Weathering, 7, 9 ; due to alterations of temperature, 10 ; due to frost, 11 ; due to water and carbonic acid, 13 ; due to roots, 14 ; of granite, 19 ; of basalt, 22
 Weight of a cubic foot of soil, 70
 Wheat as an exhausting crop, 275
 Wilfarth on fixation of nitrogen, 205
 Wilting of plants in soils containing water, 94
 Wind, transport of soil by, 10
 Winogradsky on iron bacteria, 239 ; on nitrification, 219 ; on nitrogen-fixing bacteria, 212
 Woburn, lime in soil at, 240 ; residues left by ammonium salts at, 269 ; weight of cubic foot of soil at, 64, 71 ; fruit farm, growth of trees planted with grass, 123
 Wollny on composition of soil gases, 13 ; on effect of slope on temperature, 151 ; on oxidation of humic acid, 198 ; on water required by crops, 100
 Worms, fine soil brought to surface by, 14
 Worn-out soils, 29, 298
 XEROPHYTES, 316, 321, 332
 YEASTS in the soil, 239
 ZEOLITES, 27, 44, 250
 Zircon, 37

